Wett & Windy LTD
Builders

Company no 6410643 vat no 928989935
31 Westacre , Penistone , Sheffield , S36 6bf
Tel ; 01226 765846 or 07968 308360

34 High Street
Penistone
Sheffield
S36 6bs .

The Boundary wall to the right hand side of the property is leaning significantly out towards the public footpath .
The owners of the property have said that this has visibly worsened over the last 6 months . The wall probably erected at the same time as the house and may not have significant foundations .
I cannot see any course for the damage to the wall other than the close proximity of the two trees which are less than 50cm from the wall .

To achieve a permanent solution the wall needs to be taken down and a concrete foundation laid and the wall rebuilt .
As the difference in ground level between the inside of the wall and the footpath is up to 1 metre this will involve significant digging out and any roots will need to be removed .
This could impact the stability of the two trees .