



- R1 Re-site existing column
- 'xx'A New column location  
10m Galvanised steel column  
with Philips City Soul Gen2  
20Klm Led lantern complete with  
electronic PEC
- EX'x' Replace existing column with  
10m Galvanised steel column  
with Philips City Soul Gen2  
20Klm Led lantern complete with  
electronic PEC
- 125mm Ø ducting to NPG  
requirements with 600mm cover.  
Sand surround and NPG duct  
tape cover.

All material to comply fully with current BMBC Street lighting specification.

All lighting columns are to be provided with an inmetered single phase electrical supply via the REC cable network.  
It is expected that the contractor will coordinate with the REC regarding the installation of any cable ducts they may require.

This map is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office © Crown copyright. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings. 100022264 (2009).

Rev.	By	Amendments	Date
A	NL	Kerbline amended	11/20
B	NL	Kerb Alignment taxi bay	Apr 21



Project  
**Market Gate Bridge Project**

Drawing title  
**Highways Work - Midland Street Street Lighting**

Scale	Drawn	Checked	Date
1:500	NL		Apr 2020
Drawing No.	File		
BGW2_BMB_PB_xx_PN_C_G100_0502			

Paul Castle Service Director, Place Directorate  
Environment & Transportation (Business Unit 6)  
P.O. Box 601, Westgate Plaza One, Westgate  
Barnsley S70 9FA  
Tel. (01226) 770770 Fax. (01226) 772222