



**i** 900mm External Single Sided Roundel

- SPECIFICATION
- ① Black plastic trim, fixed to aluminium carcass using small pan head screws with heads painted Black
  - ② 2mm thick Aluminium carcass finished White inside and Satin Black RAL 9005 externally.
  - ③ Tridonic P560 Crystal White LED, 38 off modules required.  
1 Off Tridonic Talex LCU 060/12 D010  
120/240V converter required.
  - ④ 3mm thick 050 Opal perspex face with face applied translucent vinyl 3M scotchall vinyl Holly Green 3630-76

