



- The symbols used on this drawing to show Street Lighting Column Positions have been enlarged for clarity and are not to scale.
- All setting out and exact positions to be agreed on site by Barnsley Council Street Lighting Section prior to start. Allow at least 2 clear working days to attend site.
- Street Lighting Columns shall only be planted in the ground (1.0m deep) once Kerbs and Edgings (Pin Kerb) have been installed establishing both line and level (or walls to rear of footways have been built) and the ground construction is up to (and including) sub-base level.
- All disconnections and connections of new Street Lighting Columns to be co-ordinated by the principal contractor

Street Lighting Arrangement

N 'x' Proposed new 6M galvanised steel column with
AriaLed 40 lantern complete with electronic PEC and 14
metres cable
(N denotes new column 'x' denotes number)

(N denotes new column 'x' denotes number)



 D 'x' Disconnect and remove to Council tip 6 metre column and lantern

Rev	By	Revision Details	Date
 BARNLSLEY Metropolitan Borough Council			
Project Gypsy Lane S38 Works			
Title Street Lighting Proposals			
Scale	Drawn	Checked	Date
1:100	SGA		20/3/2023
A1 Drawing No. SL20-94_1300_1			Rev