



**KEY**

- Meadow Mixture for Clay Soils Emmorsgate EG4
- Tarmac Paving
- Block Paving

**General Planting Notes**

1. Tree protection shall be in place prior to works commencing, refer to the submitted Existing Vegetation Removal and Protection Plan. Any existing trees to be retained are the responsibility of the main contractor on site who shall take all necessary protective measures set out in BS 5837:2012.
2. All groundworks and planting operations shall be in accordance with the following British Standards and guidelines unless otherwise indicated:
  - BS 4428:1989 Code of Practice for General Landscape Operations
  - Defra Construction Code of Practice for the Sustainable Use of Soils on Construction Sites.
3. On site soils may be used for planting subject to quality and quantity of soil resources available. Where topsoil is to be imported this should meet the criteria set out in BS3882:2015 with a clay content of no more than 30% (multipurpose). For imported subsoil the criteria set out in BS8601:2013 should be met with a clay content of no more than 30% (multipurpose). All areas of proposed planting/seeding affected by construction works to be relieved of compaction by ripping to a depth of 600mm, in two directions.
4. Effective weed control must be carried out prior to cultivation. All planting areas to be cultivated to a depth of 300mm, all proposed seeded areas to be cultivated to a depth of 150mm, except within 4.0m of any existing tree stem, unless otherwise stated in the specification.
5. Topsoil depths to be: 150mm seeded areas. Good quality on site topsoil can be used for grass areas. Pits will be dug by the landscape contractor and should be freely draining. For areas to be seeded, the soil level shall be flush with any finished paved surfaces after settlement.
6. Organic compost (PAS 100) surface mulching to be supplied to all ornamental shrub planting, individual trees in grass and hedges to a depth of 75mm.
7. Where there is possibility of damage by browsing animals, plants are to be protected with appropriate tree and shrub shelters and/or rabbit proof fencing.

C	Change of Meadow Mix	26.07.23	AB	LG	LG
B	Updated following client's comments	08.02.23	YX	LG	LG
A	Updated following client's comments	07.03.23	YX	LG	LG
REVISION		DATE	ISSUED	BY	APPD

CLIENT  
**STRATA STERLING BARNSELY WEST LTD**

PROJECT  
**BARNSELY WEST HIGHWAYS**

DRAWING TITLE  
**NORTH ROUNDABOUT PLANTING PLAN**

DRG No.	LD10593-001	REV	C	SUIT. CODE
DRG SIZE	A1	SCALE	1:500	DATE
				24.03.23
DRAWN BY	YX	CHECKED BY	LG	APPROVED BY
				LG

