

Facility Issue	Activity/Mitigation	Additional Comments
<p>Development of the site</p>	<p>Works are to comply with the Control of Noise at Work Regulations (2005)</p>	<p>Contractor to submit Construction Phase Plan to confirm management of noise arising from works.</p>
<p>Hours of operation:</p> <p><u>Building</u> Monday-Sunday – 9am -11pm*</p> <p><u>Pitch & Archery Range</u> Monday-Friday – 9am -10pm Saturday & Sunday – 9am – 6pm</p> <p>*Normal hours for the building will be 9am – 10pm, however, if there is a function, the opening may extend to 11pm. This reflects the current operation at the Rockingham site.</p>	<p>Internal activities will range from fitness classes to community meetings as well as use of the changing facilities by both internal and external facility users.</p> <p>The pitch will be used for football.</p> <p>The archery range is unlit and will therefore only be used during daylight hours.</p> <p>Closure of the site by staff will ensure that all participants or spectators are off site by 10:30pm except for functions where site will be vacated by 11:30pm.</p>	<p>Football Foundation (who are funding the pitch) require the operators to commit to maximising the revenue of the pitch to comply with their funding application criteria. The operators of the proposed Parkside facility only intend to operate the external pitches up to 9pm, however, we need to have the option to operate until 10pm if demand is there. The hours of operation for the building will mirror that of the pitch, as required for changing provision.</p>
<p>Special Functions</p> <p>(Determined to be one off social bookings for the indoor pavilion space)</p>	<p>Windows and door closed except in extenuating circumstances i.e., extreme warm weather.</p> <p>Ventilation plan mean windows should not require opening which will mitigate use of music.</p> <p>Event organisers to be made aware of, and agree, to the specific space and conditions of use.</p>	<p>Extended opening for special circumstances for functions. Non regular activity.</p> <p>All traffic left by 11:30pm</p>

<p>Social/Activity Area within the Pavilion.</p>	<p>Appropriate operating times for activities and the movement of users off site.</p> <p>Activities and their noise during operating times will be contained within the indoor footprint of the pavilion.</p> <p>Activities will be limited to indoor low level multi sports activities including fitness sessions and social activity groups.</p> <p>Windows and door closed except in extenuating circumstances i.e., extreme warm weather.</p> <p>Ventilation plan mean windows should not require opening which will mitigate use of music.</p>	
--	---	--

<p>Immediately Outside Pavilion</p>	<p>Event organisers to be made aware of the specific space and conditions of use.</p> <p>Dedicated smoking area that locates potential smokers away from residential areas.</p> <p>Relevant signage to be installed guiding users to be considerate of surrounding residents.</p> <p>Terms and conditions of bookings will specifically ask event organisers to agree to.</p>	
<p>Car Park Noise</p>	<p>Carpark entrance & exit via old Sheffield Road entrance, Slow speed notices to be displayed for site Health & Safety along with noise reduction.</p>	<p>Aim for Carpark to be empty within 30 mins of the centre closing on any given night and for special functions.</p>

<p>Playing area – Football Noise</p>	<p>Pitch is orientated lower than surrounding levels to reduce noise pollution.</p> <p>Fencing/rebound noise – dividing curtains have no sound issues. The surrounding fence is set back from the playing area to mitigate potential noise.</p> <p>Booking terms and conditions will have reference to noise especially the use of bad language and the relevant consequence.</p> <p>Relevant noise mitigations will be confirmed and put in place to ensure that the noise levels comply with World Health Organisation and Sport England Guidance on the recommended 50db limit.</p> <p>A 4m. high acoustic fence is proposed along the north side of the pitch to protect the residential properties on Parkside Road.</p>	<p>Spectator areas to the lower side of the site furthest from neighbouring properties</p>
<p>Playing area – Archery noise</p>	<p>Range is at least 100meters away from any neighbouring property and a quiet participant sport.</p> <p>Archery activities would have limited noise output.</p>	
<p>Maintenance Garage Noise</p>	<p>Sited away from neighbouring residences on a lower plateau with close board screening for visual & acoustic benefit.</p>	<p>No work from the Garage area after 8:00pm</p>

	Where reasonably practicable, ensuring the use of quiet working methods.	
--	--	--