



Proposed Site Plan
1:250

Soft Landscape Areas			
Plan view	Description	Comments	
	AG	Proposed amenity grass. Outside planning boundary	
	Mix01	Proposed native shrub mix. Ref. to Planting table	
	Mix02	Proposed ornamental shrub mix. Ref. to Planting table	
	Mix03	Slope stabilising shrub mix. Ref. to Planting table	
	Mix04	Proposed biodiversity-rich planting mix. Ref. to Planting table	
	Mix05	Proposed herbaceous SUDs-friendly planting. Ref. to Planting table	
	WFM	Proposed wildflower mix. Ref. to Planting table	

Planting table									
H01	Proposed Hedgerow	Size Height, cm	Ctr m	No. / sq.m	Root Pot Size	Notes	Mix %	Area sq.m	Total Quantity
	Loncera plicata	60-90	0.45	5	2L	Full pot- min 5 breaks	100%	33	165
TOTALS							100%	33	165
Mix 01	Proposed native shrub mix	Size Height, cm	Ctr m	No. / sq.m	Root Pot Size	Notes	Mix %	Area sq.m	Total Quantity
	Rosa canina	40-60	0.6	3	bare-root	2 years transplants	40%	272	816
	Ilex aquifolium	60-90	0.6	3	bare-root	2 years transplants	20%	136	408
	Ligustrum vulgare	40-60	0.6	3	bare-root	2 years transplants	15%	102	306
	Viburnum opulus	60-90	1.4	0.5	bare-root	2 years transplants	15%	102	51
	Ulex europaeus	40-60	0.6	3	bare-root	2 years transplants	10%	68	204
TOTALS							100%	680	1785
Mix02	Proposed ornamental mix	Size Height, cm	Ctr m	No. / sq.m	Root Pot Size	Notes	Mix %	Area sq.m	Total Quantity
	Potentilla fruticosa 'Sunset'	20-30	0.7	2	2L	Full pot- min 5 breaks	20%	163	326
	Spiraea betulifolia	20-30	0.7	2	2L	Full pot- min 5 breaks	15%	122	244
	Bergenia 'Abendglur'	20-30	0.5	4	1L	Full pot	15%	122	488
	Blechnum spicant	20-30	0.7	2	2L	Full pot- min 5 breaks	10%	81	163
	Geranium macrorrhizum 'Bevan's Variety'	15-30	0.5	4	1L	2 years transplants	10%	81	326
	Sarcococca confusa	60-80	0.6	3	2L	Full pot- min 5 breaks	5%	41	122
	Heuchera 'Lime Marmalade'	20-30	0.5	4	1L	Full pot	5%	41	163
	Urtica muscari	20-30	0.5	4	1L	2 years transplants	5%	41	163
	Polystichum aculeatum	40-60	0.5	4	1L	3 years transplants	5%	41	163
	Skimmia japonica 'Nyman's'	60-80	0.7	2	2L	2 years transplants	5%	41	81
	Vinca major	60-90	0.4	6	pot 9x9 cm	Full pot	5%	41	244
TOTALS							100%	814	2485
Mix03	Proposed slope stabilising mix	Size Height, cm	Ctr m	No. / sq.m	Root Pot Size	Notes	Mix %	Area sq.m	Total Quantity
	Potentilla fruticosa 'Sunset'	40-60	0.7	2	2L	Full pot- min 5 breaks	25%	69	137
	Cornus sanguinea 'Army's Winter Orange'	40-60	0.6	3	2L	2 years transplants	20%	55	165
	Skimmia japonica 'Nyman's'	40-60	0.5	4	1L	2 years transplants	15%	41	165
	Vinca major	20-30	0.5	4	9 cm pot	1 year transplants	15%	41	165
	Bergenia 'Abendglur'	20-30	0.5	4	1L	2 years transplants	10%	27	110
	Cytisus scoparius	40-60	0.5	4	1L	2 years transplants	10%	27	110
	Hedera helix	20-30	0.5	4	9 cm pot	1 year transplants	5%	14	55
TOTALS							100%	275	907
Mix04	Proposed biodiversity-rich mix	Size Height, cm	Ctr m	No. / sq.m	Root Pot Size	Notes	Mix %	Area sq.m	Total Quantity
	Rosa canina	40-60	1	1	bare-root	2 years transplants	20%	153	153
	Cornus sanguinea	40-60	1	1	bare-root	2 years transplants	20%	153	153
	Ulex europaeus	40-60	0.71	2	bare-root	2 years transplants	20%	153	306
	Crataegus monogyna	40-60	1.41	0.5	bare-root	2 years transplants	10%	77	38
	Viburnum opulus	40-60	1.41	0.5	bare-root	2 years transplants	10%	77	38
	Loncera periclymenum	40-60	0.71	2	bare-root	2 years transplants	10%	77	153
	Prunus spinosa	40-60	1.41	0.5	bare-root	2 years transplants	5%	38	19
	Corylus avellana	40-60	1.41	0.5	bare-root	2 years transplants	5%	38	19
TOTALS							100%	766	879
Mix05	Herbaceous SUDs-friendly mix	Size Height, cm	Ctr m	No. / sq.m	Root Pot Size	Notes	Mix %	Area, sq.m	Total Quantity
	Salvia officinalis 'Purpureasens'	10-15	0.41	6	pot 9x9 cm	Full pot	20%	31	186
	Allium 'Purple Sensation'	10-15	0.41	6	pot 9x9 cm	Full pot	15%	23	140
	Leucanthemum vulgare	10-15	0.41	6	pot 9x9 cm	Full pot	15%	23	140
	Sedum autumnale	10-15	0.41	6	pot 9x9 cm	Full pot	10%	16	93
	Allium stipitatum 'Mount Everest'	10-15	0.41	6	pot 9x9 cm	Full pot	10%	16	93
	Verbena bonariensis	10-15	0.41	6	pot 9x9 cm	Full pot	10%	16	93
	Agave reptans	10-15	0.41	6	pot 9x9 cm	Full pot	5%	8	47
	Echinacea purpurea	10-15	0.41	6	pot 9x9 cm	Full pot	5%	8	47
	Foeniculum vulgare	10-15	0.41	6	pot 9x9 cm	Full pot	5%	8	47
	Rosmarinus officinalis	10-15	0.41	6	pot 9x9 cm	Full pot	5%	8	47
TOTALS							100%	165	933
WFM	Wildflower meadow mix	Rate g/ sq.m					Mix	Total area, sq. m	Total Quant., kg
	Emmorgate seeds EM1 Basic General Purpose Meadow Mixture (to TGA quality standards)	4					100%	4032	16
TOTALS							100%	4032	16
AG	Amenity grass	Rate g/ sq.m					Mix	Total area, sq. m	Total Quant., kg
	Geminal. A16 Road Verge and Embankments	40					100%	101	4
TOTALS							100%	101	4

This document is © Bond Bryan Architects Ltd. If in doubt ASK. Drawing measurements shall not be obtained by scaling. Verify all dimensions prior to construction. Immediately report any discrepancies on this document to the Originator. This document shall be used in conjunction with associated models, specifications and related consultant documents.

Key plan

North

0 10 20 30m

1:500

Legend

- Total curtilage including adopted highway
- Developable area
- North-Eastern Highways Area*
- Electrical cable easement areas
- Proposed hard surfaces
- Proposed trees. Ref. to BALU-BBA-YAP-XX-DR-L-2001 - Soft Landscape Strategy (1 of 2)
- Existing vegetation Ref. to Arboricultural Impact Assessment & Preliminary Arboricultural Method Statement by Thompsons Consultancy
- Existing vegetation to remain
- Existing vegetation, Root Protection Area

Rev Description Drawn Checked Date

P03	Amendments to species quantities	AF	BBA	03/07/2025
P02	Stage 4 issue	AF	SR	10/02/2025
P01	Issued for Planning, Stage 3	TT	SR	16/07/2024

B

BOND BRYAN

e info@bondbryan.co.uk
w www.bondbryan.co.uk

Barnsley Metropolitan Borough Council

BARNESLEY Metropolitan Borough Council **Currie & Brown**

Barnsley Levelling Up Fund
Youth Zone Activity Park

Soft Landscaping Strategy, Planting Plan and Schedule

Originator project ref 2304B	Purpose of issue For information
Scales) 1:250	Revision description Preliminary
Paper size A0	

project originator	volume	level	type	role	number	revision
BALU-BBA-YAP-XX-DR-L-2002						P03

www.bondbryan.co.uk