

Specification for The Original Factory Shop Hoyland

Sign A

Non-illuminated Folded aluminium panel 8000 x 900mm with 50mm returns, powder coated RAL 5002 having individual 5mm white acrylic letters to read 'The Original Factory Shop' on locators with built up acrylic cube logo. Letter height 450mm. Height from base of sign to ground level 3000mm. Full projection of sign is 75mm.

Sign B

Non-illuminated Folded aluminium panel 8800 x 590mm with 50mm returns, powder coated RAL 5002 having vinyl letters to read 'Big Brand at Factory Prices'. Height from base of sign to ground level 2400mm.

Sign C

Non-illuminated Folded aluminium panel 5200 x 1400mm with 50mm returns, powder coated RAL 5002 having vinyl letters to read 'The Original Factory Shop' complete with logo. Height from base of sign to ground level 3300mm.

Sign D

Non-illuminated Flat di-bond panel (blue) with vinyl lettering to read 'Goods In' size 1800 x 400mm. Height of sign from ground level 2700mm.

Sign E

Non-illuminated Folded aluminium panel 5200 x 1400mm with 50mm returns, powder coated RAL 5002 having vinyl letters to read 'The Original Factory Shop' complete with logo. Height from base of sign to ground level 3300mm.

Sign F

Non-illuminated 60x40 inch NEW STYLE poster frames to be fitted in various locations on the front elevation and car park areas.

Sign G

Non-illuminated Freestanding totem sign comprising of flat (blue) di-bond panel on 97mm grey PVC coated posts. Vinyl to the face to read 'The Original Factory Shop', 'large arrow right', with wording to read 'Open 7 days a week'.