

Material Schedule:

1. Main Body facing brickwork colour - red multi.
2. Main Body facing brickwork colour - dark red.
3. Main Body facing brickwork colour - buff.
4. Through coloured render, colour white.
5. Soldier Course feature brickwork detailing, heads& cills, colour - to match main body dark red brick.
6. White UPVC window/door frames.
7. PAS24 external door - colour white.
8. Black UPVC half round / polypipe gutters & square profile down pipes.
9. Dark grey UPVC fascias.
10. Boxed eaves detail, colour dark grey.
11. GRP door canopy design to be confirmed.
12. Concrete interlocking roof tiles - dark grey.

Key:

PV. Indicative PV zone. Position, amount and location subject to MEP design.

Note:
All doors, frame & locks to be PAS 24 compliant, doors with laminated glazing to comply with Part Q of the Building Regulations.
All accessible windows to comply with Part Q of the Building Regulations.

© Acanthus WSM Architects Ltd.
The general contractor is responsible for the verification all dimensions on site and the architect is to be informed of any discrepancy.
The status of information contained in a computer copy of this drawing shall be limited to that conveyed by the paper copy.

Design
Site to comply with the following design criteria subject to confirmation of the form of construction and assessment by an external accredited assessor.

Revisions:

Rev	Description	Date	Issued by
P1	Initial issue.		NG/DRP



West Elevation




South Elevation



East Elevation



North Elevation- main entrance



Vistry Group	
Scale	1 : 100 @A1
Date	March 2026
Drawn/Checked	NG/ DRP
Status	S3 Rev P1

Elevations

Apartment Building Shaw Lane, Carlton



S:\4035 Valley Farmstead\Shaw Lane, Carlton\WPCAD and Design\3D Model\Photograph\Apartment Block\Shaw Lane Apartment Block 2 Storey.rvt 05/03/2026 16:35:05