


**Boundary treatment
'A' to 'B' to 'C' to 'D'**


Will be the retention of the existing brickwork boundary/retaining wall with all loose brickwork removed and re-bedded and the top of the wall to be regularised in terms of height and finished off with a 'brick on edge' coping detail.

**Boundary treatment
'D' to 'E'**

Following removal of the existing boundary down to the existing ground level, (the majority of which is in a poor and untidy condition), a new boundary fence is to be erected on top of the retained wall base, consisting of timber fence panels fitted between concrete fence posts at 1800mm ctrs. The new fence will be 1500mm high and be of the appearance detailed alongside here :



- 1) This drawing and the design and details depicted thereon are the copyright of Peter Dimberline Chartered Architect.
- 2) All dimensions on this drawing are to be checked by the Contractor and any discrepancies are to be reported to the Architect.
- 3) Do not scale critical dimensions off this drawing.
- 4) Contractor to ensure that all Health & Safety requirements (CDM Regulations) in relation to this project will be complied with.



nb: drainage from plots 'D' and 'E' to be determined once final dwelling types have been agreed but the suggested route between a, b, c and d would avoid building over with any dwelling and also pick up any existing drains connecting from the adjacent terraces

REVISIONS

PETER DIMBERLINE Dip Arch, RIBA CHARTERED ARCHITECT	
2 TIPSEY COURT, STAINCROSS BARNSELEY, S75 6FZ	
tel/fax (01226) 390947 email: pdimberline@tiscali.co.uk	
CLIENT	Julie Morgan and Susan Brownlie
PROJECT	Proposed residential development
LOCATION	Westfield Street, off Dodworth Road, Barnsley
DRAWING	Proposed site layout --- showing drainage, floor levels & boundary treatments
SCALES	1:100 at A1
DATE	Nov' 14
DRAWN BY	PD
REV.	