



Planting Schedule

Trees - Plots

Abbr	Species	Supply	Size	Grth	Number
AMARH	Amelanchier arborea 'Robin Hill'	HS1d RB	350-425cm	12-14cm	25
BETJACA	Betula utilis 'Jacquemontii'	HS1d RB	350-425cm	12-14cm	12
LIQJUES	Ligustrum lucidum 'Succulentum Superum'	HS1d RB	350-425cm	12-14cm	14
MAGKOIS	Magnolia kobus 'Isis'	HS1d RB	350-425cm	12-14cm	30
MALTRI	Malus trilobata	HS1d RB	350-425cm	12-14cm	9
					Total 90

Trees - Public Open Space

Abbr	Species	Supply	Size	Grth	Number
PRNRY	Prunus sylvatica	RB	400-450cm		5
ACCA	Acer campestre	Std BR	250-300cm	8-10cm	4
CARBE	Carpinus betulus	Std BR	250-300cm	8-10cm	3
MALSY	Malus sylvestris	Std BR	250-300cm	8-10cm	9
SORAU	Sorbus aucuparia	Std BR	250-300cm	8-10cm	6
TICO	Tilia cordata	Std BR	250-300cm	8-10cm	1
BETPE	Betula pendula	SS1d BR	300-350cm	10-12cm	19
CARBET	Carpinus betulus	SS1d BR	300-350cm	10-12cm	12
SORAU	Sorbus aucuparia	SS1d BR	300-350cm	10-12cm	7
ACECAM	Acer campestre	HS1d RB	350-425cm	12-14cm	8
AMARH	Amelanchier arborea 'Robin Hill'	HS1d RB	350-425cm	12-14cm	4
BETPE	Betula pendula	HS1d RB	350-425cm	12-14cm	1
CARBETTF	Carpinus betulus 'Pyram Fontaine'	HS1d RB	350-425cm	12-14cm	2
MALVE	Malus 'Evereste'	HS1d RB	350-425cm	12-14cm	9
PRUAV	Prunus avium	HS1d RB	350-425cm	12-14cm	2
SORAU	Sorbus aucuparia	HS1d RB	350-425cm	12-14cm	8
ACELEO	Acer platanoides 'Emerald Queen'	EH1d RB	425-500cm	14-16cm	3
BETJACA	Betula utilis 'Jacquemontii'	EH1d RB	425-600cm	14-16cm	2
TILCO	Tilia cordata	EH1d RB	425-600cm	14-16cm	1
ACECAM	Acer campestre 'Elsby'	EH1d RB	425-500cm	14-16cm	10
CARBET	Carpinus betulus	EH1d RB	425-500cm	14-16cm	2
PRUAVPL	Prunus avium 'Plena'	EH1d RB	425-650cm	18-20cm	1
					Total 125

Specimen Shrubs

Abbr	Species	Pot Size	Height	Habit	Number
PHOAR	Phormium 'Amazing Red'	1SL	80-100cm	Tip-On	8
PHOUE	Phormium 'Jester'	1SL	80-100cm	Tip-On	5
PHOYAW	Phormium 'Yellow Wave'	1SL	80-100cm	Tip-On	9
PHOFRF	Phormium x Fraseri 'Red Robin'	50L	200-225cm	SS1d 10-12cm	15
					Total 37

Single-Species Hedgerows

Abbr	Species	Pot Size	Height	Habit	Density	Length	Number
ELAEBCO	Elaeagnus ebbingei 'Compacta'	10L	80-100cm	Bushy	0.4Ctr	838.75m	2142
BETJACA	Betula utilis 'Jacquemontii'	10L	40-60cm	Bushy	0.4Ctr	87.54m	227
ELAEBV	Elaeagnus ebbingei 'Vivipar'	10L	80-100cm	Bushy	0.4Ctr	346.4m	880
PRULAU	Prunus laurastica	10L	80-100cm	Bushy	0.4Ctr	65.07m	165
					Total 1538.16m	Total 3414	

Shrubs - Plots

Abbr	Species	Pot Size	Height	Habit	Density	Area	Number
AUCJACR	Aucuba japonica 'Crotontifolia'	10L	60-80cm	Bushy	0.8Ctr	81.57m²	147
BRASU	Brachyglottis 'Sunrise'	10L	40-60cm	Bushy	0.7Ctr	57.69m²	148
CEATHR	Ceanothus thyrsiflorus repens	10L	40-60cm	Bushy	0.7Ctr	60.65m²	147
CHOAP	Choysya Actae 'Pearl'	10L	40-60cm	Bushy	0.7Ctr	13.38m²	35
CHOTE	Choysya ternata	10L	60-80cm	Bushy	0.7Ctr	5.49m²	15
CHOTES	Choysya ternata 'Sundance'	10L	40-60cm	Bushy	0.7Ctr	120.75m²	292
CORALE	Cornus alba 'Tangerissima'	3L	60-80cm	Branched	0.8Ctr	74.77m²	135
ELAPUMA	Elaeagnus purpurea 'Maculata'	10L	80-100cm	Bushy	0.8Ctr	80.89m²	146
EUOFOEN	Eucyrtus fortunei 'Emerald Gasey'	10L	30-40cm	Bushy	0.7Ctr	13.38m²	35
EUOFOEN	Eucyrtus fortunei 'Emerald Gold'	10L	30-40cm	Bushy	0.7Ctr	229.98m²	560
FATJA	Fatsia japonica	10L	60-80cm	Bushy	0.8Ctr	7.72m²	21
HEBAL	Hebe abicans	5L	20-30cm	Bushy	0.6Ctr	9.48m²	29
HEBALRE	Hebe abicans 'Red Edge'	10L	30-40cm	Bushy	0.7Ctr	103.57m²	252
HEBALRE	Hebe 'Red Edge'	10L	30-40cm	Bushy	0.7Ctr	34.8m²	80
HEBMAR	Hebe 'Marjorie'	10L	40-60cm	Bushy	0.7Ctr	18.71m²	46
HEBMW	Hebe 'Mrs Winder'	10L	40-60cm	Bushy	0.7Ctr	75.12m²	182
HEBPS	Hebe pinguifolia 'Sutherlandii'	10L	30-40cm	Bushy	0.7Ctr	170.69m²	412
HEBPD	Hebe 'Purple Cloud'	10L	40-60cm	Bushy	0.7Ctr	8.29m²	19
HYPE	Hypericum 'Hidcote'	10L	40-60cm	Bushy	0.7Ctr	18.71m²	46
LAVANNA	Lavandula angustifolia 'Hidcote'	10L	40-60cm	Bushy	0.7Ctr	95.77m²	230
LAVANNA	Lavandula angustifolia 'Munstead'	10L	30-40cm	Bushy	0.7Ctr	60.44m²	146
OSMU	Osmanthus x burkwoodii	10L	60-80cm	Bushy	0.8Ctr	8.48m²	14
PACTE	Pachysandra terminalis	2L	20-30cm	Bushy	0.6Ctr	9.48m²	29
PHOFRF	Phormium x Fraseri 'Red Robin'	10L	80-100cm	Bushy	0.8Ctr	85.67m²	155
PRULAU	Prunus laurasterous 'Toto Lucken'	10L	60-80cm	Bushy	0.7Ctr	69.67m²	166
SKOCKO	Skimmia cornuta 'Kew Green'	10L	40-60cm	Bushy	0.7Ctr	34.8m²	80
SKJAUU	Skimmia japonica 'Tubules'	10L	40-60cm	Bushy	0.7Ctr	84.53m²	207
VIBDA	Viburnum davidii	10L	40-60cm	Bushy	0.7Ctr	58.2m²	159
VINMI	Vincetoxicum	2L	20-30cm	Bushy	0.6Ctr	8.12m²	27
					Total 1698.5m²	Total 3919	

Native Hedgerow - Species-Rich (Transplants)

Abbr	Species	Supply	Height	Density	Mix %	Length	Number
CORSA	Cornus sanguinea	T1+1.5 Bires	60-80cm	0.3Ctr Double Staggered at 0.3m offset	10%	19.99m	150
CRAMON	Crataegus monogyna	T1+1.5 Bires	60-80cm	0.3Ctr Double Staggered at 0.3m offset	35%	67.87m	453
EUOEPS	Eucyrtus fortunei	T1+1.5 Bires	60-80cm	0.3Ctr Double Staggered at 0.3m offset	10%	19.99m	150
ILEAO	Ilex aquifolium	2L 5 Bires	40-60cm	0.3Ctr Double Staggered at 0.3m offset	15%	29.08m	195
LIQJUES	Ligustrum vulgare	T1+1.5 Bires	60-80cm	0.3Ctr Double Staggered at 0.3m offset	15%	29.08m	195
ROSCA	Rosa canina	T1+1.5 Bires	60-80cm	0.3Ctr Double Staggered at 0.3m offset	5%	8.69m	66
VIBOP	Viburnum opulus	T1+1.5 Bires	60-80cm	0.3Ctr Double Staggered at 0.3m offset	10%	19.99m	150
					Total 193.89m	Total 1299	

Marginal / Aquatics

Abbr	Species	Supply	Density	Mix %	Area	Number
CARAC	Carex acutata	Plug 100cc	10m²	12%	3.57m²	36
ELPAL	Elaeagnis palustris	Plug 100cc	10m²	12%	3.57m²	36
GLYMAX	Glyceria maxima	Plug 100cc	10m²	12%	3.57m²	36
IRPS	Iris pseudocorus	Plug 100cc	10m²	16%	4.76m²	48
JUNEF	Juncus effusus	Plug 100cc	10m²	12%	3.57m²	36
JUNIN	Juncus infusus	Plug 100cc	10m²	12%	3.57m²	36
SACSA	Sagittaria sagittifolia	Plug 100cc	10m²	12%	3.57m²	36
SCILA	Scirpus lacustris	Plug 100cc	10m²	12%	3.57m²	36
					Total 29.75m²	Total 300

Bulbs

Abbr	Species	Supply	Density	Number
CROCHBP	Crocus chrysanthus 'Blue Pearl'	Bulb	25m²	1040
CROCHCB	Crocus chrysanthus 'Cream Beauty'	Bulb	25m²	1040
NARICA	Narcissus 'Carnaticulatus'	Bulb	25m²	1040
NARIT	Narcissus 'Tete a Tete'	Bulb	25m²	1040
				Total 4160

Turf & Seeding

Turf

Turf to gardens to be laid as Roben 'Medallion' or similar approved.

Amenity Grass

A22 low maintenance seed mixture, as supplied by Germinal (www.germinalamenity.com) or similar approved.

Meadow Grassland

EML seed mixture for meadows, as supplied by Ennorsgate Seeds (www.wildseed.co.uk) or similar approved.

Wet Meadow Grassland

EML seed mixture for wetlands, as supplied by Ennorsgate Seeds (www.wildseed.co.uk) or similar approved.

Grassland boundary

Dashed line indicates delineation between amenity and meadow grassland, requiring differing mowing regimes.

Key

Application site boundary.

Existing vegetation to be retained.

Existing/Proposed easements

Root Barriers

Root barrier 600 root barrier to be installed as per manufacturers specification where tree planting does not fulfil the recommended distances to avoid direct damage at Table A1 of BS5837:2012. To be supplied by Green Blue Urban (www.greenblueurban.com) or similar approved.

Knee Rail

To satisfy Homes specification.

Drawing to be read in conjunction with GLY0250 SP 01 Landscape Specification.