Accredited Contractor
www.chas.gov.uk

FRED SHAW & CO.
specialists in sheetmetal fabrication

BUILDING & ENGINEERING SERVICES ASSOCIATION
a new brand; a new HVCA

Email:david@fshaw.co.uk
Tel: 01484 422625

QUOTATION REFERENCE :	**Q9972**
DATE:	30.09.16
PREPARED BY:	David Sutton

PROJECT REFERENCE:	**Cannon hall Garden centre**
TO:	DM Eco Design
FOR THE ATTENTION OF:	Dean Morton

We thank you for you enquiry and take pleasure in offering our quotation as follows:
For the manufacture ,supply and installation of a Grade 204 S/Steel canopy ductwork and fan unit
If you have any question regarding the equipment proposed, our sales staff will be happy to help.

Item	Description	Number	Price each £	Total £
1	1 x Grade 304 S/Steel wall canopy with recessed lights and baffle cells 2.5m x 1.4m x 0.5m	1	2,468.00	2,468.00
2	1 x Roof mounted Vertical discharge fan Ec Motor	1	1,051.00	1,051.00
3	Grade 304 S/Steel wall cladding from U/S of canopy to floor level	1	627.00	627.00
4	1 x window mounted Natural filtered fresh air input unit in Grade 304 S/steel	1	585.00	585.00
5	1 x Gas watch /vent control unit inclusive of free issue cellnoid valve	1	1,298.00	1,298.00
6	wire Gas watch /control panel (all other wiring ie power to fan by others)	1	1,481.00	1,481.00
7	Ozone odour control unit	1	1,039.00	1,039.00
8	Galv ductwork from Canopy to roof fan	1	906.00	906.00
9				0.00
				0.00
				0.00
				0.00
				0.00
				0.00
			TOTAL £	9,455.00

	Optional Extras	Number	Price each £	Total £
				0.00
				0.00
				0.00
				0.00
				0.00
				0.00
				0.00
				0.00
				0.00
				0.00
			TOTAL £	0.00

All prices exclude VAT
Based on normal hours
Prices Include Delivery Main Land Uk.

GRAND TOTAL **£9,455.00**

DELIVERY PERIOD: **TBC**

Exclusions:

Roof work
External Scaffold
Electrical work
Gas Work
Builders work

Drawings: The above costs are inclusive of full AutoCAD drawings for the ventilation work, all sets and plant room layouts will be site measured and drawings produced in isometric view within plant areas.

Payment terms: All prices are subject to VAT at the current rate. Payment term 30 days net for approved accounts
Retentions and liquidated damages are not applicable

Terms: Any work procured from this quotation shall be subject to standard JCT contract terms

Warranty Claims: Replacement equipment and site visits are chargeable. Once products are proved faulty these cost will be credited.
Cost for site visits due to warranty claims must agreed in writing before a visit can be carried out.
Our products have a 1 year warranty from the date of delivery.

Orders are accepted only on our standard terms and conditions of sale, a copy of which is available on request.

constructionline

FRESHCAN
bespoke kitchen ventilation canopies

FRE-SH-AIR
bespoke air handling equipment

CSA Commissioning Specialists Association
Associate Member