



BARNSELEY ROAD

entrance

exit

BUS SHELTER

BRICK WALL

TARMAC

customer parking

staff parking

utility bay

customer parking

jet washes

bin & secure compound

deliveries

ROY KILNER ROAD

CHANNEL

CONC POST WOOD PANEL FENCE HT 1.8M

WOOD FENCE HT 1.8M

WOOD FENCE HT 1.8M

WOOD FENCE HT 1.8M



location plan 1/1250

lighting key

- canopy light positions shown thus
 - all fittings to be LED low energy exact aperture size to be confirmed with light fitting supplier
 - light fitting supplier to confirm output of fittings and average lux over pump islands measured at 1.5m above forecourt level - to be max. 500 lux
 - LED light fitting on lighting pole to illuminate utility bays - to approx. 350 lux
 - under soffit LED low energy lights with approx. 150 lux to shopfront
- nb. all fittings are to be downward & directional so as prevent overspill beyond the site boundary

This drawing has been prepared specifically for the purpose of obtaining Planning Permission and/or Building Regulation Approval. Its suitability for other purposes, without supplementary details and specifications cannot be guaranteed. The Permissions and/or Approvals are beyond the Architects control and no guarantee that such will be granted is given or to be inferred by reason of the preparation of this drawing. Only figured dimensions are to be used. All dimensions to be checked on site. This drawing together with the design is the property and copyright of the Architect and must not be reproduced without prior written permission.

P01 Drawing originated 20.07.18 AS AS
 rev. description date draw. apprd.



project proposed redevelopment of site to reinstate petrol filling station at 245, Barnsley Road, Wombwell Barnsley for Dove Retail Ltd

title forecourt lighting
 number 18048D-31-P01
 scale 1:100
 size A1