

KFC - Ext 21



Ral 7022

KFC - Ext 22



Ral 7022

KFC - Ext 23



Ral 7022

Specification

- 01 No Entry (Sign Ref A) roundal manufactured from 3mm aluminium being primed and powder coated silver Ral 9006 with standard red vinyl applied to face having border and details to face in reflective white vinyl.
- 02 Grill Bay Sign (Sign Ref B) roundal manufactured from 3mm aluminium being primed and powder coated silver Ral 9006 having black self adhesive vinyl applied to face.
- 03 Disabled Parking Sign (Sign Ref C) manufactured from 3mm aluminium being primed and powder coated silver Ral 9006 having digitally printed vinyl with protective laminate applied to face.
- 04 Post manufactured from 76mm x 3mm diameter C.H.S. aluminium primed and powder coated grey Ral 9006
- 05 Grey plastic capping
- 06 100mm diameter plastic sleeve back filled with sand and cement dry mix
- 07 Extruded aluminium brackets riveted to roundal.
- 08 Steel clamping bracket with fixing bolts.

