



Plant Schedule							
Trees							
Number	Abbreviation	Species	Specification	Height	Pot Size	Girth	Density
3	Ace cam Q E	Acer campestre 'Queen Elizabeth'	Extra Heavy Standard; clear stem 175-200; 5 breaks; 3x; RB	425-600cm	RB	14-16cm	Counted
2	Ame arb R H	Amelanchier arborea Robin Hill	3x; Extra Heavy Standard; clear stem 175-200cm; 5 breaks; RB	425-600cm	RB	14-16cm	Counted
3	Bet pen	Betula pendula	3x; Extra Heavy Standard; clear stem 175-200cm; 5 breaks; RB	400-450cm		14-16cm	Counted
3	Bet uti jac	Betula utilis jacquemontii	3x; Multi-stem; bushy; 3 stems minimum; RB	300-350cm			Counted
1	Mal E	Malus 'Everest'	3x; Extra Heavy Standard; clear stem 175-200cm; 5 breaks; RB	400-450cm	RB	14-16cm	Counted
2	Pru avi	Prunus avium	3x; Extra Heavy Standard; clear stem 175-200cm; 5 breaks; RB	400-450cm	RB	14-16cm	Counted
3	Pru avi P	Prunus avium 'Plena'	3x; Extra Heavy Standard; clear stem 175-200cm; 5 breaks; RB	400-450cm		14-16cm	Counted
1	Pru dom C	Prunus domestica 'Czar'	Heavy Standard; clear stem 175-200cm; 5 breaks; RB	300-350cm		10-12cm	Counted
Total: 18							

Climbers							
Number	Abbreviation	Species	Specification	Height	Pot Size	Density	
3	Hyd see	Hydrangea seemannii	Cane; several shoots; 3 breaks	40-60cm	3L	Counted	
4	Jas nud	Jasminum nudiflorum	Cane; several shoots; 3 breaks	60-80cm	10L	Counted	
Total: 7							

Shrubs							
Number	Abbreviation	Species	Specification	Height	Pot Size	Density	
7	BUD DAV	Buddleja davidii	Branched; 5 breaks	60-80cm	5L	3/m <sup>2</sup>	
4	Ela ebb L	Elaeagnus ebbingei 'Limeglow'	Branched; 4 breaks	40-60cm	6L	3/m <sup>2</sup>	
5	Euo for S	Euonymus fortunei 'Sunspot'	Bushy; 9 breaks	30-40cm	10L	3/m <sup>2</sup>	
10	For int L	Forsythia intermedia 'Limegold'	Branched; 5 breaks	60-80cm	5-7.5L	3/m <sup>2</sup>	
14	Heb M B	Hebe 'Midsummer Beauty'	Bushy; 7 breaks	30-40cm	5-7.5L	3/m <sup>2</sup>	
4	Vib opu C	Viburnum opulus 'Compacta'	Bushy; 4 breaks	30-40cm	3L	3/m <sup>2</sup>	
9	Vib pc	Viburnum plicatum	Branched; 3 breaks	40-60cm	5L	3/m <sup>2</sup>	
5	Wei flo F P	Weigela florida 'Trollis Purpurea'	Branched; 4 breaks	30-40cm	3L	3/m <sup>2</sup>	
Total: 58							

Fruiting mix							
Number	Abbreviation	Species	Specification	Height	Pot Size	Density	
3	Rib nig B N	Ribes nigrum 'Ben Nevis'	0/1; Cutting; Bush; 3/5 shoots; BR	60-80cm	3L	1.5/m <sup>2</sup>	
3	Rib rub R L	Ribes rubrum 'Red Lake'	0/1; Cutting; Bush; 3/4 shoots; BR	60-80cm	3L	1.5/m <sup>2</sup>	
3	Rib rub W H	Ribes rubrum 'White Holland'	0/1; Cutting; Bush; 3/4 shoots; BR	60-80cm	3L	1.5/m <sup>2</sup>	
2	Rib uva c	Ribes uva-crispa	1+0; Seeding; branched; 2 breaks; BR	30-40cm	3L	1.5/m <sup>2</sup>	
Total: 11							

Ornamental mix							
Number	Abbreviation	Species	Specification	Height	Pot Size	Density	
23	Car osh E	Carex oshimensis 'Evergold'	Full pot		3L	4/m <sup>2</sup>	
38	C san 'M F'	Cornus sanguinea 'Midwinter Fire'	Branched; 4 breaks	60-80cm	5-7.5L	4/m <sup>2</sup>	
19	Cro E M	Crocus 'Emily McKenzie'	Full pot		3L	4/m <sup>2</sup>	
35	Hyd mac V	Hydrangea macrophylla 'Voyager'	Branched; 5 breaks	40-60cm	5-7.5L	4/m <sup>2</sup>	
19	Leu sup W S	Leucanthemum superbum 'Wirral Supreme'	Full pot		5L	4/m <sup>2</sup>	
28	Mis sin M L	Miscanthus sinensis 'Morning Light'	Full pot		5-7.5L	4/m <sup>2</sup>	
Total: 160							

Hedges							
Number	Abbreviation	Species	Specification	Height	Pot Size	Density	
63	LIGVU	Ligustrum vulgare 'T'	Branched 4 brks	60-80cm	3L	0.35Cr Double Slaggered at 0.35m offset	
Total: 63							

Native Hedge Mix							
Number	Abbreviation	Species	Specification	Height	Pot Size	Density	
119	Ace cam	Acer campestre	1+1; Transplant - seed raised; BR	60-80cm		0.35Cr Double Slaggered at 0.35m offset	
77	Cor san	Cornus sanguinea	1+1; Transplant - seed raised; branched; 3 breaks; BR	60-80cm		0.35Cr Double Slaggered at 0.35m offset	
93	Cor ave	Corylus avellana	1+2; Transplant - seed raised; branched; 3 breaks; BR	60-80cm		0.35Cr Double Slaggered at 0.35m offset	
68	Cra mon	Crataegus monogyna	1+2; Transplant - seed raised; BR	100-125cm		0.35Cr Double Slaggered at 0.35m offset	
68	Lig vul	Ligustrum vulgare	0/2; Cutting; branched; 3 breaks; BR	60-80cm		0.35Cr Double Slaggered at 0.35m offset	
Total: 425							

### Legend

**SOFT LANDSCAPE**

- Site boundary
- Existing trees/vegetation to be retained & protected during construction in accordance with BS5837:2012
- Proposed Specimen Tree Planting
- Proposed Native Tree Planting
- Proposed Native/Ornamental Clipped Hedge
- Proposed Ornamental Shrub/Perennial Planting
- Proposed Grass Area: Boston Seeds BS Eco-Clover grass seed; sowing rate 25g/m<sup>2</sup>. To be sown over playground safety mats 1.5x1m 22mm thick within stepping logs area only.
- Proposed Species - Rich Grassland: Bromegrass EM3 - Special General meadow mixture; sowing rate 6g/m<sup>2</sup>

**HARD LANDSCAPE**

- Proposed Surface: Premium play grade bark chippings. To be laid over heavy duty landscape fabric fixed with ground pegs.
- Proposed Graveled Surface: 20mm pea gravel/chippings or similar approved. To be laid over heavy duty landscape fabric fixed with ground pegs.
- Proposed Access Footpath Surface: Bradstone Marina Concrete Paving (Buff) 450x450mm or similar approved. To be edged with treated timber edging.
- Proposed Footpath Surface: ESP Play Rubber mat surface (Brown) or similar approved. To be edged with treated timber edging.
- Proposed Palisade Fencing: Additional section of fencing to match existing. Height: 2.35m.
- Proposed Bow Top Fence: Additional section of fence to match existing. Height: 1.2m.
- Proposed Picket Fence: Section of picket fence to be installed adjacent to retained wall to prevent access. Treated round top 1.2m(L) x 95 (W) x 20 (T)mm fence board fixed to posts or similar approved.
- Proposed Garden Gate: Bow top gate 1.2m high or similar approved. Colour to match existing fence.
- Proposed Timber Structure: Buyfencingdirect Forest Garden 6m Premium Oval Wooden Gazebo With Cedar Roof 6243 (W) x 3352 (H)mm or similar approved. <https://www.buyfencingdirect.co.uk/20-x15-premium-oval-furnished-wooden-garden-gazebos-with-new-angled-cedar-roof-seals-up-to-27-people>
- Proposed Outdoor Planters: 200x100mm treated railway sleeper raised bed 700mm high.
- Proposed Top Soil/Multipurpose Compost
- Proposed Stepping Logs: Playark stepping logs 0.125x0.125m or similar approved to be installed within grassed areas.
- Proposed Stepping Stones: Trade Point antique brown stepping stone 600(W) x 50(H) or similar approved.
- Proposed Timber Archway: 100x100x2000(H)mm Oak posts underplanted with climbers.
- Proposed Shade Sale: 3x4m outdoor kitchen shade sale in grey with supporting 100x100x3000(H)mm planed timber posts or similar approved. Supplier: Amazon.
- Proposed Fire Pit Cobble: Various sizes Rockery stone to create a fire pit edge.
- Proposed Outdoor Mud Kitchen: Costcutters UK Early Years Outdoor Wooden Supreme 'U' Shaped Mud Kitchen 2000 (L) x 500 (D) x 1100 (H)mm or similar approved.
- Proposed Bollard Lighting: Barriers Direct Shoreham LED Wood Bollard 125 x 125 x 1150mm (900mm above ground level) or similar approved. Technical information to Engineers specifications.
- Proposed Storytelling Chair & Seating Logs: Costcutters Early Years Outdoor Wooden Story Telling Chairs 2x 1600 (H)x460mm (W). Tree Stump Seating Logs 31cm (H) 17-24cm (D) or similar approved.
- Existing Retaining Wall: Existing steps to be removed with western part of the timber wall to be retained and made structurally sound. Regrade soil north east to avoid T12 RPA. Levels to be confirmed by project Engineer.

Levels design to Engineers specifications.

Revision	By	Date	Details
Initial	DM	24.09.25	For Comment
A	DM	11.11.25	T7, T8 removed. Replacement trees included. Path redesign.

Project Reference / Name: BG25.237 Bank End Primary School

Client: BARKER

Drawing title: Soft and Hard Landscape Proposals

Purpose of Issue: INITIAL ISSUE	Date of Issue: 24/09/2025
Scale @ A1: 1:100	Activity: S4
Drawn: DM	Checked and approved: HCK
Issue: P02	Revision: A

Drawing No: BG25.237-BRGR-ZZ-DR-L-00001

Brindle & Green Ltd  
www.brindlegreen.co.uk  
Tel: 0800 222 9105

