

Legend


Herbaceous	
Miscanthus sinensis 'Gracillimus'	Mis Gra
Shrub	
Choisya ternata	Cho ter
Hebe 'Midsummer Beauty'	Heb Mid
Hypericum patulum 'Hidcote'	Hyp Hid

Shrubs to BS 3936 to be planted in debris and weed free topsoil 45cm deep. Topsoil to BS 3882. Any heavily compacted and panned ground to be deep ripped to relieve the compaction. All beds to be accurately cut with even curves and straight lines as appropriate. Allow for 50mm of Contract Ornamental bark mulch to all planting beds. Plants to be good quality bushy stock commensurate with the stipulated pot size.

Trees	
Pyrus calleryana Redspire	T1 - Girth 14-16 cms - triple staked
Amelanchier arborea Robin Hill	T2 - Girth 14-16 cms

Trees to be staked and tied at low level using 75mm peeled larch stakes and durable rubber ties. Triple staked trees to have 3 no. peeled larch stakes 2.1m long, 600mm into the ground. Trees triangulated using 3 no. 500mm long x 75mm x 25mm tanalised timber spacer bars nailed to top of stakes with galvanised clout nails. Tree held in place centrally using durable rubber ties. Base of triple staked tree to have a 1m diameter circle of grass free topsoil which is to be mulched and maintained weed free. Tree pits are to be 900mm x 900mm x 750mm deep with layer backfill containing the recommended quantity of mycorrhizal fungal spores. Trees are to be well watered at planting time and during time of low rainfall.

Grass
Front and rear gardens are to be turfed using good quality meadow turf on 150mm topsoil raked to a filth with all stones and deleterious materials removed



Ornamental shrub planting, including 50mm depth no-fines bark mulch



Areas of cultivated-grade turf



Areas of decorative gravel



Tree planting

