
Carrs Lane, Cudworth



NAME	STOREYS	BED	FLOOR AREA	% MIX	UNITS	TOTAL
			Private			
(Was) Washington - End	2		615	5.4	15	9225
(Was) Washington - Mid	2		615	0.4	1	615
(Hal) Halton	2		1268	4.7	13	16484
(Mai) Maidstone - End	2		830	7.9	22	18260
(Mai) Maidstone - Mid	2		830	2.9	8	6640
(Fol) Folkstone - End	2		830	15.8	44	36520
(Fol) Folkstone - Mid	2		830	1.8	5	4150
(Win) Windermere	2		1074	6.8	19	20406
(Enn) Ennerdale - Det	2		916	5.4	15	13740
(Enn) Ennerdale - End	2		916	3.6	10	9160
(Che) Chester	2		1032	3.2	9	9288
(Kin) Kingsley	2		1079	10.4	29	31291
(Esk) Eskdale - Det	2		1058	2.2	6	6348
(Esk) Eskdale - End	2		1058	2.9	8	8464
(Rip) Ripon	2		1120	4.3	12	13440
(Rad) Radleigh	2		1316	8.6	24	31584
(Ald) Alderney	2		1225	8.3	23	28175
			Private Total		**263**	**263790**
			Bungalows			
(Alt) Alton	1		800	3.2	9	7200
(Bea) Beadale - End	1		594	2.2	6	3564
			Bungalow Total		**15**	**10764**
				Overall Total	**278**	**274554**

Overall Density		
Gross Area	28.7	Acres
Net Area	19.6	Acres
Density	14008	Per Acre
Units Per Ha	35.02	
Units Per Acre	14.18	

Technical Layout Legend

- Existing dwellings
- Front entrance door
- Secondary entrance
- Denotes handing of plot
- 1800mm high screen wall + fence
- 1800mm high close board timber fence
- 450mm high timber knee rail fence
- 1.5m post and rail stockproof fence with 4 rails.
- Ball Top metal railings
- Lockable personnel gate
- Denotes additional windows to habitable rooms
- Bin collection points
- Landscaping Retained
- Landscaping Removed
- Permitted Development rights removed.
- Private Dwelling Bin Storage
- Grit Bin Locations (2m x 1m hard-standing area)
- Sewer Easements
- Cable Easements
- Block Paving
- Grass/Low landscaping highway verges

GENERAL SPECIFICATION NOTES:-

1. All rear gardens to be gated with lockable gate.
2. Refer to engineers drawings for retaining wall / drainage details.
3. Where heights are shown to step by more than 600mm guarding/balustrading to be provided in accordance with Building Regulations Part K. Where step is shown to be exactly 600mm contractors must ensure this height is not exceeded.

BOUNDARY SETTING OUT NOTES:-

- Refer to Boundary Setting Out drawings.
- Set boundaries out in accordance with the approved Technical Layout.
- If a boundary cannot be constructed in accordance with the Setting Out Drawings (e.g. if there is an obstruction) please contact the technical department for advice.

Rev.	Date.	
C	11/12/17	Highways amended to match S38 drawing. Adopted verge areas hatched. Grit bin and Bin collection points amended. Retaining walls above 600mm shown. Fence added around perimeter of Attenuation Basin. Private drives serving 83-86 & 62-65 shortened to 45m or less. Plots 145/146 garage adjusted forward to allow tree protection measures to be put in place.
B	06/11/17	Plots 1-4 show swinging gate to rear. Adopted highway verge margin removed. Services shown and footpath 83-86 & 45m serving 49-53. P1 codes added. Folkestone handings amended. Attenuation area revised. Meter box positions added to Beadle housetype. Bungalow 'Alford' re re-refferenced as 'Alton'. Ramps removed other than entrance to block paved roads. Sub Station shown in in SE corner. Cable easements shown.
A	03/08/17	Bin storage and Grit Bin locations indicated. Rear access provided to Plot 184.

NOTES

This drawing and all the information shown is the property of DK Designs and shall not be copied whole, or in part, or used for any other purpose without written permission of the Company

ALL DIMENSIONS TO BE CHECKED ON SITE

ALL SUBJECT TO STRUCTURAL ENGINEERS CHECKS AND CALCULATIONS

DO NOT SCALE FROM THIS DRAWING EXCEPT FOR THE PURPOSES OF LOCAL AUTHORITY PLANNING

IF ANY VARIATIONS ARE MADE TO SPECIFICATION/DRAWINGS WITHOUT DK DESIGNS KNOWLEDGE, DK DESIGNS WILL NOT BE HELD ACCOUNTABLE FOR NON COMPLIANCE OF PLANNING AND BUILDING REGUALTIONS

DK DESIGNS
FUTURE PROJECTS TODAY

96 Blackburn Drive
Chapeltown
Sheffield
S35 2ZP

TEL/FAX:- 0114 2571043 MOB:- 07710783875
EMAIL :- Designs@DK-Designs.co.uk
WEB:- www.DK-Designs.co.uk

Client.

Barratt Homes

Project/Title.

Carrs Lane, CUDWORTH
Technical Layout

Scales.		Date.
1:500 @ A0		June 17
Drawing Number.	Revision.	Drawn by.
2017-083-01	C	MTS