16
18
4
6
2
2
Churchfields Close
RELOCATE EXISTING PARK BENCH AND MAKE GOOD
1600
NEW BLOCK PAVING TO INSIDE BIN STORE AREA TO MATCH EXISTING PAVING.
INCLUDE FOR RELAYING 20M2 BLOCK PAVING AND ALLOW FOR NEW PIN KERBS
7100
EXISTING RETAINING WALLS TO BE RETAINED.
1500 HIGH FENCING ENCLOSURE TO BIN STORE ON 3 SIDES
3400
INCLUDE 1M WIDE GATE AND LARGE GATE WITH SECURITY LOCKS. SMALL GATE FOR ACCESS TO WHEELER BINS
HEDGE TO BE CUT BACK 3.5M
NO TREES TO BE CUT DOWN
EXISTING BLOCK PAVED AREA TO BE EXTENDED TO MATCH EXISTING
H LANE

REV	DATE	DESCRIPTION

The contractor is to comply in all respects with the current Building Regulations and is to check all site dimensions and levels.
Do not scale from the drawing, use written dimensions. To be read in conjunction with Pre-Tender Health & Safety Plan / Preliminaries Section (Section A34 etc.)
Maps are reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office
© Crown copyright. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings 100022264 (2011)

nps group
NPS BARNSLEY LTD
PO BOX 634
BARNSLEY
SOUTH YORKSHIRE, S70 9GG
TEL: 01226 774605 FAX: 01226 774399
EMAIL: enquiries@nps.co.uk

Head Office:
Lancaster House, 16 Central Avenue, St Andrews Business Park, Norwich, NR7 0HR Tel: 01603 706000 Fax: 01603 700001
Other Office locations can be found on website : www.nps.co.uk

PROJECT: Churchfields Close Barnsley	CLIENT: Berneslai Homes
	CAD FILE REF: — DATE: Dec 2011 SCALE: 1:50
SUBJECT: Sheltered Housing Alterations Landscaping	REV: — DRAWN: P Hepp CHECKED: —
	PROJECT NR: HSG_4256 DRAWING NR: 203

© NPS This drawing may not be reproduced in any form without prior written agreement

A1