



Soft Landscape

BALU-BBA-YM-ZZ-SH-L-00001- PLANTING SCHEDULE- Planning										B	
Client: Currie & Brown - Location: YMCA,Barnsley											
Created by: Bond Bryan Architects - Landscape											
PLANT SCHEDULE- : Rev P01- (31.05.2024)										B O N D B R Y A N	
Refer to dwg nos.: SOFT LANDSCAPE PLAN: BALU-BBA-YM-ZZ-DR-L-1013											
Name	Ctr	No.	Girth/	Height	Root	Container	Form	Quantity			
	m	/m²	Dia. cm	cm	zone	Size					
INDIVIDUALLY PLANTED TREE SPECIES											
Acer campestre / Field Maple										2	
INDIVIDUAL HEDGING										Length M	
single mature block rows spaced at 300mm ctrs. (4no. per linear metre); reduced height by 25% once planted (to obtain density & form)											
Name	Size	Height	Ctr	No.	Root/	Notes		%	Total Area/	Total Quant.	
	cm	cm	m	/m	Pot Size			Mix	%		
Juniperus scopulorum 'Skyrocket' /Rocky Mountain Juniper/	60-80	0.45	5		3L	Container feathered			2.5	9	
Photinia x fraseri 'Red Robin'	90-120	0.45	4		10L/ 1.m			100%	4	16	
Taxus baccata 'Yew'	90-120	0.45	5		10L/ 1.m	RB formed sections		100%	10	50	
Lavandula angustifolia 'Hidcote' /Lavender/ (La)	60-80	0.45	5		5L	dense hedge form, full pot		100%	8	40	
Name	Size	Height	Ctr	No.	Root/	Notes		%	Total Area/	Total Quant.	
	cm	cm	m	/m²	Pot Size			Mix	%		
NATIVE HEDGES TO PERIMETER EDGES -Mix 01										Length M	
staggered rows spaced at 450mm ctrs. 300mm row spacing ; reduced height by 25% once planted											
Barberis darwinii /Darwin's barberry	100	0.45	4		trough 1.m	RB formed sections		30%	15	18	
Ilex aquifolium /Common holly	100-125	0.45	4		trough 1.m	RB formed sections		40%	20	32	
Carpinus betulus /Hornbeam/	100-125	0.45	4		40L/1.m	RB instant hedge-formed sections		30%	15	18	
TOTALS								100%	50	68	
ORNAMENTAL PERENNIAL											
Ornamental Grass Mix	Size	Ctr	Density	Pot Size	Notes			%Mix	Total length (m)	Quantity	
Carex morrowii 'Aureovariegata'	35-50	0.45	3	2L	Plant in groups of 3 and 5			50	0.2	30	
Carex morrowii 'IceDance'	35-50	0.45	3	2L	Plant in groups of 3 and 5			50	0.2	30	
TOTALS								100	0.6	60	
SPECIMEN PLANTING											
Carpinus Betulus-Pleached / Hornbeam	200cm	1	1	Potted	clear stem -120cm, stem 8/10cm Pleached tree	As shown on drawing			3		
Cornus sericea 'Flaviramea' /Golden twig dogwood/ (CsF)	80-100	0.8	1	20L	Branched: 3 brks				3		
Stipa tenuissima /Mexican feather grass/ (St)	40-60	0.4	6.25	10L	full pot				3		
Carex oshimensis 'Evergold'	35-50	0.45	3.5	3L	full pot, split equally into two beds				30		
Betula Utilis 'Jacquemontii' / Silver Birch	200cm	1	1	Potted	clear stem -150cm, stem 8/10cm Pleached tree				1		
Understorey Planting Mix 02											
Dryopteris erythrosae /Autumn fern/ (De)	40-60	0.4	6.25	10L	full pot		35%	4.2	9		
Hyacinthoides non-scripta /Bluebell/ (Hns)		0.1	100	bulbs	100mm, spaced out evenly.		10%	1.2	12		
Parthenocissus quinquefolia (Pg)	40-60	0.3	11.111	3L	full pot, min 3 breaks		15%	1.8	3		
Anemone x hybrida 'Honoree Jobert' (Azh)	60-80	0.4	5	10L	full pot		15%	1.8	9		
Asplenium scolopendrium /Hart's tongue fern/ (As)	40-60	0.4	5	10L	full pot		15%	1.8	9		
hellebore/ (Hvo)	30-40	0.3	6.25	5L	full pot		10%	1.2	8		
TOTALS							100%	12	50		
Woodland Bulb Mix 01- Under existing trees											
Galanthus nivalis /Common snowdrop/ (Gn)		0.2	25	bulbs	fbulbs; planting depth 80-150mm, spacing min 50mm, spaced out evenly.		50%	0.5	13		
Cyclamen coum /Eastern cyclamen/ (Co)		0.1	75	bulbs	bulbs; planting depth 50-75mm, spacing min		50%	0.5	38		
TOTALS							100%	1	51		
Wild Flower Meadow Grass Seed Mix for areas under existing trees											
-To be used for areas defined as 'Wildflower Meadow'											
-Source : (based on) Emorsgate Seeds EW1 Woodland Mixture											
-Sowing rate - 4g/m²											
Native Wild flower (20%)											
Allium ursinum / Ramsons /							% per Mix	m²			
Alliaria petiolata / Garlic Mustard/							1.0%	0.7			
Angelica sylvestris / Wild Angelica /							2.0%	1.4			
Anthriscus sylvestris / Cow Parsley /							0.5%	0.4			
Arum maculatum / Lords-and-Ladies/							1.5%	1.1			
Digitalis purpurea / Foxglove /							0.2%	0.1			
Eupatorium cannabinum / Hemp-agrimony/							4.0%	2.8			
Filipendula ulmaria / Meadowsweet /							0.1%	0.1			
Galium album / Hedge Bedstraw /							0.8%	0.6			
Geum urbanum / Wood Avenas/							1.5%	1.1			
Hyacinthoides non-scripta / Bluebell /							2.1%	1.5			
Primula vulgaris / Primrose /							1.6%	1.1			
Prunella vulgaris / Selfheal /							0.1%	0.1			
Ranunculus acris / Meadow Buttercup /							1.0%	0.7			
Silene dioica / Red Campion /							0.4%	0.3			
Teucrium scorodonia / Wood Sage /							3.0%	2.1			
							0.2%	0.1			
Grasses (80%)											
Agrostis capillaris /Common Bent/							20%				
Anthoxanthum odoratum /Sweet Vernal-grass/							2.4%	1.7			
Brachypodium sylvaticum – False Brome (w)							1.6%	1.1			
Cynosurus cristatus /Crested Dogtail/							0.8%	0.6			
Deschampsia cespitosa – Tufted Hair-grass (w)							48.0%	34.1			
Festuca rubra /Slender-creeping Red Fescue/							1.6%	1.1			
Poa nemoralis – Wood Meadow-grass							19.2%	13.6			
Totals							6.4%	4.5			
							80%				
							100%	71			
								18 sq.m			
</											