



OUTLINE SPECIFICATION:

- a. GENERAL
 - All works shall be in accordance all relevant British Standards and the Landscape Consultant's planting plans and shall comply with National Landscape Specification (NBS) 1998, latest revision.
- b. HEALTH AND SAFETY
 - The contractor shall familiarise themselves with the Health and Safety Plan and all risk assessments.
 - The contractor shall familiarise themselves with the location and nature of all hazards including services.
 - All appropriate precautionary steps shall be taken to protect workers when working in close proximity to hazards including services
- c. SETTING OUT
 - All dimensions and levels should be checked and adjusted on site.
 - The Contractor is responsible for locating and taking care around all services.
 - Do not scale from this drawing.
- d. PLANTING AREAS - SITE PREPARATION
 - All building rubble and any other extraneous material in excess of 50mm dimension to be removed, compaction ripped 150mm deep or broken out by JCB back-actor leaving surface rough.
 - The landscape contractor shall ensure that all subsoil areas are free of compaction and free draining prior to the placement of topsoil.
- e. TOPSOIL
 - Site won topsoil shall be clear of all weeds, roots, sticks and any other extraneous material.
 - Site won topsoil shall be clear of any stones exceeding 50mm in any direction.
 - Any shortfall of site won topsoil shall be made up with imported topsoil. Imported topsoil shall be general purpose Grade topsoil BS:3882 medium loam, not more than slightly stoney, pH 5.7-7.5.
 - Minimum depths:
 - 450mm to all planting areas.
 - 150mm to all grass.
 - Topsoil shall be cultivated and ameliorated prior to planting.
- f. TREE PITS
 - Size: 900x900x900mm or 100mm wider and deeper than root system, whichever is the greatest, and wide enough to accommodate roots when fully spread. Tree pits to be square not round.
 - Backfill mix: 30% Enmag P4 Compost (30%) incorporated into topsoil (70%) during planting.
 - Tree pits must be free draining. If, on excavation, the tree pit holds water seek the advice of the contract administrator and await further instruction before proceeding with planting.
 - Trees shall be watered to field capacity immediately following planting.
- g. PREPARATORY HERBICIDE TO ALL PLANTING
 - Weed allowed to grow and treated with up to three applications glyphosate prior to cultivation or planting during the fallow period.
- h. PLANT SUPPLY
 - Supplier: To be approved by the landscape architect and shall be a nursery listed in the Horticultural Trades Association Nursery Certification Scheme.
 - Plant material shall be in accordance with the HTA's National Plant Specification 1997. All plants shall be container grown, well formed and free from disease.
 - Plant handling to CPSE Plant Handling Code.
- i. PLANTING
 - Planting shall take place between November and March.
 - Planting areas shall be weeded to be weed free prior to planting.
 - Planting areas cultivated 300 mm deep and stone picked of any material greater than 50mm in any direction.
 - Approved planting compost and slow release fertiliser shall be incorporated into the topsoil during planting.
 - Planting beds shall be mulched with 75mm depth amenity grade bark mulch on completion.
 - Planting areas shall be watered to field capacity on completion.
- j. TREE STAKING
 - All trees: Short Double Staking unless stated otherwise.
 - Stakes shall be preservative treated softwood 100mm min diameter. Driven vertically 450mm into base of pit on either side.
 - Cross bar - timber, as stake. Secured with rubber J Tom's 37.5mm wide standard nylon reinforced rubberbelt ref L2 ties including rubber spacer pads ref L1.
- k. MAINTENANCE
 - All new and existing trees, planting and turfing shall be maintained for twelve months following practical completion by the landscape contractor.
 - Maintenance visits shall be every two weeks March to October inclusive. Maintenance visits shall be monthly for November to February inclusive.
 - All planting beds shall be weeded during each visit.
 - All lawn and amenity grass areas shall be mown to a height of 25mm on each visit. Arisings to be removed from site.
 - All litter shall be removed from site.
 - All new trees, planting and grass shall be watered sufficiently to ensure healthy establishment.
- l. DEFECTS LIABILITY
 - Twelve months on plant material and grass.
 - Replacements in November in year of loss.
- m. PLANTING
 - Planting shall take place between November and March.
 - Planting areas shall be weeded to be weed free prior to planting.
 - Planting areas cultivated 300 mm deep and stone picked of any material greater than 50mm in any direction.
 - Approved planting compost and slow release fertiliser shall be incorporated into the topsoil during planting.
 - Planting beds shall be mulched with 75mm depth amenity grade bark mulch on completion.
 - Planting areas shall be watered to field capacity on completion.

Copyright of this drawing is the property of Urban Edge Architecture Limited. It must not be reproduced or amended nor used in the execution of any works whether in conjunction with the proposed works for which it is prepared or otherwise without the express consent in writing of Urban Edge Architecture Limited.

UrbanEdge Architecture Limited
One Scotgate Mews, Scotgate,
Stamford, Lincolnshire, PE9 2FX.

Tel. +44 (0)1780 755665
Fax. +44 (0)1780 755360

DO NOT SCALE FROM THIS DRAWING - ALL DIMENSIONS TO BE CHECKED ON SITE, ANY DISCREPANCIES RAISED WITH URBAN EDGE

DRAWING TO BE READ IN COLOUR

KEY:

Application boundary

PLANTING

Existing tree to be Retained.

Proposed tree planting.

Proposed shrub and herbaceous planting.

PLANT SCHEDULE

TREES						
QTY	UNIT	CODE	PLANT NAME	STOCK	FORM	GIRTH/HEIGHT
2	No.	ACE CAM SW	Acer campestre 'Streetwise'	RB	STD	20-25cm
3	No.	BET PEN xhs16	Betula pendula	RB	STD	16-18cm
SHRUBS						
QTY	UNIT	CODE	PLANT NAME	STOCK	SIZE	SPACING
146	No.	Lon May 5L	Lonicera nitida "Maygreen"	C 5L	30-40cm	6/m2
16	No.	Ros MJU	Rosmarinus "Miss Jessops Upright"	C 5L	40-60cm	5/m2
HERBACEOUS PLANTS						
QTY	UNIT	CODE	PLANT NAME	STOCK	SPACING	
20	No.	Dry wal	Dryopteris wallichiana	C 5L	6/m2	
164	No.	Pac GC 3L	Pachysandra terminalis "Green Carpet"	C 3L	8/m2	
46	No.	Lib gra	Libertia grandiflora	C 2L	6/m2	

NOTES AND ABBREVIATIONS
 C = Container (or pot) grown, followed by size of the container (or pot).
 FORM = Shape of tree as supplied by the nursery.
 RB = Rootballed (balled and wrapped).
 SIZE = Height or Spread of juvenile plant.
 STD = (clear stem) Standard.
 STOCK = Root condition/protection method eg Bare root.
 - Refer to specification for further information.
 - All plants to be completely hardened off
 - Substitutions to be agreed with Landscape Architect.
 Plant Schedule generated by "Qscape" software 25/02/2025

P01	Planting updated	YH	25/02/25
P00	First Issue	YH	18/02/25
Rev No	Description	Drawn By	Date



Client
BKUK GROUP LIMITED

Project
BURGER KING BARNSELY

Drawing
DETAILED PLANTING PLAN

PLANNING						
Uf Price No	Scale	Date	Drawn	Status	Revision	
2763	1:200 @ A1	FEB 2025	YH	-	P01	
Project / Organisation / Drawing System / Level / Type / Date / Revision						
2763-URB-BA-00-DR-L-208151						

