Proposed Site Plan
1:250

TREE SCHEDULE

Plan Preview	Code	Latin name	Girth/ cn	Height, cm	Specification	Quantity
	AC	*Acer campestre*	*14-16*	*350-400*	*Clear Stem min. 200 :3 brks :26 in. diam. ball :3x Advanced Nursery stock*	*3*
	AL	*Amelanchier lamarckii*	*14-16*	*350-400*	*Clear Stem min. 200 :3 brks :26 in. diam. ball :3x Advanced Nursery stock*	*1*
	BP	*Betula pendula*	*10-12*	*350-400*	*Clear Stem min. 200 :3 brks :26 in. diam. ball :2x*	*3*
	CBF	*Carpinus betulus 'Fastigiata'*	*14-16*	*350-400*	*Slender, upright form — with single, dominant leader. 26 in. diam. ball : 3x Advanced Nursery stock*	*5*
	CC	*Corylus colurna*	*14-16*	*350-400*	*Clear Stem min. 200 :3 brks :26 in. diam. ball :3x Advanced Nursery stock*	*1*
	CLG	*Chamaecyparis lawsoniana 'Green Pillar'*	*14-16*	*350-400*	*Slender, upright form — with single, dominant leader. 26 in. diam. ball : 3x Advanced Nursery stock*	*4*
	CLI	*Chamaecyparis lawsoniana 'Intertexta'*	*14-16*	*350-400*	*Slender, upright form — with single, dominant leader. 26 in. diam. ball : 3x Advanced Nursery stock*	*1*
	CM	*Crataegus monogyna*	*14-16*	*350-400*	*Clear Stem min. 200 :3 brks :26 in. diam. ball :3x Advanced Nursery stock*	*1*
	CSS	*Cupressus sempervirens 'Stricta'*	*14-16*	*350-400*	*Slender, upright form — with single, dominant leader. 26 in. diam. ball : 3x Advanced Nursery stock*	*3*
	FSA	*Fagus sylvatica 'Atropurpurea'*	*14-16*	*350-400*	*Clear Stem min. 200 :3 brks :26 in. diam. ball :3x Advanced Nursery stock*	*1*
	FSP	*Fagus sylvatica 'Pendula'*	*14-16*	*350-400*	*Clear Stem min. 200 :3 brks :26 in. diam. ball :3x Advanced Nursery stock*	*1*
	JCO	*Juniperus chinensis 'Obelisk'*	*14-16*	*350-400*	*Slender, upright form — with single, dominant leader. 26 in. diam. ball : 3x Advanced Nursery stock*	*4*
	LS	*Liquidambar styraciflua*	*14-16*	*350-400*	*Clear Stem min. 200 :3 brks :26 in. diam. ball :3x Advanced Nursery stock*	*6*
	SA	*Sorbus aucuparia*	*14-16*	*350-400*	*Clear Stem min. 200 :3 brks :26 in. diam. ball :3x Advanced Nursery stock*	*1*
	SB	*Salix babylonica*	*14-16*	*350-400*	*Clear Stem min. 200 :3 brks :26 in. diam. ball :3x Advanced Nursery stock*	*1*
	TCS	*Tilia cordata 'Streetwise'*	*14-16*	*350-400*	*Clear Stem min. 200 :3 brks :26 in. diam. ball :3x Advanced Nursery stock*	*4*
						40

This document is © Bond Bryan Architects Ltd.
If in doubt ASK. Drawing measurements shall not be obtained by scaling. Verify all dimensions prior to construction.
Immediately report any discrepancies on this document to the Originator. This document shall be read in conjunction with associated models, specifications and related consultants' documents.

Key plan

North

N

1:500 0 10 20 30m

Legend

- Total curtilage including adopted highway
- Developable area
- North-Eastern Highways Area*
- Electrical cable easement areas
- Proposed hard surfaces
- Proposed soft landscape areas
- Proposed shrub planting areas

Existing vegetation
Ref to *Arboricultural Impact Assessment & Preliminary Arboricultural Method Statement* by Thompsons Consultancy

- Existing vegetation. Category A
- Existing vegetation. Category B
- Existing vegetation. Category C
- Existing vegetation. Category U
- Existing vegetation. Root Protection Area
- T4: Cat C — Existing vegetation to be removed

Rev	Description	Drawn	Checked	Date
P03	Amendments to species quantities	AF	BBA	03/07/2025
P02	Stage 4 issue	AF	SR	19/02/2025
P01	Issued for Planning- Stage 3	TT	SR	16/07/2024

B O N D B R Y A N
e info@bondbryan.co.uk
w www.bondbryan.co.uk

Barnsley Metropolitan Borough Council

BARNSLEY Metropolitan borough council — Currie & Brown

Barnsley Levelling Up Fund
Youth Zone Activity Park

Soft Landscaping Strategy. Tree Plan and Schedule

Originator project ref: **23048**
Purpose of issue: **For information**
Scale(s): **1:250**
Paper size: **A0**
Revision description: **Preliminary**

project originator volume level type role number: **BALU - BBA -YAP- XX - DR - L - 2001**
revision: **P03**

Name model: 23048-model-yap-xx-m3.rvt