



DRILLING LOG SHEET

SITE: Edward road

CREW INITIALS: NP

RIG: SM400

LEAD DRILLER INITIALS

GP

LEAD DRILLER SIGNED

DATE: 9-2-22

SHEET: 1 OF 1

EQUIPMENT USED:

BH	DEPTH	STRATA DESCRIPTION
1	000 - 0.90	made ground
	0.90 - 2.70	clay
	2.70 - 4.80	mudstone brown
	4.80 - 30.00	mudstone grey
2	000 - 0.70	made ground
	0.70 - 2.20	clay
	2.20 - 4.40	mudstone brown
	4.40 - 15.00	mudstone grey
2A	000 - 0.70	made ground
	0.70 - 2.20	clay
	2.20 - 3.00	mudstone brown
Install 2.00 mt slotted pipe 1.00 mt plain pipe Gravel 3.00 mt to 1.00 mt Bentonite 1.00 mt to 0.00 mt 1 end cap 1 gas tap Concrete in 1 cover		
3	000 - 0.80	made ground
	0.80 - 2.10	clay
	2.10 - 4.50	mudstone brown
	4.50 - 15.00	mudstone grey
4	000 - 0.60	made ground
	0.60 - 1.90	clay
	1.90 - 5.00	mudstone brown

BH	DEPTH	STRATA DESCRIPTION
	5.00 - 15.00	mudstone grey
4A	000 - 0.60	made ground
	0.60 - 1.90	clay
	1.90 - 3.00	mudstone brown
Install 2.00 mt slotted pipe 1.00 mt plain pipe Gravel 3.00 mt to 1.00 mt Bentonite 1.00 mt to 0.00 mt 1 end cap 1 gas tap Concrete in 1 cover		
5	000 - 1.10	made ground
	1.10 - 2.40	clay
	2.40 - 4.20	mudstone brown
	4.20 - 15.00	mudstone grey
5A	000 - 1.10	made ground
	1.10 - 2.40	clay
	2.40 - 3.00	mudstone brown
Install 2.00 mt slotted pipe 1.00 mt plain pipe Gravel 3.00 mt to 1.00 mt Bentonite 1.00 mt to 0.00 mt 1 end cap 1 gas tap Concrete in 1 cover		

BH	CASING DIA	CASING DEPTH

GAS READING

TOTALS	BH's	DRILL	CASE	CORE
TODAY	8	99		
PREVIOUS	-	-		
TO DATE	8	99		