

Your ref IFS-RBS-SUB-11-0031530

Our ref SM3568INF


Geo-Serv Limited
17 Hoveden Road
London NW2 3XE

monitoring 020 8208 0343 ↩

general enquiries 020 8208 4476

e-mail: mon@geo-serv.com

Consulting
Civil and
Geotechnical
Engineers



GEO-SERV

Innovation Property (UK) Ltd,
3 Smiths Way
Grove Park
Enderby
Leicester LE19 1SX

Issue date: 16/07/2014

following survey No: 10

Monitoring Plus Report

Owners name	Dr John Harban	Suspected cause	Root-induced shrinkage	Monitoring type	Levels
Address	The Gables □ Carlton Road □ Carlton, □ Barnsley S71 3JD	Principal area of damage	To be advised	Installed	17/08/2012
		Damage category	To be advised	No of visits / weeks	tbc @
		Surface geology	To be advised	Completion date	tbc
				Status	
Home phone	01226728876 (day) □ 01226728876 (eve)	Feedback from last visit			
Work phone	07775558931 □ johnharban@harban.fsnet.co.uk				
Correspondence address		Sketch showing location of monitoring points			
Comment	<div>Max movement 0.0</div> <div>Focal area</div> <div>16/07/14 - Results to date show small seasonal movements (especially Pts 8 & 9) consistent with soil shrinkage in summer and swelling in winter</div>				

Level monitoring results

Survey:	1		2		3		4		5	
By:	BL		BL		BL		BL		BL	
Date:	17/08/2012		23/10/2012		07/01/2013		10/04/2013		28/05/2013	
Point ID	levels	chngs	levels	chngs	levels	chngs	levels	chngs	levels	chngs
	mm	mm	mm	mm	mm	mm	mm	mm	mm	mm
1	1000.00	0.0	1000.00	0.0	1000.00	0.0	1000.00	0.0	1000.00	0.0
2	259.45	0.0	259.49	0.0	262.06	2.6	263.10	3.7	263.42	4.0
3	259.99	0.0	258.87	-1.1	261.28	1.3	262.58	2.6	263.01	3.0
4	290.38	0.0	289.29	-1.1	291.79	1.4	293.39	3.0	293.65	3.3
5	546.86	0.0	546.44	-0.4	546.20	-0.7	547.02	0.2	546.94	0.1
6	356.50	0.0	356.77	0.3	355.82	-0.7	356.82	0.3	356.14	-0.4
7	857.19	0.0	856.93	-0.3	856.29	-0.9	857.51	0.3	857.48	0.3
8	360.16	0.0	357.17	-3.0	360.10	-0.1	363.01	2.9	363.15	3.0
9	236.58	0.0	234.56	-2.0	238.78	2.2	241.31	4.7	241.14	4.6

closing error (mm)

-0.09

0.49

-0.42

-0.20

-0.50

Survey:	6		7		8		9		10	
By:	BL		BL		BL		BL		BL	
Date:	25/07/2013		24/09/2013		03/12/2013		20/05/2014		16/07/2014	
Point ID	levels	chngs	levels	chngs	levels	chngs	levels	chngs	levels	chngs
	mm	mm	mm	mm	mm	mm	mm	mm	mm	mm
1	1000.00	0.0	1000.00	0.0	1000.00	0.0	1000.00	0.0	1000.00	0.0
2	263.97	4.5	261.16	1.7	256.90	-2.5	261.09	1.6	262.32	2.9
3	260.70	0.7	255.57	-4.4	256.82	-3.2		#N/A	260.61	0.6
4	292.61	2.2	287.58	-2.8	289.59	-0.8	293.16	2.8	293.88	3.5
5	547.71	0.8	547.17	0.3	546.68	-0.2	547.20	0.3	548.10	1.2
6	356.97	0.5	356.58	0.1	355.71	-0.8	356.74	0.2	356.98	0.5
7	857.26	0.1	855.70	-1.5	855.21	-2.0	856.74	-0.5	856.36	-0.8
8	357.63	-2.5	349.02	-11.1	351.63	-8.5	360.05	-0.1	358.44	-1.7
9	237.35	0.8	230.09	-6.5	229.22	-7.4	236.55	0.0	235.67	-0.9

closing error (mm)

0.27

-0.03

0.05

0.35

0.01

