



ELEVATION

CAREFULLY TAKE DOWN EXISTING BOUNDARY HEDGE AND CART AWAY.

EXCAVATE GROUND TO A DEPTH OF 450MM MIN TO FIRM LOAD BEARING STRATA.

LAY CONCRETE FOUNDATION 1:2:6 CEMENT:SAND AGGREGATE, 200MM THICK AND 300MM WIDER THAN THE PROPOSED WALL (EQUAL WIDTH EITHER SIDE OF CENTRE LINE OF WALL).

CONSTRUCT NEW BOUNDARY WALL USING 65MM FACING BRICKS TO MATCH EXISTING WITH DOUBLE CANT COPING/HEADER COURSE . INSERT EXPANSION JOINTS USING FIBRE BOARD FOR SPACING AND FILL WITH POLYSTYRENE WASTE AT SPACINGS OF NO MORE THAN 6M. COLOURED MORTARS FROM THE TILCON RANGE OR SIMILAR APPROVED. WEEDHOLES MAX 900 CENTRES, INCLUDE FOR PEDESTATED LAND DRAIN BEHIND WALL WHERE GROUND LEVEL IS HIGHER.

WALLS TO BE 215MM SOLID BRICK IN EQUAL BTH GARDEN WALL BOND, 6 STRETCHER COURSES TO ONE HEADER COURSE.

BRICK PILLARS WITH PYRAMID 330X440MM AND 440X330MM GATE PILLAR CAPS.

FABRICATION OF GATES AND RAILINGS ARE TO INCORPORATE A FRAMEWORK OF 40MM X 10MM FLAT BAR WITH 16MM ROUND INFILL BARS. INSTALLATION OF THE GATES TO INCLUDE 50MM X 50MM STEEL POSTS FOR PEDESTRIAN GATES (70MM X 70MM STEEL POSTS FOR DOUBLE / 24-FOLD / DRIVEWAY GATES) ANCHORED ON TO THE PILLARS AND BEDDED INTO CONCRETE TO A DEPTH SUFFICILE TO CARRY THEIR WEIGHT. ALL RAILWORKS TO BE GALVANISED AND POWDER COATED.

BOTTOM OF GATES TO FOLLOW BAKE OF GROUND LEVEL.

SECTION

Revisions		A. A----	00-00-
This drawing is for planning permission only and is not a construction drawing.			
Drawing Title		PROPOSED-ELEVATION-SECTION	
Job No. - Dwg No.	SC/2013/4		—
Client:	PAUL RONKSLEY 1 RYTON AVENUE WIMBORNE SP7 9SD		
Scale.	1:50		