


FIRE KEY:

- ONE HOUR FIRE RATED WALL CONSTRUCTION
- HALF HOUR FIRE RATED WALL CONSTRUCTION
- 30 MINUTE FIRE DOOR WITH SELF CLOSING MECHANISM & SMOKE SEALS
- 30 MINUTE FIRE DOOR WITHOUT SELF CLOSING MECHANISM OR SMOKE SEALS
- FD20
- FD30S
- ESCAPE

- MINOR INDICATED IS TO BE SURFACE ROUTE AS SHOWN IN APPROVED DOCUMENT B. OPENING LIGHT W/IN AREA OUTSIDE W/IN HEIGHT OR WITH CLEAR OPENING W/IN 1100mm ABOVE FLOOR.
- MAINS OPERATED INTERLINKED SMOKE ALARM.
- MAINS OPERATED INTERLINKED SMOKE ALARM.
- NOTE THAT ALL ELEMENTS SEPARATING DIFFERENT BUILDINGS SHOULD BE OF MINIMUM 1 HOUR FIRE RESISTANCE. ELEMENTS TO BE MIN. 30 MINUTES FIRE RESISTING UTILISING EITHER INTUMESCENT PAINT OR PLASTERBOARD UNITS IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS AND RECOMMENDATIONS.
- FIRE ALARM SYSTEM / AUTOMATIC DETECTION TO BS 5839 Pt 1 1989.
- THE WALLS TAKEN UP TO O/S OF FLOOR OR THROUGH CEILING AND FIVE METERS TO SMOKE RESISTANCE TO WALL.
- THE SYMBOLS INDICATED ON THE DRAWING DO NOT RELATE TO A SPECIFIC NUMBER OF FITTINGS REQUIRED TO COVER A WALL AREA. ALL FITTINGS ARE TO BE SIZED TO SUIT THE AREA COVERED. ALL FITTINGS ARE TO BE SIZED TO SUIT THE AREA COVERED. THE INSTALLER IS TO PROVIDE INSTALLATION AND COMMISSIONING TESTS CERTIFICATES TO SHOW COMPLIANCE WITH THE RELEVANT BRITISH STANDARDS AND TO THE SATISFACTION OF THE LOCAL FIRE AUTHORITY.
- PROVISION OF ALL FIRE DETECTION, ALARM SOUNDS, DISCREPANCY AND INSTALLATION, ALL DRAWINGS TO BE SUBMITTED TO FIRE OFFICER PRIOR TO INSTALLATION FOR APPROVAL.



Coda Studios Ltd
70-71 Cornish Place, Cornish Street,
Sheffield, S6 3AF
Tel: 0114 2796003
email: info@coda studios.co.uk

Client	Coalfields Regeneration Trust
Job	Washington Road, Goldthorpe
Plans	Bamsley
Ap't Type 01	Title

DRAWN	CHECKED	DATE	SCALE	AS ISSUE	AT ISSUE
MH	PH	JULY 2015	1:100		1:50
REVISION	DRAWING STATUS				
B	-				2334-102

© COPYRIGHT. EXISTING ON THE REVISION AND INFORMATION SHOWN ON THIS DRAWING. The Contractor must verify all dimensions on site before making shop drawings. Architect to be notified of any discrepancies in dimensions immediately.