



- BARNSELY MBC HIGHWAY NOTES**
- TREE ROOT BARRIERS REQUIRED FOR ANY TREES LOCATED WITHIN 3m OF THE PROSPECTIVELY ADOPTABLE HIGHWAY.
 - NO UNBOUND MATERIAL TO BE INSTALLED WITHIN 2m OF THE PROSPECTIVELY ADOPTABLE HIGHWAY.
 - CBR'S TO BE UNDERTAKEN ON ROAD FORMATION LEVEL AT 20m INTERVALS, USING A 90mm DIA PLATE. THE RESULTS OF WHICH ARE TO BE PROVIDED TO BMBC HIGHWAYS' ENGINEER FOR REVIEW ALONG WITH A LOCATION PLAN.
 - CCTV SURVEY OF ALL HIGHWAY DRAINAGE IS TO BE PROVIDED TO BMBC HIGHWAYS FOR REVIEW PRIOR TO ISSUE OF A PART 1 CERTIFICATE AND PRIOR TO FINAL ROAD SURFACING.

KEY

- CARRIAGEWAY (TARMAC)
- CARRIAGEWAY (BLOCK PAVED)
- FOOTWAY
- VERGE (BLOCK PAVED)
- PROPOSED HIGHWAY GULLY
- SITE BOUNDARY

STREET LIGHTING KEY

- DENOTES EXISTING COLUMN TO BE REMOVED.
- DENOTES NEW 6m GALVANISED STEEL COLUMN WITH LANTERN COMPLETE WITH ELECTRONIC PEC.
- DENOTES NEW 8m GALVANISED STEEL COLUMN WITH LANTERN COMPLETE WITH ELECTRONIC PEC.

REFER TO BARNSELY MBC DRAWING SL20-109, 1300, 1' STREET LIGHTING PROPOSALS FOR FULL DETAILED OF PROPOSED STREET LIGHTING DESIGN

P1	15.08.25	Preliminary Issue	GW	PB	PB
Issue	Date	Description	By	Chkd	Appd



Client
BELLWAY HOMES

Job Title
HOYLAND BARNSELY

Drawing Title SECTION 38 AGREEMENT	
Scale at A1 1:500	
Drawing Status PRELIMINARY	
Job No 25035	Issue P1
Drawing No 111	

Do not scale