
INFORMATION WITHIN THIS DRAWING IS NOT NECESSARILY PRODUCED TO SCALE.
ALWAYS USE FIGURED DIMENSIONS AND CO-ORDINATES - IF IN DOUBT, ASK.



Street Lighting Arrangement

LN3

Denotes 6M galvanised steel column with AriaLED 30 lantern complete with electronic PEC. NL denotes new lantern and NLC dentes new lantern and 6 metre column

All materials to comply fully with current BMBC Street Lighting Specification.

It is the responsibility of the developer to advise their clients of the location of street lighting columns relative to their property and to programme column installation works commensurate with property occupation.

Column positions may be adjusted slightly to suit site conditions and services, but must not normally be erected within 500mm of defined driveway boundaries.

BMBC will not enter into third party discussion on column positions, any such discussion will be carried out between BMBC and the developer.

The street lighting columns and lanterns and their maintenance remain the responsibility of the developer until completion of the adoption process.

All lighting columns are to be provided with an unmetered single phase electricity supply via the REC cable network.
It is expected that the developer will coordinate with the REC regarding the installation of any cable ducts they may require.

NOTES

KEY:

- Proposed Adoptable Carriageway - Type 5B
- Proposed Adoptable Carriageway - Type 5A
- Proposed Adoptable Footway/Margin
- Proposed Drive crossing of Footway/Margin
- Proposed tactile paving
- Proposed gully.
- Surface water sewer.
- Site Boundary

REV	DESCRIPTION	SIG	CHK	DATE
A	First Issue.			
B	Revised to suit latest layout.	RH	CH	20.05.21
C	Raised table removed	CH	PR	24.05.21

DUCHY HOMES

MOUNT VERNON
WORSBOROUGH

S38 LAYOUT

Eastwood & Partners
CONSULTING ENGINEERS
St. Andrew's House
23 Kingfield Road
Sheffield
S11 9AS
Tel 0114 255 4554
Fax 0114 255 4330
mail@eastwoodandpartners.com
www.eastwoodandpartners.com

SCALE WHEN PLOTTED AT A1	DRAWING STATUS
1:500	PRELIMINARY

DRAWN	CHECKED	DATE	DRAWING NUMBER	REV
RH	CH	01.05.21	45521/103	C