PLANTING NOTES

Subsoil: Should be ripped and free draining

Topsoil: Planted areas to be cultivated to an approximate depth of 150mm prior to planting (any existing weedgrowth to be treated with a Glyphosate based herbicide no less than 14 days prior to cultivation).

Trees: To be planted it pits exceeding dimensions of root system by 100mm in each direction. Bottom of pit to be broken up to aid drainage. Peat free compost to be incorporated into the backfill. Trees to be secured using 75mm diameter pressure treated timber stake and tied at low level. Trees should not be planted within 5m of a building. Root barrier to be installed where trees planted adjacent services.

Shrubs: To be planted it pits exceeding dimensions of root system by 50mm in each direction. Peat free compost to be incorporated into the backfill.

Bark mulch: Planted areas to be dressed with bark mulch to a settled depth of 50mm.

General: All planting material to be true to type and size and in accordance with BS 3969-1 1992. Plant stock to be watered to field capacity on completion of works and watered regularly especially during periods of warm/dry weather.

LEGEND

- Trees
- Specimen shrubs
- Shrub beds (frontage)
- Shrub beds (rear gardens)
- Hedgerows
- Turf/Seed
- Gravel
  20mm Cotswold chippings with geotextile membrane under

Refer to layout no. G3HO/OXSP/002 for planting schedule



Rev A: Tree to front plot 4 removed
Turf/plants removed to front plots 5-7 and replaced with gravel

PHOENIX
LANDSCAPE SERVICES LTD
Unit 22 New Mesters, 53 Mowbray Street, Sheffield S3 8EN
Tel 0114 400 0112 / 07903 155398
info@phoenixls.co.uk / www.phoenixls.co.uk

Client	G 3 Homes Ltd
Project	Roughbirchworth Lane, Oxspring, Penistone, Sheffield S36 8YE
Title	Soft Landscape Proposals

Layout number	Rev	Drawn by	Date
G3HO/OXSP/001	A	AM	30/11/2020

DO NOT SCALE FROM HARD COPY