

SITE: 37 TIVYDALE, CAWTHORNE

DATE OF SURVEY: 5 JUNE 2008

Tree No.	Species	Height m	Stem diameter mm	Branch spread m	Crown clearance m	Age Class	Physiological condition	Category grading	Life Expectancy years	Notes/Structural condition	Preliminary management recommendations
T1	Birch	6	120	N - E - S - W -	-	Y	P	R	1	Virtually dead	Remove
T2	Willow	4.5	110	N 1 E 1 S 2 W 2	1.5	Y	F	C	3	Young tree no value	No action/remove
T3	Willow	4.5	140	N 1 E 2 S 1.5 W 1.5	1.5		F	C	3	Young tree no value	No action/remove
T4	Oak	3	50	N 0.5 E 0.5 S 0.5 W 1	0.5	Y	F	C	3	Young tree of no value	No action
T5	Sycamore	3	40	N 1 E 0.5 S 1 W 0.5	1	Y	F	C	3	Young tree of no value	No action
T6	Thorn	5	Multi-stem 400 at g/l	N 2 E 2 S 2.5 W 2.5	-	MA	P	C	2	Poor tree no value	Remove
T7	Pear	4	160	N 2 E 1 S 0.5 W 2	1	MA	P	C	2	Poor tree no value	Remove

T8	Pear	3	250	N 1.5 E 3 S 2 W 3	1	MA	P	C	2	Poor tee no value	Remove
T9	Cupressus	4.5	160	N 0.5 E 0.5 S 0.5 W 0.5	0.5	MA	P	C	2	Poor tee no value	Remove
T10	Spruce	6	290	N 2.5 E 2.5 S 2.5 W 2.5	-	MA	F	B	3	Good shape, appears sound	Retain if possible
T11	Cupressus	5	260	N 0.5 E 0.5 S 0.5 W 0.5	-	MA	F	C	3	Appears sound	No value
T12	Cupressus	5.5	250	N 0.5 E 0.5 S 0.5 W 0.5	-	MA	F	C	3	Appears sound	No value
T13	Fir	6	280	N 1.5 E 1.5 S 1.5 W 1.5	-	MA	F	B	3	Good shape, appears sound	Retain if possible
T14	Oak	9	340	N 3 E 3 S 3 W 4	2	MA	G	B	4	Sound	Retain if possible
T15	Laburnum	5	Multi- stem 340 at g/l	N 3.5 E 3 S 3 W 3	-	O/M	F	C	2	Leans, Some dead wood in crown, of little value	No action

T16	Pear	5	220	N 3 E 2 S 2 W 2	2	O/M	P	R	1	Poor shape, much dead wood, no value	Remove
T17	Pear	2.5	100	N 1 E 0.5 S 1 W 2	1.5	MA	P	R	1	Poor shape, much dead wood, no value	Remove
T18	Cherry	3	Multi- stem 200 at g/l	N 3 E 2.5 S 3 W 2	-	MA	P	R	2	Poor shape, much dead wood, no value	Remove
T19	Pear	4	170	N 2 E 1 S 2 W 2	1	MA	P	C	2	Poor shape, no value	Remove
G1	Thorn	3	0.75 average	N 2 E 1 S 2 W 1	Ground level	Y	F	C	2	Group of young thorn, no value	Remove if necessary
G2	Cuppressus	5/6	200 average	N 1 E - S 1 W -	Ground level	MA	F	C	3	Group of 9, no value	Remove

EXPLANATION OF TERMS AND ABBREVIATIONS

Height	Estimated approximately in metres
Stem diameter	Measured at 1.5 metres above ground level in millimetres
Branch spread	Measured at the crown's widest point in metres
Crown clearance	Estimated in metres above adjacent ground level
Age Class	Y – Young MA – Middle Aged M – Mature O/M – Over-mature V - Veteran
Physiological condition	Tree's Condition G – Good F – Fair P – Poor
Category grading	A – High quality and value B – Moderate quality and value C – Low quality and value R – Trees for removal
Life Expectancy	Tree's Expected Remaining Life 1 – 0 - 10 years 2 – 10 - 25 years 3 – 25 - 50 years 4 – 50+ years
Notes/Structural condition	eg, description of tree, collapsing, decay, physical defect, sound
Preliminary management recommendations	eg. further investigations, prune, remove dead wood, no action