

Side Elevation
As Proposed




Front Elevation
As Proposed



Side Elevation
As Proposed

0 0.51m 2m 5m

1:100



Side Extension Section

Tree

Tree

Tree

Assumed underground drainage runs. Contractor to confirm on site prior to commencement of any works.

I.C.

New Gate Access

New Vehicle Access

New Hedging

Existing Above and Below Drainage to be adapted and reconfigured as necessary

4153

1913

Air Source Heat Pump

Dry

Wash

Dish

Rooflight

Shower

Covered Porch

Corner Post

2075

Low wall detail

2700

External Seating
Permeable paving

Proposed Car Parking
Permeable paving

7000

4000

Tree

Tree

Tree's and canopy to be reduced (subject to TPO)

Tree

Tree

Tree

Tree



Rear Elevation
As Proposed

Garage

Beams Over

Kitchen
Kitchen layout shown indicative

Fridge

Freeze

Breakfast Bar

Pocket Door

Cill level reduced

Entrance Hall

Edge of existing window

New brick arch formed over

Lounge

Rooflight

New Window

Wall removed

Beams Over

Chimney removed

Vaulted ceiling Over

Beams Over

5470

Store

Dining

Hall

Study

Door swing revised

RWP

RWP

RWP

RWP

Matching window

2925

Paving extended around the side extension

New Hedging

New Hedging



Rear Extension Section
As Proposed

Proposed Materials

Proposed Walls - Multi Red Brickwork & light render to match
Proposed Roof - Roof Slate to match
Proposed External Windows - White framed to match
Proposed External Doors - Timber
Proposed Rainwater Goods - Black Plastic
Proposed Fascias - Black Timber

0 0.5m 1m 2m 5m

1:50

DATE	NOTES	BY	REV
07/12/22	For Planning	MS	A

Architectural

Phone: 0114 350 3415 Email:info@cka.design www.ckarchitecturalsheffield.co.uk

PROJECT TITLE **Proposed Side & Rear Extension's, Plus Internal Remodeling**	CLIENT **BARRY. 70 Church Street, Brierley, S72 9JG.**		
DRAWING STAGE **Planning**	SCALE **1:50/100 @ A1**	CHK **-**	DRAWN BY **MS**
SHEET TITLE **Plans & Elevations as Proposed.**	PROJECT NUMBER **572-3384**	STAGE **PLN**	REV **A**
			SHT **002**