

KEY

- Private surface water sewer and chamber.
110mm dia UPVC unless stated otherwise.
- Private foul water sewer and chamber.
110mm dia UPVC unless stated otherwise.
- 110mm HDPE bottle gully to EN1401-1
- 300x600 HDPE yard gully to EN1401-1
(for large shared drive areas)
- Rodding Eye.
- Proposed foul drag out manhole
- Proposed storm drag out manhole

NOTES

All works to comply with Building Regulations Approved document Part H.

Drainage points shown are approximate and should be checked against the house type working drawings.

All existing drainage to be checked for line and level prior to commencement.

Invert levels shown indicate the invert level of the main channel within the chamber. Branches connect at +50mm. At changes of direction the main channel is to be used with bends outside the chamber. Branches not to be used for changes of direction.

Preliminary

A		Plus 3034 floor levels amended		4:7:19	ASJ
Rev		Details		Date	Drawn/Chk
Hoover Limited					
Pearsons Crescent					
Wombwell, Barnsley					
Plot Drainage					
Sheet 1					

Dwg No. : STE/19/06/02/01 A

Date : 27-2-19

Scale : 1:200

Copyright © Shaun Tonge Engineering

SHAUNTONGEENGINEERING

11 Broomfield Road, Wombwell, Barnsley, S73 1SA.
Tel 01226 755926, Mobile 077262 278070. Email shauntongeengineering@btconnect.co.uk

