





(GREGGS)



KEY:-

-  9no. – Existing Street Lighting Columns to disconnect and remove to tip at Smithies Depot (D denotes Disconnection. 'x' denotes number)
-  10no. – Proposed 10 metre Steel column with Urbis Axia 3.2 5295 800ma 10.54 Klmm Type A (LED) lantern and electronic PCU (N denotes New. 'x' denotes number)
-  7no. – Existing Street Lighting Columns to Remain. Old Lanterns to be removed to tip at Smithies Depot. Existing column to be fitted with Urbis Axia 3.2 5295 800ma 10.54 Klmm Type A (LED) lantern and electronic PCU (E denotes Existing. 'x' denotes number).
-  1no. Existing Street Lighting Column assumed to be Privately Owned by ASDA. Shown on drawing for reference only. Contractor to make own arrangements with ASDA regarding disconnection and re-installation. (P denotes Private. 'x' denotes number)

NOTES:-

1. The symbols used on this drawing to show Street Lighting Column Positions have been enlarged for clarity and are not to scale.
2. All setting out and exact positions to be agreed on site by Barnsley Council Street Lighting Section prior to start. Allow at least 2 clear working days to attend site.
3. Street Lighting Columns shall only be planted in the ground once Kerbs and Edgings (Pin Kerb) have been installed establishing both line and level (or walls to rear of footways have been built) and the ground construction is up to (and including) sub-base level.
4. All disconnections and connections of new Street Lighting Columns to be co-ordinated by Barnsley Council.
5. New Electrical Mains installation and any diversion or removal works to be co-ordinated by the Principle Contractor.
6. Temporary Lighting must be provided by the Principle Contractor where existing Street Lighting is removed from service and areas of Highway are in blackout during hours of darkness.
7. Sub-Service ducting for Traffic Signs is not shown on this drawing. Routes and positions are to be agreed with Barnsley Council Street Lighting section when Traffic Sign information is finalised. The Ducting may be installed by the Contractor to the requirements of Barnsley Council and NPG Standards. All cabling for Electrical work must be carried out Barnsley Council Street Lighting Section.


(ASDA STORE)

Exit from ASDA

Canal Street / Entrance to ASDA

A61 Old Mill Lane

(B&M STORE)

A	SC	All Lanterns wider optic 5295	12th Oct 2021
--	SC	First Issue	October 2021
Rev	By	Revision Details	Date
			
Project			
A61 CORRIDOR - PHASE 1 OLD MILL LANE BRIDGE UPGRADE AND WIDENING			
Title			
STREET LIGHTING SITE CLEARANCE & PROPOSED Revision A			
Scale	Drawn	Checked	Date
1:500	SC		12.10.21
Drawing No.			Rev
A1 SL20-57/1300/01A			A