The quote summary

General Specification:

To supply and install ball stop fencing consisting of the following to southern boundary:

98m long x 20m high tower fencing to sports ground.

Price inclusive of labour, materials & Delivery, ex vat [redacted]

Material Specification:

Supply and install cricket ball stop fencing 98m long x 20m high. Fencing to consist of 4no x 20m high galvanised triangular lattice towers bolted to galvanised stubs set inside concrete foundations at circa 30m centres. High tensile galvanised cable rope secured horizontally between lattice towers at 5m centres. HDPE black knotted netting secured to line wires using UV resistant cable ties. Weak link system incorporated in netting where wind speeds exceed 75mph the nets will fall free of towers guaranteeing structural integrity.

To supply and install ball stop fencing consisting of the following to western boundary:

110m long x 12m high steel SHS fencing to sports ground.

Price inclusive of labour, materials & Delivery, [redacted]

Material Specification:

Supply and install cricket ball stop fencing 12m high x 110m long. Steel UC support columns set inside concrete foundations at 10m centres. Steel SHS posts 12m long bolted inside support columns. All steels finished galvanized only. Galvanised line wires tensioned horizontally between uprights at 2m centres. HDPP 50mm knotted cricket netting secured to line wires using carbine hooks.

TOTAL QUOTE: [redacted]

Valid for 30 days from date of quotation