DRAINAGE

38mm to L.G. with 75mm outrayken traps. No waste to discharge into stack within 200 mm of centre line of W.C. inlet to stack. Building open to changes in direction. Stub stack with air admittance valves on under stair case. Half hour fire collar to foul pipe entering and existing garage. Foundations taken below level of any drains. Drains to be installed over through walls. 100mm plastic underground drainage for new sections, fitted as installed to manufacturer instructions.

Drain runs shown are assumed.

VENTILATION.

Ventilation of habitable rooms by means of vent openings having an open area equal to 1/20 of floor area. Trickle vents to give 5,000 mm².

Ventilation to L.F. via an extractor extracting at a rate of 6 litres per second (maybe operated intermittently and timed over run time. Extractor linked to light switch).

GENERAL.

Safety glass fitted to all doors with glazing incorporated and glazing within 300mm of a door. Double glazing to give U value of 1.6 W/m²k (28mm units).

Electrical work to be carried out/meet requirements of Part P (electrical safety) and will require electrical installation certificate issuing.

Steelwork to have half hour fire protection, consisting 12.5mm fireline plasterboard and plaster skim finish.

Calculations to be supplied for steelwork and roof construction by client/contractor 28 days before commencement of works on site.



EXISTING FIRST FLOOR LAYOUT.



EXISTING GROUND FLOOR LAYOUT.



EXISTING SIDE ELEVATION.



EXISTING REAR ELEVATION.



EXISTING SIDE ELEVATION.



PROPOSED SIDE ELEVATION.



PROPOSED REAR ELEVATION.



PROPOSED SIDE ELEVATION.



PROPOSED GROUND FLOOR LAYOUT.



EXISTING ROOF LAYOUT.



PROPOSED ROOF LAYOUT.

SECTION.



WELLFIELD GROVE.

BLOCK PLAN.
SCALE 1: 500

NOTES
The contractor is to check and verify all building and site dimensions, levels and sewer invert levels at connection points before tendering and work commences.
This drawing must read with and checked against any structural or other specialist drawings provided.
The contractor is to comply in all respects with the current building regulations whether specifically stated on these drawings or not. Internal dimensions exclude plaster thickness.
Do not scale off this drawing.

ROOF.

Main roof section to be interlocking concrete roof tiles all nailed and clipped at verges on 25x50mm battens on breathable sarking felt on 175x50mm C24 grade rafters at 400mm crs. Flat roof sections to be one layer of liquid roof membrain on 12mm plywood on 50mm Kingspan on 12mm plywood on 150x50mm C24 grade ceiling joists at 400mm crs (ceiling joists to match) with 100mm Kingspan between joists. Main lean to section to have 150mm Kingspan between rafters. All to have vapour control layer to undersides of joists and rafters. Kingspan 25mm thick below and 12.5mm plasterboard and plaster skim finish. Flat roofs to fall 1:80. 100x50mm wall plate. Wall plate tied down with 1.0m long m.s. straps at 600mm crs. 35x5mm m.s. straps across two rafters/ceiling joists (staggered between) and built into gable at max 2.0m crs, fascia and soffit to suit, with 114 p.v.c. h.r.w.g. and 68mm soil pipes, 150mm lead flashings, d.p.c's and tray to adjoining wall.

STRUCTURE.

102mm brickwork to match existing, bonded on alternate courses, 100mm cavity with 100mm Britherm insulation batts built in, inner skin 100mm Plasmor Fibalite blockwork. Two double triangle type ties per m² and every 225mm up reveals. Wall ties to be at max 750mm horizontally. D.p.c's to heads and reveals. Lintels to be Keystone HD/K 90 or similar and approved 225x75mm air grates with lintels, d.p.c's and trays over, in corners and at max 1.2m crs. External reveals to be insulated to prevent cold bridging with 'Thermabate' cavity closers. Walls finished off with 12.5mm plasterboard (dot/dabbed to walls) and plaster finish.

FLOOR.

18mm t and g chipboard type C4 on 175x50mm joists at 400mm crs, supported on 100mm honeycomb bond sleeper walls and d.p.c. over. Sub floor to be 100mm oversite concrete on 150mm sulphate free hardcore fill. 100mm Kingspan insulation board fitted between joists, supported on nails, nailed to sides of joists.

FOUNDATION.

To suit site conditions, normally 600x225mm concrete strip. 900mm min depth of foundation D.p.c. 150mm min above ground level. Below ground trench type blockwork to be used. Trial holes required to determine foundation design.

TIMBER WALL.

75x50mm s.w. partition, vertical members at 400mm crs and horizontal bracing with plasterboard and plaster skim finish to face. Void filled with glasswool with min density of 10 kg/m³.

© Copyright

Job Title: PROPOSED REAR EXT'N.		
Client: MR J. DURR		
Drawing Title: LAYOUTS.		
Drawn By: I.W.	Date: MARCH 15.	Scale: 1:50 1:100

IAN WILLIAMS
DESIGN AND BUILD
FAIRFIELDS, CHURCH ROAD,
ALTOFTS, W. YORKS WF6 2NU
Telephone: 01924 893311

DRG. No. 50. 01. 03. 15.

CORPORATE MAIL ROOM
05 MAY 2015
Received by:
ORIGINAL COPY