

For Assessment Window at 75 Haverhill Grove			Distance	5
			Barrier	Not Seen
MCS 020 - Manual Sound Calculator			Heat Pump	EDLA04E2V3
			Reflecting Surfaces	1
Step	Instructions	MCS contractor results/notes		
1	<p>From manufacturer's data, obtain the A-weighted sound power level of the heat pump. See 'Note 1: Sound power level'. The highest sound power level specified should be used (the power in "low noise mode" should not be used).</p> <p><i>Example: Manufacturer's data states the sound power level of the heat pump is 55 dB(A)</i></p>	58		
2	<p>Use 'Note 2: Sound pressure level' and 'Note 3: Determination of directivity' below to establish the directivity 'Q' of the heat pump noise.</p> <p><i>Example. The heat pump is to be installed on the ground and against a single wall hence the directivity (Q) of the heat pump noise is Q4</i></p>	Q4		
3	<p>Measure the distance from the heat pump to the assessment position in metres</p> <p><i>Example. Distance between heat pump and assessment position is 4 metres.</i></p>	5		
4	<p>Use table in 'Note 4: dB distance reduction' below to obtain a dB reduction</p> <p><i>Example. 4metres@ Q4 = -17 db</i></p>	-18.8		
5	<p>Establish whether there is a solid barrier between the heat pump and the assessment position using 'Note 5: Barriers between the heat pump and the assessment position' and note any dB reduction.</p> <p><i>Example. There is a brick wall between the heat pump and the assessment position. Moving less than 25cm enables the assessment position to be seen. dB reduction = -5 dB</i></p>	-10		
6	<p>Calculate the sound pressure level (see 'Note 2: Sound pressure level') from the heat pump at the assessment position using the following calculation: (STEP 1) + (STEP 4) + (STEP 5)</p> <p><i>Example (55) + (-17) + (-5) = 55 - 17 - 5 = 33 dB(A) Lp</i></p>	29.2		
7	<p>Background noise level. For the purposes of the MCS Planning Standard for air source heat pumps 40 dB(A) the background noise level is assumed to be 40 dB(A) Lp. For information see 'Note 6: MCS Planning Standard for air source heat pumps background noise level'.</p> <p><i>Example. Background noise level is 40 dB(A)</i></p>	40		
8	<p>Determine the difference between background noise level and the heat pump noise level using the following calculation: (STEP 7) - (STEP 6)</p> <p><i>Example: 40 dB(A) (background) - 33 dB(A) (heat pump) = 7 dB(A)</i></p>	10.8		
9	<p>Using the table in 'Note 7: Decibel correction' obtain an adjustment figure and then add this to whichever is the higher dB figure from STEP 6 and STEP 7. Round to nearest whole number</p> <p><i>Example: Adjustment figure is 0.8 dB and higher figure is 40 dB(A) 40 + 0.8 = 40.8 dB(A) Rounded up to 41 dB(A) Final result at this assessment position is 41 dB(A)</i></p>	40.34		
10	Final Result? (Greater or equal to 42 dB(A) is under PD)	Pass		