



ARBORICULTURAL REPORT & Impact Assessment to BS 5837:2012 at:

***Greenland Cottages,
High Hoyland,
Barnsley,
South Yorkshire
S75 4AZ***

Prepared for: ***Mr Steven Warsop***

Report Date: *April 2025*

Reference: *AWA6578*

0114 272 1124 / 0776 631 0880
info@awatrees.com
awatrees.com

Union Forge, 27 Mowbray Street, Sheffield S3 8EN
AWA Tree Consultants Limited. Company No. 85201
Registered in England & Wales.



TMP006 – B
Revision 02
Auth By: APW
Date: 27/03/2025

Contents

1. Introduction	3
1.1 Instructions and Brief	3
1.2 Survey Details	3
2. The Site	4
2.1 Location and Description	4
3. The Trees	5
3.1 Legal	5
3.2 Tree Survey Results	5
3.3 Photographs	7
4. Arboricultural Impact Assessment	8
4.1 Proposed New Development	8
4.2 Direct Impacts	8
4.3 Indirect Impacts	8
4.4 Protection of the Retained Trees	9
5. Signature	10
Appendix 1: Authors Qualifications & Experience	12
Appendix 2: Survey Methodology and Limitations	13
Appendix 3: Explanation of Tree Descriptions	14
Appendix 4: Tree Data	15
Appendix 5: Tree Constraints Plan	16
Appendix 6: Tree Impacts Plan	17

1. Introduction

1.1 Instructions and Brief

- 1.1.1 We have been instructed by Steven Warsop to visit the site and prepare our findings in a report.
- 1.1.2 The report is required in accordance with BS 5837:2012 *Trees in relation to design, demolition and construction – Recommendations*, to provide detailed, independent, arboricultural advice on the trees present, in the context of potential development.

1.2 Survey Details

- 1.2.1 The survey took place during April 2025.
- 1.2.2 The trees were surveyed visually from the ground using “Visual Tree Assessment” techniques and in accordance with the guiding principles of British Standard 5837:2012.
- 1.2.3 Any additional off-site trees that could impact a new development design have been included in the tree survey parameters.
- 1.2.4 We have been provided with a topographical survey with tree positions plotted. Where surveyed trees were not included on the topographical survey the tree positions were plotted using enhanced GPS technology (1-2m accuracy) and laser distance measurer.
- 1.2.5 This report has been prepared by Adam Winson, Chartered Arboriculturist, MSc, BSc (Hons), MICFor, MArborA, Principal and Director of AWA Tree Consultants Ltd.
- 1.2.6 Full qualifications and experience are included within **Appendix 1**. Explanatory details regarding the survey methodology are included within **Appendix 2**. A full explanation of the tree data can be found at **Appendix 3**. Full details of all the trees surveyed are found in **Appendix 4**. For tree locations please refer to the Tree Constraints Plan at **Appendix 5** and for detail of the impacts of the new development refer to the Tree Impacts Plan at **Appendix 6**.

2. The Site

2.1 Location and Description

- 2.1.1 The site is located in High Hoyland, a small village in the metropolitan borough of Barnsley, South Yorkshire.
- 2.1.2 The site is an area of land located to the north of a small strip of residential housing. The site is set back from the road and is in an elevated position.
- 2.1.3 The approximate area of the survey is highlighted in the (2023 Google Earth) image below:



3. The Trees

3.1 Legal

- 3.1.1 The following advice is for guidance purposes only. Some trees are protected by legislation, and it is essential that the legal status of trees is established prior to carrying out works to them. Unauthorised work to protected trees could lead to prosecution, resulting in enforcement action such as fines or a criminal record. Tree Preservation Orders, Conservation Areas, Planning Conditions, Felling Licences or Restrictive Covenants legally protect many trees in the UK.
- 3.1.2 Due to the large potential penalties for illegally carrying out work to protected trees, before authorising any tree works a check should be made with the Local Planning Authority to see if the trees are covered by a Tree Preservation Order or if they are within a Conservation Area. If either applies, then statutory permission is required before any works can take place (unless such work is approved as part of full planning permission).
- 3.1.3 The Multi-Agency Geographical Information for the Countryside (MAGIC) website was used to search for areas of ancient woodlands listed on the Ancient Woodland (DEFRA 2021), and a check for catalogued Ancient and Veteran trees using the woodland trust ancient tree inventory (ATI) (Woodland Trust 2021).
- 3.1.4 It was confirmed that there are no designated ancient woodlands or veteran or ancient trees within the survey area.
- 3.1.5 Trees provide a wide range of habitats for many species, some of which are legally protected such as bats, nesting birds, badgers and dormice. It is essential that appropriate care is taken to ensure that this legislation is not contravened.
- 3.1.6 When appointing a tree surgeon, only properly qualified and experienced companies should be used, who have adequate Public Liability and Employer's Liability Insurance.
- 3.1.7 All tree work should be carried out according to British Standard 3998:2010 Tree Work - Recommendations.

3.2 Tree Survey Results

- 3.2.1 The tree survey revealed 8 items of woody vegetation, comprised of 5 individual trees and 3 tree groups or hedges.
- 3.2.2 Of the surveyed trees: 3 trees are retention category 'B' and 5 trees, tree groups and hedges are retention category 'C' (explanatory details

regarding the retention categories are included at Appendix 3).

- 3.2.3 Full details of the surveyed trees, tree groups and hedges are provided in the attached tree data schedule at Appendix 4. General comments are provided below:
- 3.2.4 The significant tree cover within the site consists of trees along or beyond the eastern and northern boundary, with a small clump of trees to the western area.
- 3.2.5 Species diversity at the site is fair, with a mix of species including Sycamore and Oak, and shrubs including Hawthorn, Plum and Holly. Most of the trees are semi-mature or early-mature with only occasional mature trees.
- 3.2.6 A line of semi to early-mature Sycamore and Oak trees are situated along the site's eastern boundary (T1 to T4). The Sycamore T1 and Oak T2 are in the most prominent positions and are of moderate amenity value.
- 3.2.7 The land to the west of trees T1 to T2 drops down sharply, with an old quarry wall and retaining structures restricting root growth into the site.
- 3.2.8 The Root Protection Area (RPA) for each tree has been plotted as a polygon centred on the base of the stem. Where the presence of roads/hard surfaces, retaining structures and topography will have clearly impacted the tree roots actual morphology and disposition, the shape of the RPA has been modified to reflect this, without a reduction its area. Where modifications to the RPA have been undertaken this has been clearly detailed and justified on the attached Tree Constraints Plan at Appendix 5.
- 3.2.9 Some trees were covered in dense Ivy or were inaccessible (as detailed in Appendix 4). In such cases measurements were estimated and the condition values are indicative only.
- 3.2.10 Some lower value tree, hedge and shrub groups do not have RPAs detailed on tree plans. The detailed extent and spread of these low value groups, in conjunction with the tree schedule, is sufficient to assess the associated potential constraints.

3.3 Photographs



Photo 1: T1, looking north



Photo 2: T1, looking east



Photo 3: T1 to T4, looking northeast



Photo 4: T1 to T2, looking east



Photo 5: G6, looking west



Photo 6: G7, looking west

4. Arboricultural Impact Assessment

4.1 Proposed New Development

4.1.1 It is proposed to build a new residential development with associated access, parking, landscaping and facilities. The development proposals have been provided by my client and inform this arboricultural impact assessment and the Tree Impacts Plan at Appendix 6.

4.2 Direct Impacts

4.2.1 From assessing the new development proposals, no trees will require removal to facilitate the development, all the trees can be retained as part of the new development.

4.2.2 Trees requiring pruning to facilitate the new development are T2 Oak.

4.2.3 T2 Oak pruning works: Crown lift occasional low overhanging branches to clear 5m from ground level. Reduce crown to provide 2m clearance from proposed dwelling. Do not prune beyond boundary.

4.2.4 The required pruning works are minor in nature and the trees will not be significantly impacted in terms of condition or loss of visual amenity.

4.3 Indirect Impacts

4.3.1 The tree Root Protection Area (RPA) detailed on the Tree Plans at Appendices 5 and 6, has been used as a layout design tool, to inform on the area around a tree where the protection of the roots and soil structure is treated as a priority.

4.3.2 Potentially damaging activities are proposed in the vicinity of retained trees. The new development encroaches close to and into the edge of the RPA of T1 and T2. Construction within the RPA, can have negative impacts on tree roots. However, due to the sharp changes in land levels and landform, there will be little to no significant roots within the developed area from trees T1 and T2. As such, the retained trees should remain largely unaffected by the works, provided care is taken during construction.

4.3.3 The design of the new development has considered the trees crown position in relation to the dwelling. Some shade from trees may be beneficial. However, the design proposals avoid excessive shading and give adequate provision for future tree growth.

4.3.4 All the retained trees have been assessed as suitable for retention in terms of BS5837 (2012) section 5 "Proximity of structures to trees." The retained trees will not cause unreasonable inconvenience or nuisance issues to

future occupiers, leading to associated pressures for felling or excessive pruning. The layout allows sufficient space to enable the retained trees to grow to maturity without significantly adversely affecting the amenity of the dwelling or amenity space.

- 4.3.5 The buildability of the proposed development has been assessed in terms of access, adequate working space and provision for the storage of materials, including topsoil, in relation to the trees.

4.4 Protection of the Retained Trees

- 4.4.1 To ensure the successful retention of trees during the development process, all trees identified for retention must be physically protected from the outset of site preparation through to final landscaping. This protection should be in accordance with section 6.1 of BS:5837:2012 – Trees in Relation to Design, Demolition and Construction – Recommendations.
- 4.4.2 The primary method of protection will be the installation of tree protection fencing, constructed in line with the specification shown in BS 5837:2012.
- 4.4.3 This fencing must be installed prior to the commencement of any site clearance, demolition, or construction activity and remain in place for the duration of all potentially damaging operations.
- 4.4.4 The protected areas must be treated as construction exclusion zones. No materials, spoil, or equipment should be stored within these zones, and no access should be permitted.
- 4.4.5 Ground levels within the RPAs should be left unaltered, and care must be taken to avoid compaction of the soil structure, which could have long-term impacts on tree health.
- 4.4.6 If conditioned by the Local Planning Authority, an associated Arboricultural Method Statement (AMS) and Tree Protection Plan (TPP) detailing protective fencing locations and specifications, construction methods close to the retained trees, and any required site monitoring, can be provided.
- 4.4.7 The AMS and TPP explain how and when the protection measures will be installed and maintained throughout the development. They are designed to be referenced for practical guidance on how to protect the retained trees at the site to ensure contractors do not accidentally damage trees during construction.

5. Signature

I trust this report provides all the required information.

Signed



.....
Adam Winson, Chartered Arboriculturist, MSc, BSc (Hons), MICFor, ACIEEM

7th April 2025

**AWA Tree Consultants Limited
Union Forge
27 Mowbray Street
Sheffield
S3 8EN**

www.awatrees.com



Our Charity Partner: Kids Plant Trees

At AWA Tree Consultants, we are proud to partner with the local charity, Kids Plant Trees. This collaboration allows us to support a cause that reflects our commitment to trees and the environment while making a positive impact on local communities.

Kids Plant Trees is a grassroots charity dedicated to improving tree equity by planting trees in underserved areas with limited green spaces, often in communities facing higher levels of deprivation.

We are proud to support their mission to create greener, healthier environments for future generations.



Appendices

Appendix 1: Authors Qualifications and Experience

Appendix 2: Survey Methodology and Limitations

Appendix 3: Explanation of Tree Descriptions

Appendix 4: Tree Data

Appendix 5: Tree Constraints Plan

Appendix 6: Tree Impacts Plan

Appendix 1: Authors Qualifications & Experience

Adam Winson: Chartered Arboriculturist, MSc, BSc (Hons), MICFor, MArborA, ACIEEM, QTRA Registered

Adam is the company Director and Principal Consultant. He has a mix of the highest-level academic qualifications and relevant work experience. He has worked within the tree care profession for over 20 years and was awarded an MSc in Arboriculture and Urban Forestry, with distinction. Adam is a Chartered Arboriculturist and a Registered Consultant with the Institute of Chartered Foresters, a Professional Member of the Arboricultural Association and he has original research published by the UK Forestry Commission. His work ranges from individual expert tree inspections to managing trees on major infrastructure projects. His work often involves trees with preservation orders or litigation, and he has appeared as a tree expert, at planning appeal hearings up to the crown court. Adam also regularly undertakes locum Tree Officer work for several Local Planning Authorities.

James Brown: BSc (Hons) Arboriculture, MArborA, PTI (Lantra), QTRA Registered

James is a highly experienced and qualified Arboricultural Consultant. He has a BSc (Hons) in Arboriculture, attaining first class honours, as well as being awarded the Institute of Chartered Foresters student award. He is a Professional Member of the Arboricultural Association, an Associate of the Institute of Chartered Foresters, and he is working towards becoming a Chartered Arboriculturist. James joined AWA in 2016, he has many years' experience as an Arboricultural Consultant, he previously worked in Europe's largest container tree nursery and he has experience of local authority Tree Officer work.

James Godfrey: BA (Hons), FdSc Arboriculture and Tree Management, TechArborA, PTI (Lantra), QTRA Registered

James has had extensive arboricultural experience working as an arborist within the public and private sector. While working at AWA, James completed his FdSc in Arboriculture and Tree Management, graduating with a distinction and was also awarded for achieving the highest overall mark in his year. James has used his arboricultural knowledge to inform and carry out accurate tree surveys and produce detailed reports that aim to balance appropriate tree retention with the requirements of landowners.

Joe Thomas: MSci Biology, Award L4 Arboriculture, TechArborA, PTI (Lantra), QTRA Registered

Joe achieved a first class degree in Biology with an integrated Masters (MSci) from the University of Sheffield. Additionally, he has a Level 4 Award in Arboriculture. Joe joined AWA after an Urban Forestry role with the Sheffield and Rotherham Wildlife Trust and Sheffield City Council, where he gained a variety of experience in different aspects of the arboriculture sector.

Lucy Garbutt: MSc, PGCert, BSc (Hons) Biology, PTI (Lantra), TechArborA, QTRA Registered

Lucy graduated with a masters degree in Animal Behaviour from the UK's highest rated university, St Andrews of Scotland, immediately following the completion of her BSc degree in Biology from Lancaster University. Lucy has experience in botany and plant science and moved into arboriculture after previous experience of protected species and botanical surveys with a large environmental consulting company.

Sophie Beckerman: BA (Hons), Dip Arboriculture Level 4, PTI (Lantra), TechArborA, QTRA Registered

Sophie has more than 10 years' experience as an arborist, working for a variety of private companies as well as undertaking tree management with Sheffield City Council Ranger Service and The Wildlife Trust. Her expertise in arboriculture is demonstrated in the practical NPTC qualifications gained, and her excellent knowledge is reflected in the L4 diploma in Arboriculture, which she completed while working. Her roles as a climbing arborist and team leader included estimating for jobs and project management, supervising tree contracting teams - ensuring that work is carried out safely and efficiently and that health and safety standards are adhered to, and risk assessments are carried out.

Ross Lane: FdSc Environmental Conservation, Diploma Arboriculture, MArborA, PTI (Lantra), QTRA Registered

Ross has a diverse background spanning horticulture, arboriculture, and ecology. Ross has extensive experience conducting surveys throughout the UK and has worked on projects of all sizes, including major infrastructure projects such as HS2. In his previous role as a Tree Inspector at Derbyshire County Council, projects involved managing the county wide tree stock in relation to the ash dieback response and contributing to ambitious County Council targets of planting a million trees. Possessing technician-level membership with the Arboricultural Association, coupled with a comprehensive range of qualifications from tree risk assessment to habitat management, underscores Ross' dedication in professional arboriculture.

Appendix 2: Survey Methodology and Limitations

The survey was undertaken in accordance with British Standard 5837:2012 *Trees in relation to design, demolition and construction – Recommendations*. The trees were assessed objectively and without reference to any proposed site layout. The trees were surveyed from the ground using 'Visual Tree Assessment' (VTA) methodology. VTA is appropriate and is endorsed by industry guidance. It is used by arboriculturists to evaluate the structural integrity of a tree, relying on observation of trees biomechanical and physiological features. Measurements are obtained using a diameter tape, clinometer, laser distometer and loggers tape. Where this is not practical measurements are estimated. Tree groups have been identified in instances as defined in BS 5837:2012. Shrubs and insignificant trees may have been omitted from the survey.

This report represents a BS 5837:2012 tree survey and should not be accepted as a detailed tree safety inspection report; however, tree related hazards are recorded and commented upon where observed, yet no guarantee can be given as to the absolute safety or otherwise of any individual tree. All recommended tree work must be to BS 3998:2010 - '*Tree Work: Recommendations*'.

The findings and recommendations contained within this report are valid for a period of twelve months from the date of survey. The author shall not be responsible for events which happen after this time due to factors which were not apparent at the time, and the acceptance of this report constitutes an agreement with these guidelines and terms.

Appendix 3: Explanation of Tree Descriptions

HEIGHT of the tree is measured from the stem base in metres. Where the ground has a significant slope the higher ground is selected.

CROWN HEIGHT is an indication of the average height at which the crown begins.

STEM DIAMETER is measured at 1.5 metres above (higher) ground level. Where the tree is multi-stemmed at this point; the diameter is measured close to ground level or else a combined stem diameter is calculated.

CROWN SPREAD is measured from the centre of the stem base to the tips of the branches in all four cardinal points.

AGE CLASS of the tree is described as young, semi-mature, early-mature, mature, or over-mature.

PHYSIOLOGICAL CONDITION is classed as good, fair, poor, or dead. This is an indication of the health of the tree and takes into account vigour, presence of disease and dieback.

STRUCTURAL CONDITION is classed as good, fair or poor. This is an indication of the structural integrity of the tree and takes into account significant wounds, decay and quality of branch junctions.

LIFE EXPECTANCY is classed as; less than 10 years, 10-20 years, 20-40 years, or more than 40 years. This is an indication of the number of years before removal of the tree is likely to be required.

Retention Categories

A (marked in green on Appendix 5) = retention most desirable. These trees are of very high quality and value with a good life expectancy.

B (marked in blue on Appendix 5) = retention desirable. These trees are of good quality and value with a significant life expectancy.

C (marked in grey on Appendix 5) = trees which could be retained. These trees are of low or average quality and value, and are in adequate condition to remain until new planting could be established.

U (marked in red on Appendix 5) = trees unsuitable for retention. These trees are in such a condition that any existing value would be lost within 10 years.

Tree ID	Tree Species		Maturity	Measurements			Crown (m)				Comments	Physiological	Structural	Life Expectancy	Value		Management		
	Common Name	Latin Name		Height (m)	Stems	Stem Diameter (mm)	Estimated	Crown height	N	E					S	W		Amenity	Category
T1	Sycamore	<i>Acer pseudoplatanus</i>	Early-mature	11	1	440	Yes	6	4	5	5	4	No major visible defects. Crown overhanging road. Land drops to the west, limiting any root growth into the site. Heavily lvy clad stem and crown prevents detailed inspection. Crown lifted recently to west. Historical pruning evident near overhead utility cable to south	Good	Good	>40	Moderate	B	No action required
T2	Oak	<i>Quercus robur</i>	Early-mature	16	2	500, 350	Yes	4	9	8	8	5	No major visible defects. Adjacent/boundary tree, restricted access prevents detailed inspection. Land drops to the south west with old quarry face, and rises sharply to the north west, with retaining wall around 3m from stem, limiting any root growth into the site. Recent crown lift works evident to west. Occasional small snapped hanging branch in north crown	Good	Good	>40	Moderate	B	Crown lift occasional low overhanging branches to clear 5m from ground level. Reduce crown to provide 2m clearance from proposed dwelling. Do not prune beyond boundary
T3	Sycamore	<i>Acer pseudoplatanus</i>	Semi-mature	12	1	160	Yes	5	4.5	4	5.5	5.5	No major visible defects	Good	Fair	>40	Low	C	No action required
T4	Sycamore	<i>Acer pseudoplatanus</i>	Semi-mature	12	6	250	Yes	2	6	6	5	6	Multiple-stemmed form	Good	Fair	>40	Low	C	No action required
G5	Blackthorn	<i>Prunus spinosa</i>	Semi-mature	3	1	100	Yes	5	See Plan				Shrubby boundary group	Fair	Fair	>40	Low	C	No action required

Tree ID	Tree Species		Maturity	Measurements				Crown (m)				Comments	Physiological	Structural	Life Expectancy	Value		Management	
	Common Name	Latin Name		Height (m)	Stems	Stem Diameter (mm)	Estimated	Crown height	N	E	S					W	Amenity		Category
G6	Sycamore, Oak, Beech	<i>Acer pseudoplatanus</i>	Semi-mature	7	1	500	No	5	See Plan				Established boundary group	Good	Good	>40	Moderate	B	No action required
G7	Oak, sycamore	<i>Quercus robur</i>	Semi-mature	11	2	300	No	5	See Plan				Small clump of trees	Fair	Fair	20 to 40	Low	C	No action required
T8	Spruce	<i>Picea sp</i>	Semi-mature	11	1	300	No	4	3	3	3	3	Situated by access drive in adjacent garden area. Recent crown lift works evident to north crown	Good	Good	>40	Moderate	C	No action required



**Appendix 5:
Tree Constraints Plan**

Greenland Cottages, S75 4AZ
Ref: AWA6578

BRITISH STANDARD 5837:2012
RETENTION CATEGORIES
Definitions of these categories can be
found in Appendix 2 of the report.


SCALE: 1:200

PAPER: A3

	CATEGORY A: HIGH VALUE RETENTION MOST DESIRABLE
	CATEGORY B: MODERATE VALUE RETENTION DESIRABLE
	CATEGORY C: LOWER VALUE COULD BE RETAINED
	CATEGORY U: UNSUITABLE FOR RETENTION
	RPA: ROOT PROTECTION AREA
	TREE STEM

The former quarry wall, retaining walls and topography will have clearly impacted the tree roots actual morphology and disposition, as such the shape of the RPA has been modified to reflect this, without a reduction in area.

Felled to stump.
Previously T2.





**Appendix 6:
Tree Impacts Plan**

Greenland Cottages, S75 4AZ
Ref: AWA6578

BRITISH STANDARD 5837:2012

SCALE: 1:200

PAPER: A3

	TREE TO BE RETAINED
	TREE TO BE REMOVED
	RPA: ROOT PROTECTION AREA
	TREE STEM

