



Trees					
Trees					
Number	Species	Height	Girth	Specification	Density
11	Betula pendula 'Fastigiata'	300-350cm	12-14cm	Heavy Standard :3x :RB	Counted

Remove any general rubbish, stones, large roots and existing weed vegetation from the planting site. Plant in the dormant season between late October to late March. Plant immediately upon delivery from the supplier. Roots must be well soaked prior to planting. Dig a planting pit larger than the root ball (at least 150mm wider in all directions) and break up the base. Back fill multipurpose topsoil to comply with BS 3882 into the planting pit to bring the root ball level with the soil surface. Place the tree into the planting pit and backfill with top soil, firming in to hold the root ball in place. Water immediately. Trees will require staking, place two stakes driven 500mm into the base of the tree pit with 600mm clearance above ground directly opposite each other with the tree in between the two. Using cross bracing and soft tree ties to secure the tree loosely to the stakes. Apply 75mm settled depth of chipped bark to an area 1m radius from the tree trunk.

During the first growing season, water regularly until new roots have established. Thereafter water regularly in hot weather. Allow 10L per tree per day. Top up annually to 75mm settled depth chipped bark. After the fifth year remove the stakes from the trees.

Brooks
Ecological
Grounded advice