

Goldthorpe Roundabout Sculpture

Materials

Mild steel, various sizes

20 mm plate, 114.3 x 5 mm CHS, 60.3 x 4 mm CHS, 33.7 x 3.2 mm, 4 mm plate

Finish

All mild steel galvanised

Anti-graffiti varnish with translucent water based green colouring.

Inspection

Base plate fixings should be inspected at regular intervals throughout the year for signs of movement or wear.

All weld connections and bolted fixings should be inspected at least once a year and should be checked for tightness and adjusted if necessary.

The foundation block where visible should be inspected for cracks or weakness.

Maintenance -

Remove any debris from the base plate and sculpture

Any graffiti can be removed with a suitable solvent or thinners based cleaner, e.g. acetone.

Clean with warm soapy water and rinse with clean water.

No other maintenance should be necessary