



General Notes:-

1. DO NOT USE THIS DRAWING IN ISOLATION. This drawing has been prepared as part of a set, and must therefore be read in conjunction with all other drawings. Any discrepancies must be reported to the engineer prior to commencing works.
2. Third party information is used to prepare the engineering design (including architectural layout, ground investigation, existing utilities records, and specialist design items). The engineering design must therefore be read in conjunction with all third party information prior to commencing work. Queensberry Design Ltd are not responsible for any third party information or details.
3. House type working drawings are to be used in conjunction with the plot setting out drawing.
4. Drawing status will remain preliminary until full technical approval is received from local authority and sewerage undertaker. Works commenced prior to technical approval are done so at risk and may be subject to change.
5. The contractor is expected to prepare appropriate construction method statements for all aspects of appointed work. This should include any temporary protection works.
6. Land drainage is not permitted to discharge into the public sewer network. Any need for land drainage should be assessed by the ground worker and landscaper during construction and placement of gardens on an individual plot basis. If land drainage designs are required, they should be appointed prior to plot completion.
7. The contractor is expected to cross check all drainage inverts prior to commencing work, this may involve completion of trial holes if invert levels have been interpolated.
8. The position, line and diameter of all existing drainage apparatus should be confirmed on site prior to the commencement of the works. Any discrepancies must be reported to the engineer immediately.
9. The connection of foul and surface water drainage to the existing public sewer system shall be subject to the approval of the local sewerage undertaker. The contractor is expected to apply for relevant permits prior to commencing the work.

Highways

1. All highway works to be carried out in accordance with the current South Yorkshire design guide and specification.
2. All excavations below proposed and existing highways to be back filled with granular Type 1 sub base and well compacted in layers not exceeding 150mm, unless otherwise agreed.
3. Highway authority to be notified by the contractor prior to the commencement of works.

Yorkshire Water Notes

1. All adoptable sewer works and material to be in accordance with 'Sewers for Adoption' 6th Edition. The Relevant British/European and Yorkshire Water's Standards/Requirements/Adendum and Kitemarked.
2. Manhole covers shall must have a clear covering of 200mm and shall be Class D400 to BS EN 124 with 150mm deep frames in highways.
3. Fill ground must be filled and consolidated under the supervision and to the satisfaction of Yorkshire Water before any sewer works are carried out.
4. Yorkshire Water is not obliged to accept filter drain/land drainage runoff into the public sewer network or adoptable drainage system (directly or in-directly). An alternative method of disposal of the land drainage runoff will therefore be required and you will have to liaise with the Local Authority, Land Drainage Section with regard to the disposal of the filter drain/land drainage runoff.
5. Cover slabs must carry the BSI Kitemark or will be rejected by Yorkshire Water Inspector. Where the clear opening of the Kitemarked product is different to that of the cover and frame, a loading bearing slab should be fitted above the cover slab to bring the size down to 500mm x 500mm for the Yorkshire Water specified cover size. Please refer to Concrete Pipe Systems Association (CPSA) 'Technical Bulletin' issued autumn 2004 for Kitemarked cover slab opening sizes.
6. Cover slabs must carry the BSI Kitemark or will be rejected by Yorkshire Water Inspector. Where the clear opening of the Kitemarked product is different to that of the cover and frame, a loading bearing slab should be fitted above the cover slab to bring the size down to 500mm x 500mm for the Yorkshire Water specified cover size. Please refer to Concrete Pipe Systems Association (CPSA) 'Technical Bulletin' issued autumn 2004 for Kitemarked cover slab opening sizes.
7. The adoptable sewers should be a minimum of 1m and manholes 0.5m from kerb faces and service margins.
8. 'Sewers must have 5 metres clearance from trees and hedges (please also refer to Figure 2.3 on page 33 in 'Sewers for Adoption' 6th Edition for restrictions on tree planting adjacent to sewers).
9. Sewers to be laid in Class 'S' Bedding (150mm granular bed and surround). Where depth of cover to top of the sewer is less than 1.2m in highways and verges (or less than 900mm in non vehicular access areas) then a concrete slab should be provided above granular bed and surround.
10. Bedding and backfill material to conform to the requirement of Water Industry Specification 4-06-02 (Table A2).
11. The chamber size of manholes with more than one connection in them may need to be increased an increment to accommodate the connections and bends.
12. Yorkshire Water policy is not to accept Type 'C' brick manholes and 1050mm Ø manhole rings. Instead it is preferred that you use a Type 'B' manhole with 1200mm Ø or 1500mm Ø rings, with the opening slab over the chamber where depth of cover to pipe is 1 - 1.5m.
13. All adoptable sewers to be BSI Kitemark (Certified to WIS 4-3501).
14. Adoptable sewer pipes to be laid in maximum 3m lengths unless there is a specific operational need to lay longer lengths. 12. Bedding and backfill material to conform to the requirement of Water Industry Specification 4-06-02 (Table A2).
15. Plastic channel sections in manholes are not acceptable and Yorkshire Water would prefer clayware channel in manholes, we have found that plastic channels are difficult to set in concrete because they float and a satisfactory finish cannot be obtained on the bedding.
16. Yorkshire Water policy is not to accept Type 'C' brick manholes and 1050mm Ø manhole rings. Instead it is preferred that you use a Type 'B' manhole with 1200mm Ø or 1500mm Ø rings, with the opening slab over the chamber where depth of cover to pipe is 1 - 1.5m.
17. Concrete pipes should be Class 120 to EN 1916 / BS 5911-1: 2002.
18. The position, line and diameter of all existing drainage apparatus should be confirmed on site prior to the commencement of the works. Any discrepancies must be reported to the engineer immediately.
19. The connection of foul and surface water drainage to the existing public sewer system shall be subject to the approval of the local sewerage undertaker. The contractor is expected to apply for relevant permits prior to commencing the work.
20. 1350Ø chamber rings are allowed on the adoptable network and are to be Kitemarked.
21. The position, line and diameter of all existing drainage apparatus should be confirmed on site prior to the commencement of the works. Any discrepancies must be reported to the engineer immediately.
22. The connection of foul and surface water drainage to the existing public sewer system shall be subject to the approval of the local sewerage undertaker. The contractor is expected to apply for relevant permits prior to commencing the work.

Existing Services

Prior to the commencement of any works under ground mapping surveys and constraints plan is to be referred to any discrepancies are to be reported to engineer.

Any existing services which may be affected by the proposed works should be located by means of a hand dig in close liaison with the statutory service authorities. The contractor shall inform the developer of any services that may affect the proposed design. Contractor to notify statutory service authorities prior to commencement of work. As Constructed Information it is the contractors responsibility to provide the following as constructed drawings to the developer upon the completion of the works covered by the contract:-

1. Position to co-ordinates of all adoptable manholes.
2. Invert and cover levels of all adoptable manholes.
3. New gully positions and connections.
4. Position and depth of service ducts for water, gas, electric, BT, cable and street lighting, stalling size and number of ducts.



| REV | REVISION    | BY | DATE     |
|-----|-------------|----|----------|
| -   | First Issue | NL | 29.07.17 |

Drawing Status

**PRELIMINARY**

Title

**Keepmoat Homes  
Thurnscoe Phase 2**

**Phase 2 External Levels St 3**

Scale

**1:250 @ A1**

Date

**July 2017**

Drawn by

**NL**

e-mail

**nl@keensberrydesign.co.uk**

Drawing no.

**QD814-04-03**

Revision

**-**

Checked by

**AL**

**QUEENSBERRY DESIGN**  
ENGINEERING & ARCHITECTURAL CONSULTANTS

**NORTH EAST OFFICE**  
SUITE 10, THE RIVERFORD PARK, STANNINGTON  
NORTHUMBERLAND, NE61 6EF T: 01676 789834

**NORTH WEST & YORKSHIRE OFFICE**  
BLAKE HOUSE, 25 ST MARTIN LANE, YORK, YO1 6LN  
T: 01904 500 663

**www.queensberrydesign.co.uk**