


SOIL ANALYSIS

for Subsidence Management Services

55 Darton Road, Barnsley, S75 4HY

Client: Subsidence Management Services
Client Contact: Alun Dwyer
Claim Number: 18HCH000602
Policy Holder: Mr & Mrs Steven Greagsby
Report Date: 18 January 2019
Our Ref: C13854S41821
Laboratory Ref: L14796

Compiled By: 
Checked By: 

Date samples received: 18 December 2018
Moisture Content Test Date: 3 January 2019
Atterberg Limits Test Date: 17 January 2019

Notes relating to soils testing

Unless otherwise stated, all soils testing was undertaken at Environmental Services' soils laboratory at unit 10H Maybrook Business Park, B76 1AL.

Soil samples have been prepared in accordance with BS1377:Part 1: 2016 Section 7

Descriptions of soil samples within the laboratory have been undertaken generally in accordance with BS5930:2015

Following the issue of this soil analysis report, samples will be retained for 1 month should additional testing, or referencing, be required. It should be noted that any tests undertaken on soils retained subsequent to the issue of this report may not give an accurate indication of the in-situ conditions of the sample.

Natural Moisture Content Tests are undertaken in accordance with ISO 17892:Part 1:2014

The Liquid Limit test is undertaken in accordance with BS1377:Part 2:1990 Section 4.4

The Plastic Limit test and the determination of the Plasticity Index is undertaken in accordance with BS1377:Part 2:1990 Section 5

This Soil Analysis Report may not be reproduced, in part or in full, without written approval of the laboratory.

Note


Where appropriate moisture contents have been corrected to demonstrate the equivalent moisture content following the sample being passed through a .425 mm sieve for comparison with the Liquid & Plastic Limit. Where this is not available, uncorrected moisture contents have been used in the graph on the following page.

Deviations to testing schedule:

All testing has been undertaken in line with the soils testing schedule provided


Lab Ref	Depth (m)	MC (%)	Corr MC (%)	LL (%)	PL (%)	PI (%)	% Passing .425mm
Samples from BH1							
001	0.65	32	32	46	18	28	100
002	0.90	27					
003	1.50	23	40	54	21	33	58

Corrected Moisture Content and Plastic Limits Graph



Lab Ref	Depth (m)	Description	BS:5930	NHBC Chapter 4.2
Samples from BH1				
001	0.65	Soft to firm brown slightly sandy CLAY with rare gravel and charcoal. Gravel is fine and medium.	CI	Medium
002	0.90	Soft to firm brown CLAY with rare gravel, sand and charcoal. Gravel is fine and medium.		
003	1.50	Soft to firm brown slightly gravelly slightly sandy CLAY with rare charcoal. Gravel is fine and medium.	CH	Medium

Plasticity Chart for Casagrande Classification



References and Interpretation

The following provides a brief interpretation of the test results by comparison of the results to published classifications. The Atterberg Limit test may be used to classify the plasticity of soils; the plasticity classes defined in BS5930:1999 "Code of Practice for Site Investigations" are as follows.

CL (ML)	CLAY and CLAY/SILT of Low plasticity
CI (MI)	CLAY and CLAY/SILT of Intermediate plasticity
CH (MH)	CLAY and CLAY/SILT of High plasticity
CV (MV)	CLAY and CLAY/SILT of Very High plasticity
CE (ME)	CLAY and CLAY/SILT of Extremely High plasticity
O	The letter O is added to prefixes to symbolise a significant proportion of organic matter.
NP	Non-plastic

The Plasticity Index (PI) Result obtained from the Atterberg Limit tests may also be used to classify the potential for volume change of fine soils, in accordance with the National House Building Council's standards - Chapter 4.2 (2003) "Building Near Trees", as summarised below.

Modified PI < 10	Non Classified.
Modified PI = 10 to <20	Low volume change potential.
Modified PI = 20 to <40	Medium volume change potential.
Modified PI = 40 or greater	High volume change potential.

The 2003 edition of Chapter 4.2 also permits use of the Plasticity Index without modification. The classifications for this are grouped by soil type (soils with similar visual soils description and using unmodified Plasticity Indices.