



BGS ID: 84430 : BGS Reference: SE30SE7/A
 British National Grid (27700) : 438317,402958 [Report an issue with this borehole](#)

SE 30 SE 7 291 87/65A B
 SECTION OF Wombwell Main Collieries at 1 mile west of Wombwell
 No. 1. Shaft to Parrogate No. 3 Shaft to Silkstone.

Maps: One-inch 87 Six-inch 283 NW County Yorkshire
 Height above O.D. 225 ft. Latitude 53° 31' N Longitude 1° 28' 17" W
 Communicated by 'Sec. Strata Gls Clfld' pp. 389-391 Date of Sinking No. 1 to Barnsley 1853-4 No. 3 to Parrogate 1892-8 No. 3 to Silkstone 1885
 Made by Dip of Strata 1 in 12 N 58 E (magnetic 1913)

Summary of published record:-		Thickness.		Depth from Surface.	
	Soil	0.30	1	0.30	1
Intervening measures are shales, limestones, with thin coals	Woolley Edge Rock	36.52	119 10	36.83	120 10
	Wath Wood Seam	1.07	3 6	41.48	136 1
	Two Foot Coal, with dirt	1.45	4 9	42.92	140 10
	Abdy Coal	0.79	2 7	43.5	208 4
	Canal	4.11	13 6	103.99	341 2
	Kent's Thin Coal	0.56	1 10	108.33	355 5
	Kent's Thick Coal with dirt	2.26	7 5	131.22	430 6
	<u>Barnsley Bed</u>	2.41	7 11	136.65	645 2
	Strong grey rock with stone band in middle	10.9	35 9	212.73	697 11
	Dunsil Seam (with thick dirt)	2.87	9 5	221.87	727 11
Swallow Wood Seam	3.68	12 1	250.32	821 3	
Birdwell Rock	14.30	46 11	264.62	868 2	
Lidgett Seam	0.91	3 -	324.99	1066 3	
Joan Coal	0.46	1 6	354.18	1162 -	
Flockton Thick (with thick dirt)	1.47	4 10	379.17	1214 -	
Rock	4.88	16 -	407.75	137 9	
Fenton Seam (with thin dirt)	4.11	13 6	429.34	1408 7	
Rock with middle band of stone band	6.86	22 6	436.19	1431 1	
Parrogate Seam (with dirt)	3.48	11 5	445.18	1460 7	
in No. 3 Pit	Thorncliffe Thin Seam	0.76	2 6	465.83	1528 4
	Rock	14.17	46 6	476.27	1562 7
	Silkstone Seam	0.91	3 -	531.27	1743 -

