



- LEGEND**
- Proposed Medium Trees**
Located along the boundaries to provide instant impact. To be 14-16cm girth, Extra Heavy Standard.
 - Proposed Mixed Native Scrub**
To be planted as bare root stock, 60-80cm, at 2 per m², and protected with spiral guards. To be planted in groups of 3-5 plants.

- GENERAL NOTES**
- This drawing is the copyright of TPM Landscape Ltd and cannot be reproduced in any form without the consent of the company.
 - This drawing is to be read in conjunction with detail landscape drawings, details and specification.
 - This drawing is to be read in conjunction with all relevant Architects', Engineer's, Specialists, Bills of Quantities and Specifications.
 - The insertion of any firm or proprietary brand on this drawing is an indication of the class or quality required and does not exclude the use of alternative materials that are equal in performance, quality and appearance, provided that they have been approved in writing by the Landscape Architect.
 - The Contractor is responsible for accurately ascertaining the position of underground services and responding to all relevant service easement requirements.
 - All dimensions are in millimetres unless stated otherwise, for the purposes of construction this drawing must not be scaled and only written dimensions used. Written and scaled dimensions to be checked on site, any discrepancies reported prior to work commencing. IF IN DOUBT PLEASE ASK.
 - All work and materials are to be in accordance with the relevant British Standards and Code of Practice.
 - All Proprietary products are to be used strictly in accordance with the manufacturer's instructions and details.

REVISION NOTES

Rev	By	Description	Date

TPM Planting Schedule (Individual)

Tree	Nr	Code	Plant Name	Height/Spread/Grade	Girth	Age	Root	Container	Habit	Form	Density/m2
	4	Bp	Betula pendula	450-500cm	225mm	3x	RB			Standard (Extra heavy)	
	2	Psy	Pinus sylvestris	550-600cm	225mm		C	10-15L		Standard (extra-heavy)	
	4	Qr ro	Quercus robur	450-500cm	18-20cm	3x	RB			Standard (extra-heavy)	

TPM Planting Schedule (Mix)

Birch & Alder Mix Imperial											
Nr	Code	Plant Name	Mix%	Height/Spread/Grade	Girth	Age	Root	Container	Habit	Form	Density/m2
12	Acr cm	Acer campestre	5.00%	60-80cm	8-10cm	0/1/1	C	2L		Whip	1.00
116	Aln gl	Alnus glutinosa	50.00%	40-60cm			B			Seeding	1.00
19	Be pb	Betula pubescens	8.00%	60-80cm		1/1	C	3L		Transplant	1.00
46	Be pnd	Betula pendula	20.00%	60-80cm		1/0	B			Seeding	1.00
5	Cryls av	Corylus avellana	2.00%	200-250cm			B				1.00
5	Prns av	Prunus avium	2.00%	550-600cm	14-16cm		C	70-100L		Standard	1.00

Client
Caulmert

Project
West Green Recycling, Cudworth

Description
Planting Plan

Status
For Approval

Scale @ A1
1:250

Drawn
EC

Checked
CT

Date
19.12.25

Job number
4667

Drawing number
201

Revision
-

