

NORTH

KEY

EXISTING VEGETATION TO BE RETAINED
(To be protected during construction in accordance with BS 5837: 2012 'Trees in relation to design, demolition & Construction'). Refer to FPCR drawings.

FEATHERED TREES
1.75-2.0m height 2x transplanted
Well furnished with lateral shoots to base
Root wrapped

Tree Species		Common name
Ac	Acer campestre	Field Maple
Ag	Alnus glutinosa	Alder
Bpu	Betula pubescens	Downy Birch
Pa	Prunus avium	Wild Cherry
Qr	Quercus robur	Oak

PROPOSED THICKET MIX PLANTING
(*300mm depth of topsoil onto 600mm depth subsoil*)
Transplants planted in groups of 7-15 of the same species on a 1.0m grid.

PROPOSED WILDFLOWER GRASS SEED - GENERAL AREAS
(Cultivated subsoil to a depth of *300mm*)
Emorsgate EM1 General Purpose Meadow Mixture at a rate of 4g/m2.

PROPOSED WILDFLOWER GRASS SEED ATTENUATION AREAS
(Cultivated subsoil to a depth of *300mm*)
Attenuation area to be seeded with Emorsgate EM8 Meadow Mixture for Wetlands at a rate of 4g/m2.

PROPOSED WILDFLOWER GRASS SEED WET MARGINAL AREAS TO PONDS/ SWALES/ ATTENTAUTION AREAS
(Cultivated subsoil to a depth of *300mm*)
Areas along average water line to be seeded with Emorsgate EP1 Pond Edge Mixture at a rate of 4g/m2.

PROPOSED CLOSE MOWN GRASS AREAS
(*150mm depth of topsoil onto 300mm depth subsoil*)
Low Maintenance Amenity Grass Mix at a rate of 35-50g/m2.

PROPOSED GRASS SEED FOR ARCHERY AREA
(*150mm depth of topsoil onto 300mm depth subsoil*)
DLF FM 81 Premier Renovation 35-75g/m2

FENCE
(To Architects/Engineers details)

BALL STOP FENCE ARRANGEMENT
(By Newlands)

SITE BOUNDARY

AREAS TO BE IMPLEMENTED BY BARNSLEY CC

Notes:
For proposed FFL's, plateau and earthworks levels refer to RPS Engineers drawings.
Layout based upon PHP Architects Land for Sports Facilities Plan 4400-SP002-P5 received 31/03/2021. Landscape design principles based upon FPCR Biodiversity Plan.

0 12.5 25 37.5 50m
0 10 20 30 40 50 60 70 80 90 100mm
Scale 1:500

LANDSCAPE SPECIES SCHEDULE

PROPOSED THICKET/SCRUB MIX PLANTING
(*300mm depth of topsoil onto 600mm depth subsoil*)
Where woodland or thicket is planted next to a hard surface/kerb/fence, it should be positioned 1m from the edge. Transplants planted in groups of 7-15 of the same species on a 1.0m grid.

%	Species	Common Name	Size	Age	Root	(TH1) 568m2 No.	(TH2) 805m2 No.
10%	Acer campestre	Field Maple	400-600mm	1+1	OG	50	80
10%	Cornus sanguinea	Dogwood	400-600mm	1+1	OG	50	80
15%	Corylus avellana	Hazel	400-600mm	1+1	OG	75	124
20%	Crataegus monogyna	Hawthorn	400-600mm	1+1	OG	102	161
5%	Ilex aquifolium	Holly	400-600mm		2L	25	40
5%	Ligustrum vulgare	Privet	400-600mm	1+1	OG	25	40
10%	Prunus spinosa	Blackthorn	400-600mm	1+1	OG	50	80
5%	Rosa canina	Dog rose	400-600mm	1+1	OG	25	40
5%	Salix caprea	Goat willow	600-800mm	1+0	OG	25	40
5%	Sambucus nigra	Elder	400-600mm	1+1	OG	25	40
10%	Viburnum opulus	Guelder Rose	400-600mm	1+1	OG	50	80
						502	805

PROPOSED INDIGENOUS HEDGEROW (TO LPA SPECIFICATION)
(*300mm depth of topsoil onto 600mm depth subsoil*)
Hedge to be planted in a double staggered row, each row 500mm apart, with plants in each row at 200mm cts. (164 Lin.m)

%	Species	Common Name	Size	Age	Root	(H1) No.
5%	Carpinus betulus	Hornbeam	600-800mm	1+1	OG	82
5%	Cornus sanguinea	Dogwood	600-800mm	1+1	OG	82
10%	Corylus avellana	Hazel	600-800mm	1+1	OG	164
50%	Crataegus monogyna	Hawthorn	600-800mm	1+1	OG	820
2.5%	Ilex aquifolium	Holly	400-600mm		2L	41
2.5%	Ligustrum vulgare	Privet	600-800mm	1+1	OG	41
10%	Prunus spinosa	Blackthorn	600-800mm	1+1	OG	164
5%	Rosa canina	Dog rose	600-800mm	1+1	OG	82
5%	Ulmus glabra	Wych Elm	600-800mm	1+1	OG	82
5%	Vibunum opulus	Guelder Rose	600-800mm	1+1	OG	82
						1640no.

This drawing, the works and concepts depicted are copyright of the consultant and may not be reproduced or made use of, either directly or indirectly without express written consent. All heights, levels, sizes and dimensions to be checked on site before any work is put to hand.

Revisions

P1	Issued for planning submission.	09/04/21 MG
P2	Marked up drawing with areas for costs review.	17/03/22 MG
P3	Revised in accordance with latest proposals.	18/03/22 MG
P4	Minor revision.	21/03/22 MGO
P5	Hedge and fence re-introduced.	25/04/22 MG
P6	Further client comments	25/04/22 MG
P7	Seeding north of archery area included to WLL wks.	23/08/22 MG
C1	As Built drawing issue.	31/10/22 MGO
C2	Hedge fence spec. changed to LPA requirements.	12/01/23 MG

Hoyland West
Hoyland

newlands developments

Barry Chinn Associates Ltd.
www.bca-landscape.com

Landscape Proposals Drawing (Parkside)

Drawing Status:	Construction
CAD Reference:	2044-20_101-C2-Parkside-lscp-proposals-2023-01-12.dwg
Drawn:	MG
Date:	08/01/2021
Scale @A0:	1:500

Project No:	Drawing No:	Rev:
2044/20	HOY-BCA-ELS-XX-DR-L-2044/20-101-S4	C2