

Priory Weathered Red

IBSTOCK



Product Information

Ibstock Code:	0585
Type:	Wirecut
Facing Description:	Smooth
Dry Brick Weight (kg):	2.1kg
Pack Quantity:	400
Packaging (standard):	Banded (plastic)
Factory:	Nostell

Technical Specification (to BS EN 771-1)

Brick Dimensions (L x W x H mm):	215x102x65
Size Tolerances Mean & Range:	T2 R1
Configuration:	Vertically Perforated
Voids (%):	25-30
Compressive Strength (N/mm ²):	60
Active Soluble Salts:	S2
Water Absorption (% weight):	10
Durability:	F2
Gross Dry Density (Sound Insulation) (Kg/m ³):	1570
Equivalent Thermal Conductivity "K" value 5% Exposed:	Refer to Ibstock
Initial Rate of Absorption (Suction Rate) (Kg/m ² /min):	Refer to Ibstock
EAN:	5036335031179