

PRODUCT NAME	EDLA04-08E3V3				
					EDLA08E23V3
Heating capacity	Nom.			kW	7.50 (1), 7.80 (2)
Lämmitysteho	Vaihe 1			kW	3
Power input	Heating		Nom.	kW	1.63 (1), 2.23 (2)
COP					4.60 (1), 3.50 (2)
Dimensions	Unit		Height	mm	770
			Width	mm	1,250
			Depth	mm	362
Weight	Unit			kg	91.0
Operation range	Heating	Vesi	Min.	°C	15 (3)
			Maks.	°C	65 (3)
	Kuuma käyttövesi	Ympäristö	Min.	°CDB	-27
			Maks.	°CDB	35
		Vesi	Min.	°C	25
			Maks.	°C	55 (3)
Sound power level	Heating		Nom.	dBA	62.0 (1)
Sound pressure level	Heating		Nom.	dBA	49.0 (1)
Refrigerant	Type				R-32
	GWP				675.0
	Charge			kg	1.35
Space heating	Average climate water outlet 55°C	General	SCOP		3.32
			Seasonal space heating eff. class		A++
	Average climate water outlet 35°C	General	SCOP		4.56
			Seasonal space heating eff. class		A+++
Compressor component	Main power supply		Phase		3N~
			Voltage	V	220
Power supply	Name				V3
	Phase				1~
	Frequency			Hz	50
	Voltage			V	230 +/-10%
Notes					(1) - Condition 1: cooling Ta 35°C - LWE 18°C (DT = 5°C); heating Ta DB/WB 7°C/6°C - LWC 35°C (DT = 5°C)
					(2) - Condition 2: cooling Ta 35°C - LWE 7°C (DT = 5°C); heating Ta DB/WB 7°C/6°C - LWC 45°C (DT = 5°C)
					(3) - For more details, see operation range drawing