HOOBER LTD

Hough Lane , Wombwell

Landscape Schedules

To be read in conjunction with drawing number 2001 /5 /La1
Sheets 1, 2

February 2021

Leflay Design

Shrubs

Species references	Species	Height in cms.	Pot size	Density	Quantity
Aucjr	Aucuba japonica Rozannie	15-30 cms	3L	3/m2	72 no
Budl	Buddleia Nanho blue	30-40 cms	3L	1/m	2 no
Cham	Chaenomeles Crimson and Gold	30-40 cms	3L	2 per lin M	6 no
Chots	Choisya ternata Sundance	30-40 cms	3L	3/m2	21 no
Escr	Escallonia rubra Crimson Spire	30-40 cms	3L	3/m2	18 no
Euofs	Euonymus fortunei Sunshine	15-30 cms	3L	4/m	123 no
Germ	Geranium macrorrhizum Czakor	15-30 cms	3L	5/m2	50 no
Hebc	Hebe Caledonia	15-30 cms	3L	5/m2	10 no
Helc	Helleborus Corsicus	15-30 cms	3L	4/m	12 no
Ligo	Ligustrum ovalifolium aureum	30-40 cms	3L	.3 m cts	30 no
Lonn	Lonicera nitida Baggesens Gold	30-40 cms	3L	3/m2	3 no
Mahsc	Mahonia Soft Caress	30-40 cms	3L	4/m	12 no
Maha	Mahonia Aquifolium Apollo	30-40 cms	3L	4/m	12 no
Pach	Pachysandra terminalis	15-30 cms	3L	5/m2	75 no
Pyrsy	Pyracantha saphyr yellow	40-60 cms	5L	1m cts	4 no
Salv	Salvia purpurascens	15-30 cms	3L	5/m2	15 no
Skic	Skimmia confusa Kew Green	30-40 cms	3L	3/m2	21 no
Skijr	Skimmia japonica rubella	15-30 cms	3L	4/m	44 no
Vibd	Viburnum davidii	15-30 cms	3L	3/m2	36 no

Shrubs to BS 3936 to be planted in debris and weed free topsoil 30 cms deep. Topsoil to BS 3882. Any heavily compacted and panned ground to be deep ripped to relieve the compaction. All beds to be accurately cut with even curves and straight lines as appropriate. Allow for 75 mm of Contract Ornamental bark mulch to all planting beds. Plants to be good quality bushy stock commensurate with the stipulated pot size.

Hedging

Ligustrum ovalifolium aureum planted in a single row with plants at 300 mm centres to be maintained at 600 mm maximum height to permit visibility.

TREES including those to Open Spaces

REF	SPECIES	GIRTH	QUANTITY
Acerce	Acer campestre Elegant	14 -16 cms	4 no
Amel	Amelanchier arborea Robin Hill	12-14 cms	1 no
Betj	Betula utilis Jacquemontii	12-14 cms	3 no
Carpf	Carpinus betulus Frans Fontaine	12-14 cms	14 no
Malr	Malus Rudolph	12-14 cms	1 no
Pyrcr	Pyrus calleryana Redspire	12-14 cms	1 no
Querk	Quercus robur Kosteri	14 -16 cms	3 no

Trees to be staked and tied at low level using 75 mm peeled larch stakes and durable rubber ties. Triple staked trees to have 3 no peeled larch stakes 2.1 metres long, 600 mm into the ground. Trees triangulated using 3 no 500 mm long x 75 mm x 25 mm tantalised timber spacer bars nailed to top of stakes with galvanised clout nails. Drainage runs are to be avoided by 6 metres. Tree held in place centrally using durable rubber ties. Base of triple staked trees to be have a 1 metre diameter circle of grass free topsoil which is to be mulched and maintained weed free. The triple staking is to reduce the possibility of damage sustained by mowers and strimmers and not necessarily for the stability of the tree. Tree

pits are to be 900 mm x 900 mm x 750 mm deep with layered backfill containing the recommended quantity of mycorrhizal fungal spores. Trees to be planted at the same level as originally planted and to the same collar mark in relation to the soil level. Trees are to be well watered at planting time and during times of low rainfall.

Existing trees to be protected in accordance with BS 5837 for the duration of the construction process.

Grass mixes

The Emorsgate EG22c mix is to be sown within the Public Open Space at 25 g/m on 100 mm topsoil to BS 3882 which is to be raked to a tilth with all stones above 50 mm diameter removed. The EG22c is to be cut regularly during the growing season from March to September. The establishment and subsequent aftercare in the Emorsgate area is to be in accordance with the Emorsgate recommendations at www.wildseed.com.

Front gardens are to to be turfed using good quality meadow turf which is to be laid on 100mm topsoil to BS 3882 raked to a tilth with all stones and deleterious material removed.