

TPS Transport Consultants Ltd

Stage 1 RSA Brief

Client	Avant Homes
Project	Barugh Green Road, Barnsley
TPS Reference	P2636
Date Prepared	27.06.25
Prepared By	JT

Copyright Statement

This report is the copyright of TPS Transport Consultants Ltd.

The information, ideas and other intellectual property set out in this report and supporting technical appendices are the property of TPS Transport Consultants Ltd and are for the sole benefit of the client.

TPS Transport Consultants Ltd. requires that the information, ideas and other intellectual property set out in this report are:

- Not shared with third parties and particularly with direct or indirect competitors of TPS Transport Consultants Ltd;
- Not conveyed to other consultants or personnel without the prior approval of TPS Transport Consultants Ltd; and
- Not copied in part or in whole.

1. PROJECT SUMMARY

Unique Reference	P2636_20250627_Barugh Green Road, Barnsley_Stage 1 RSA
Prepared by	TPS Consultants
On behalf of	Avant

Scheme Title	Proposed access arrangement for residential development
Road Safety Audit	Stage 1

Prepared by	John Turner
Organisation	TPS Consultants
Date	27.06.25

I approve the RSA brief and instruct the RSA to take place on behalf of the Overseeing Organisation:	
Signed	
Name	Andrew Tunnacliffe
Organisation	Barnsley Metropolitan Borough Council
Date	

2. GENERAL DETAILS

Type of Scheme	Access arrangements for residential estate road from Barugh Green Road, Barnsley			
Select RSA Stage Highlight as appropriate >	1	2	3	4
Overseeing Organisation	BMBC			
Design Organisation	TPS Transport Consultants Ltd			
Police Contact Details	N/A at this stage			
RSA Team Membership (refer to RSA policy for team requirements – or speak to RSA team)	Haydn Vernals – Road Safety Audit Team Leader Sarah Vernals – Road safety Audit Team Member (CVs attached)			
Other Attendees	Nathan Copley - BMBC			
Terms of reference	RSA to GG119			

3. SCHEME DETAILS

Scheme Details	RSA to cover proposed access arrangement from Barugh Green Road, Barnsley
Design Standards	Access designed in line with DMRB
Design Speed	30mph
Speed Limit	30mph
Traffic Data	No traffic data available
Pedestrian Desire Lines	In order to facilitate desire lines for pedestrians, a refuge island is provided on Barugh Green Road to provide for north/south movements across Barugh Green Road
Collision Data	Collision data included in attached Transport Assessment
Previous RSA reports and audit responses	No previous RSA
List of drawing and supporting documents	RSA CVs Preliminary Access Arrangement Transport Assessment

Appendix A

Sevenairs CVs

Name: Haydn Vernals FCIHT FIHE CMILT MSoRSA

Profession: Traffic and Road Safety Engineering

Current Position: Director – Sevenairs Consulting Ltd

Specialisation: Traffic & Road Safety Engineering

Role on Audit: Team Leader

Professional Status

Sheffield Hallam University – Civil Engineering Construction and Highway Design

RoSPA 10 Day - Accident Investigation and Prevention

Road Safety Audit Certificate of Competency – Awarded Dec 2016

Employment

2017 to present	Sevenairs Consulting – Providing Road Safety related services to a variety of clients plus various longer-term roles with Kier (HE Area 7 Road Safety Team Leader), Sweco (Major HE Projects), NE Lincolnshire (Road Safety), Coventry CC (Road Safety and Covid-19), HS2 Ltd (Highways Technical Oversight) and TYP SA as Road Safety Specialist
2015 to 2017	Jacobs Manchester – Predominantly Smart Motorways and HE Major Projects
2012 to 2015	AECOM Leeds – Highways England, Regional and Local Authorities
2001 to 2012	Freelance Traffic & Road Safety Engineer – Strategic and Local Roads
1999 to 2001	WS Atkins – Highways Agency MAC Area 11
1988 to 1999	Sheffield City Council – Traffic Engineering and Major Projects

Experience

Chartered Transportation Professional with over three decades of experience covering a broad range of traffic, transportation and road safety commissions.

General Road Safety Engineering Experience

- Haydn is a Member of the Society of Road Safety Auditors with a background in road safety and traffic engineering. He has undertaken audits on highway schemes across the UK and holds a Road Safety Audit Certificate of Competency, is on the SoRSA committee and a CPD reviewer for both CIHT and SoRSA.
- Haydn has worked on collision investigation and prevention schemes, safety risk assessments, preliminary design of major schemes and extensive experience of traffic engineering on both the strategic and local roads networks for over three decades.
- Haydn's current roles are focused on operational safety, collision investigation, early-stage studies, road safety audit, walking, cycling & horse-riding assessment and staff development. Haydn brings a detailed knowledge of traffic and highway design on the motorway, trunk and local authority highway network, including aspects of geometric design, traffic signs, traffic signals, intelligent transport systems, vehicle restraint systems, carriageway construction methods and road safety techniques.
- Haydn has been previously involved in the geometric design of high-speed roads, including
 - Highways and traffic technical oversight on HS2 Phase 2b Lot 1 (2021-2022) specifically around the M56 J6 Proposals (value range £350-750M) for Manchester Airport HS2 Station.
 - Option development and costing of £150m worth of infrastructure improvements to the M621, A643 and key city centre roads on the south bank of the River Aire.
 - Junction/link design on the Birmingham Northern Relief Road (M6 Toll).

Road Safety Audit Experience

- Experience specifically related to audits of this type of work in last 12 months
 - Over 130 residential Road Safety Audits in the last 12 months, Stages 1-3, covering residential private access points, through small to large sized developments, to multi-development “new town” type sites.
 - A9 Tomatin to Moy Improvement, Highlands, **Transport Scotland** – Ongoing from May 2025, two reports to date – Acted as team member and part wrote reports. £150M provision of new dual carriageway, several new junctions and extensive works on the local access roads.
 - A63 Bramham, North Yorkshire, **National Highways** – RSA1 – Apr 2025 - Acted as team leader and wrote the report. Repurposed existing access for a new EV charging station and supporting food retail. Issues around wrong way collisions, signing and conspicuity.
 - A641 Corridor, Brighouse, Calderdale – RSA1 – Mar 2025 – Acted as team leader and wrote the reports. Active mode and bus priority scheme over four reports, major interventions to promote mode change, including new canal bridge, signal controlled junctions, off carriageway cycles etc.
 - Islay Woodhouse, Leicestershire – RSA1 – Feb 2025 - Acted as team leader and wrote the reports. New town south of East Midlands Airport, over four reports covering various elements, including a new A453 bypass route, improvements to existing junctions, cycling improvements etc.
 - Immingham Eastern Ro-Ro Terminal – RSA2 – Nov 2024 – Acted as team leader and wrote the report. New three berth terminal, customs and passport control, various issues raised around integration with the existing port facilities.
 - ORCS Pilot (On-street Residential Chargepoint Scheme), Sheffield – RSA2 – Oct 2024 – Acted as team leader and wrote the report. Six pilot sites for on street EV charging points, issues raised around accessibility and conspicuity.
 - Northallerton Link Road, North Yorkshire – RSA4 – Sep 2024 – Acted as team leader and wrote the report. Mile long link road, new issues raised around speed and surface water management.
 - Darnall-Attercliffe-City Centre, Transforming Cities, Sheffield – RSA2 – Aug/Sep 2024 – Acted as team leader and wrote the four reports. 6km of routes across several schemes, for active modes and bus priority. Kerbside routes, parallel crossings, traffic signals, major streetscape transformational works.
 - **HS2 Ph1 C2/C3 (TYPASA/EKFB)** – Multiple locations over 19 reports in Warwickshire, Northamptonshire, Buckinghamshire and West Northamptonshire – RSA1 & RSA2 – Jul 2022 to current. Acted as team leader and wrote the reports. New highway works, permanent highway works, various issues relating to geometry, vehicle restraint, maintenance access, pedestrians etc.
 - **HS2 Ph1 N8/N9 (BBV)** – Multiple locations over 18 reports between Staffordshire and Warwickshire – RSA1, RSA1/2 & RSA2 – Apr 2021 to Feb 2025 – Acted as team leader and wrote the reports. New highway works, construction access points and temporary highway works, issues relating to geometry, vehicle use and operational aspects.
 - 74 Road Safety Audits for Derbyshire County Council, Rotherham MBC, Sheffield City Council and Calderdale MBC – RSA Stages 1-3 – Apr 2022 to current. Public Realm, Bus Priority, Major Projects, Road Safety Improvements, Traffic Calming, Traffic Signals, Zebra Crossings, Parking & Active Mode Schemes. Various value works, up to multi-million pounds.
 - Eight Road Safety Audits on **Transport Scotland** Trunk Roads – RSA Stages 1-3 – Jul 2024 to current. A9 major project highlighted above, temp works, average speed cameras and development accesses.
- Completion of over 750 road safety audits in the last five years mostly as Team Leader
- Types of schemes audited as Team Leader/Member include:
 - Motorways and Trunk Roads
 - Local roads, level crossings, development site accesses
 - Roundabouts, Traffic signals and priority junctions
 - NMU facilities and public realm
- 113 Road Safety Audits completed to date in 2025 (106 as Team Leader)
- 217 Road Safety Audits completed in 2024 (175 as Team Leader)
- 160 Road Safety Audits completed in 2023 (138 as Team Leader)
- 113 Road Safety Audits completed in 2022 (88 as Team Leader)

- Experience specifically related to audits on trunk road projects beyond last 12 months
 - M42 Junction 10, **National Highways** – RSA1 – May 2024 – Acted as team leader and wrote report. New development access of the A5 with junction changes around the M42 Junction 10 roundabout. Issues raised around departures, landscaping, pedestrians, cycles, signs and lines.
 - A47 Major Improvements, Norfolk and Cambridgeshire (Tuddenham, Blofield, Thickethorne and Wansford) (**National Highways**) – 4x RSA2 – Aug/Sep 2022 – Acted as team leader and wrote the reports on these large multi-million improvement schemes. Works involve provision of new all purpose dual carriageways, grade separated junctions, roundabouts, local access roads and non-motorised user facilities. Extensive reports covering aspects of geometry, road restraint systems, NMU routing, tunnel emergency access, boundaries, visibility, etc
 - 75 Road Safety Audits for **Highways England** Area 7 – 2017-2018, including RSA Stages 1 to 4, and notably, two major trunk road improvements, one at A43 Towcester (circa £15m roundabout improvement) and another at A5 Old Stratford, a roundabout improvement.
 - A5-M1 Link Road, Northamptonshire (**Highways England**) – RSA3 – 2017 – Major new trunk road scheme and new motorway junction, two day audit acting as maintaining agent team member.
 - M6 J16-19 Smart Motorway (**Highways England**) – 2016 – 13 RSAs covering aspects of both the online and offline temporary traffic management for the project.
 - A1M Leeming to Barton Motorway (**Highways Agency**) – 2014 – Five RSAs for both mainline and local access road elements of this £400M project.

Full list of Road Safety Audits available on request

Road Safety Engineering Projects and Accident Studies

Last 2 years

- M1 south of J16, Northamptonshire – Safety Risk Assessment – Jun 2025 – Review of collision data linked to a Safety Risk Assessment for roadside advertising signs. 4 collisions over a 5yr period.
- A141 March, Cambridgeshire – Safety Risk Assessment – Jun 2025 – Review of collision data linked to a Safety Risk Assessment for traffic signal controlled junction. 14 collisions over a 10yr period.
- Bury, Cambridgeshire – Safety Risk Assessment – May 2025 – Review of collision data linked to a Safety Risk Assessment for highways works over a bridge structure for a utility company. 3 collisions over a 10yr period.
- Finham Park 2, Coventry – Collision Study – Sep 2024 – Study to support the development of measures for a new school site. 2km initial study scope, 197 collisions, filtered to focus on 23 secondary age casualties, various comparisons, statistical tests, conclusions and recommendations.
- A35/A31 Bare Regis – WCHAR – Mar 2024 – Collision analysis as part of a wider report for a service area site adjacent to the trunk road.
- A628 Penistone – Collision Analysis Study – Nov 2023 – Oversight study using CrashMap data to inform a local working group on potential road safety initiatives along the corridor, focused on pedestrian safety.
- A49 Lyde, Herefordshire – Safety Risk Assessment – Aug 2023 – Review of collisions as part of a GG104 report around a development access and on a trunk road with four departures to consider, three localised collisions and a view on approaches either side.

More than 2 years

- A6178 Sheffield Road, Rotherham – Safety Risk Assessment – Apr 2023 – Review of collisions as part of a GG104 report on use of narrow lanes on a major road to facilitate a cycle superhighway. Review looked at five/ten year timeframes and 16 collisions over an extended period to 1999, including five serious and one fatal.
- M56 J5-6 – HS2 Station – Aug 2021 - Review of collision data, specifically linked to weaving collisions, as current “assumption” contradicted issues highlighted in different report prepared by HV in 2015
- A18, Laceby, North East Lincs Council – Oct 2019 – Collision investigation and safety risk review to support the next stage of design in £1.8M safety scheme, with junction and verge works – 37 collisions over 5yrs
- A52 Safety Study Highways England Area 7 – Oct 2018 – Lead a team of two into an investigation of 423 collisions over 38km of the A52, identification of common themes, immediate interventions, speed limits and an asset review

- A1 Safety Study, Highways England Area 7 – Aug 2018 – Lead a team of three into an investigation of 504 collisions over 100km of the A1, identification of common themes, immediate interventions, long term aspirations and an asset review.
- Highways England Area 7 – Fatal Collision Reports – Mar-Nov 2017 – Package of reports to gather information pertaining to the highway and its environs and to review the collision history at 24 fatal collision sites in Area 7, including motorways, dual carriageways and single carriageways, a mix of casualty types, vehicles and collision types. Period of collision occurrence, Oct 2015 to Sep 2016

Formal Training (DMRB GG 119 or Equivalent)

RoSPA Road Safety Engineering Accident Investigation & Prevention (10 days) – Completed in 2013

Continual Professional Development (CPD) (DMRB GG 119 or Equivalent)

Upcoming CPD

- Jul 2025 – 5hrs – ITAI Crash Day, Ashbourne (ITAI) – Booked
- Jun 2025 – 8hrs – Day 2 Only – SoRSA Conference (CIHT/SoRSA) – Booked

Last 12 months (Current to Jun 2024) – **24hrs**

- Apr 2025 – 2hrs – Forensics Crash Scene Investigators Season 1 (Channel 5 TV)
- Feb 2025 – 6hrs – SoRSA East Midlands Workshop (CIHT/SoRSA)
- Feb 2025 – 1hr – Self-Reading – Review of updated GG104
- Jun 2024 – 10hrs – SoRSA Conference (CIHT/SoRSA)
- Jun 2024 – 5hrs – ITAI Crash Day, Ashbourne (ITAI)

Selected CPD beyond 12 months (Before Jun 2024)

- Feb 2024 – 6hrs – SoRSA East Midlands Workshop (CIHT/SoRSA)
- Feb 2024 – 2hrs – Self-Reading – Creating better streets: Inclusive and accessible places CIHT
- Feb 2024 – 3hrs – Self-Reading – Traffic Signs Manual – Chapter 6 – Traffic Signals
- Nov 2023 – 1hr – TRL Webinar, Speed we need a new narrative
- Nov 2023 – 1hr – Self-Reading – CYCLOPS Technical Guide
- Sep 2023 – 6hrs – SoRSA Scottish Workshop (CIHT/SoRSA)
- Jun 2023 – 12hrs – SoRSA Conference (CIHT/SoRSA)
- Feb 2023 – 4.0hrs – SoRSA East Midlands Workshop, including presentations on human issues, road safety audit process and workshops on problems and recommendations.
- Feb 2023 – 4.0hrs – Preparation and presentation to SoRSA East Midlands Workshop focused on Road Safety Audit and Human Issues, breaking down specific issues for various age groups
- Dec 2022 – 2.0hrs – Self-Reading – National Highways GG104 Hub (website and documents)
- Nov 2022 – 2.0hrs – Self-Reading – DfT Inclusive Mobility (Dec 2021)

CV Last Updated – 4th June 2025

Name: Sarah Vernals BAHonsQTS NPQH

Profession: Traffic and Road Safety Engineering

Current Position: Director – Sevenairs Consulting Ltd

Specialisation: Road Safety, Risk Assessment, Non-Motorised Modes and Child Safety

Role on Audit: Team Member

Professional Status

Leeds University – Bachelor of Arts in Education

RoSPA 10 Day - Accident Investigation and Prevention

Employment

2020 to present	Sevenairs Consulting – Providing Road Safety related services provided by Sevenairs to a variety of clients including local authorities, consultants and developers. Key workload includes Road Safety Audit, Safety Risk Assessment, WCHARs and collision analysis.
2024 to present	SEN Tutoring through a variety of end providers – Providing at home education for children between the ages of 5 and 16 with a mix of special educational needs, including complex family situations, autism, behaviour and long term serious illness.
2011 to 2023	Greenfield Primary (Barnsley MBC) – Assistant Head Teacher responsibility for inclusion, designated safeguarding lead, involvement in all aspects of school improvement. Line manager for SENDCo, family inclusion officer, looked after children designated teacher, Thrive Licenced Practitioner, behaviour lead, PSHCE coordinator, punctuality and attendance lead, performance management team leader, teaching student mentor, ECT mentor and Key Stage 1 coordinator
1999 to 2011	Altofts Junior School (Wakefield MDC) – Assistant Head Teacher, inclusion lead, SENDCo, gifted and talented coordinator, DT coordinator, performance management team leader and year 3 coordinator

Experience

Experienced Senior Leadership Professional with 24 years' experience in the educational field including risk assessment, child safeguarding and road safety education in the school environment. Begin within the road safety field in early 2020, supporting the collision study and safety risk assessment (GG104) workload with Sevenairs, before completing the RoSPA 10 Day Accident Investigation and Prevention training to facilitate her support for the Road Safety Audit (GG119) business stream.

General Road Safety Experience

- Sarah has worked on collision investigation data analysis since early 2020, feeding into transport assessments, safety risk assessments, and non-motorised studies on both the strategic and local roads networks.
- Sarah's current role with Sevenairs is focused mostly on supporting the road safety audit business stream, as a team member and writing reports, with work extending to safety risk assessments, walking, cycling and horse-riding assessment and review, and the collision analysis work associated with these.
- Sarah brings a strong background in child and vulnerable non-motorised users, through her two decades in senior leadership roles within primary education, is a parent of three children, has been a long-term carer for a parent in a wheelchair, is a keen cyclist and completes middle distance runs two to three times a week.

Road Safety Audit Experience

- Experience specifically related to audits of this type of work in last 12 months
 - Over 120 residential Road Safety Audits in the last 12 months, Stages 1-3, covering residential private access points, through small to large sized developments, to multi-development “new town” type sites.
 - A63 Bramham, North Yorkshire, **National Highways** – RSA1 – Apr 2025 - Acted as team member. Repurposed existing access for a new EV charging station and supporting food retail. Issues around wrong way collisions, signing and conspicuity.
 - A641 Corridor, Brighouse, Calderdale – RSA1 – Mar 2025 – Acted as team member. Active mode and bus priority scheme over four reports, major interventions to promote mode change, including new canal bridge, signal controlled junctions, off carriageway cycles etc.
 - Rosegarth Street, Boston – RSA1/2 – Jan 2025 – Acted as team member. Public realm S278 works linked to a larger off highway square.
 - Broad Street, Rotherham – RSA1 – Jan 2025 – Acted as team member. Bus priority and pedestrian signal controlled crossing.
 - Immingham Eastern Ro-Ro Terminal – RSA2 – Nov 2024 – Acted as team member. New three berth terminal, customs and passport control, various issues raised around integration with the existing port facilities.
 - ORCS Pilot (On-street Residential Chargepoint Scheme), Sheffield – RSA2 – Oct 2024 – Acted as team member. Six pilot sites for on street EV charging points, issues raised around accessibility and conspicuity.
 - Northallerton Link Road, North Yorkshire – RSA4 – Sep 2024 – Acted as team member. Mile long link road, new issues raised around speed and surface water management.
 - Darnall-Attercliffe-City Centre, Transforming Cities, Sheffield – RSA2 – Aug/Sep 2024 – Acted as team member. 6km of routes across several schemes, for active modes and bus priority. Kerbside routes, parallel crossings, traffic signals, major streetscape transformational works.
 - Spring Lane, Radcliffe, Bury – RSA1/RSA2 – Nov 2023/Sep 2024 – Acted as team member. Introduction of a CYCLOPS type junction for a new school development site.
 - M42 Junction 10, **National Highways** – RSA1 – May 2024 – Acted as team member. New development access of the A5 with junction changes around the M42 Junction 10 roundabout. Issues raised around departures, landscaping, pedestrians, cycles, signs and lines.
 - A63 Myton Moving Bridge Refurbishment, Hull (**National Highways**) – RSA3 – April 2024 – Acted as team member. The refurbishment of a swing bridge, changes to lane configuration and revised VRS.
 - **HS2 Ph1** N8/N9 (BBV) – RSA2 / RSA3 – Watling Street – Jan / Apr 2024 – Acted as team member. Works on former trunk road to bypass construction site for bridge over the HS2 mainline.
 - **HS2 Ph1** C2/C3 (TYPASA/EKFB) – Multiple locations over 12 reports in Warwickshire, Northamptonshire Buckinghamshire and West Northamptonshire – RSA1 & RSA2 – Aug 2023 to current. Acted as team member. New highway works, permanent highway works, various issues relating to geometry, vehicle restraint, maintenance access, pedestrians etc.
 - 70 Road Safety Audits for Derbyshire County Council, Rotherham MBC, Sheffield City Council and Calderdale MBC – RSA Stages 1-3 – May 2023 to current. Public Realm, Bus Priority, Major Projects, Road Safety Improvements, Traffic Calming, Traffic Signals, Zebra Crossings, Parking & Active Mode Schemes. Various value works, up to multi-million pounds.
- Types of schemes audited as Team Member include:
 - Trunk roads, local roads and development site accesses
 - Roundabouts, traffic signals and priority junctions
 - NMU facilities and public realm
 - Residential developments
- 106 Road Safety Audits completed to date in 2025 as Team Member
- 173 Road Safety Audits completed in 2024 as Team Member
- 124 Road Safety Audits completed in 2023 as Team Member
- 65 Road Safety Audits completed in 2022 as Team Member

Road Safety Projects and Accident Studies

Last 2 years

- Tilstock, Shropshire – Jun 2025 – Review of collision data linked to a WCHAR for a 70 home residential development planning application. 8 collisions over a 10yr period.
- A5 Grendon, Warwickshire – Sep 2024 – Review of collision data linked to a WCHAR for a 200 home residential development planning application. 14 collisions over a 5yr period.
- A49 Bayston Hill, Shropshire – Safety Risk Assessment – Sep 2023 – Review of collision data linked to a Safety Risk Assessment for Section Agreement works on a trunk road linked to a nearby residential development.

More than 2 years

- Flitwick, Bedfordshire – Safety Risk Assessment – Apr 2023 – Review of collision data linked to a Safety Risk Assessment for a residential development planning application.
- A5 Hockliffe, Bedfordshire – Safety Risk Assessment – Mar 2023 – Review of collision data linked to a Safety Risk Assessment for a Section Agreement on a residential access off a trunk road.
- Toddington – Safety Risk Assessment – January 2022 – Review of collision data linked to a Safety Risk Assessment for a planning application appeal linked to construction access routes through residential areas.
- M61 Junction 5 – Hulton Park Development – November 2021 – Supporting investigation of collisions at a motorway junction as part of a WCHAR document for a planning application.
- A1 Thornhaugh – Safety Risk Assessment – August 2021 – Review of collision data linked to a Safety Risk Assessment for a planning application for a new distribution centre adjacent to the A1 near Peterborough, review looking specifically into goods vehicle collisions.

Formal Training (DMRB GG 119 or Equivalent)

RoSPA Road Safety Engineering Accident Investigation & Prevention (10 days) – Completed over Christmas 2021

Continual Professional Development (CPD) (DMRB GG 119 or Equivalent)

Upcoming CPD

- Jul 2025 – 5.0hrs – ITAI Crash Day, Ashbourne (ITAI) – Booked
- Jun 2025 – 8.0hrs – Day 2 Only – SoRSA Conference (CIHT/SoRSA) – Booked

Last 12 months (Current to Jun 2024) – **23hrs**

- Apr 2025 – 2.0hrs – Forensics Crash Scene Investigators Season 1 (Channel 5 TV)
- Feb 2025 – 6.0hrs – SoRSA East Midlands Workshop (CIHT/SoRSA)
- Jun 2024 – 10.0hrs – SoRSA Conference (CIHT/SoRSA)
- Jun 2024 – 5.0hrs – ITAI Crash Day, Ashbourne (ITAI)




Beyond 12 months (Before Jun 2024)

- Feb 2024 – 6.0hrs – SoRSA East Midlands Workshop (CIHT/SoRSA)
- Feb 2024 – 3.0hrs – Self-Reading – Traffic Signs Manual – Chapter 6 – Traffic Signals
- Dec 2023 – 3.0hrs – Self-Reading – Think! – Review of educational resources (3-6, 7-12 & 13-16 age groups)
- Dec 2023 – 1.0hr – Self-Reading – Wales 20mph Impact Analysis - Agilysis
- Dec 2023 – 2.0hrs – Self-Reading – Older Drivers – Review of online resources (linked to ADI training)
- Nov 2023 – 1.0hr – TRL Webinar, Speed we need a new narrative
- Nov 2023 – 1.0hr – Self-Reading – CYCLOPS Technical Guide
- Nov 2023 – 2.0hrs – Crash Detectives Season 4 Ep 1-4 (BBC)
- Oct 2023 – 2.0hrs – Self-Reading – Buses in Urban Developments CIHT
- Oct 2023 – 2.0hrs – Self-Reading – Creating better streets: Inclusive and accessible places CIHT
- Feb 2023 to Current – 4.0hrs – Approved Driving Instructor Training (37hrs in car plus 10hrs reading)
- Dec 2021 – **10 days** – RoSPA Road Safety Engineering Accident Investigation & Prevention



Appendix B

Preliminary Access Arrangements



Standard Notes

- This drawing is to be read in conjunction with all relevant Architect's and Engineer's drawings and specification.
- This drawing should not be scaled.

Location Plan

Notes and Keys

17.12.24	A	Site layout plan updated to final layout	JA	JT
Date	Rev	Description	Drawn	Checked

TPS

ADDRESS: TPS Transport Consultants Ltd, Stonebridge Court, 151-153 Wakefield Road, Horbury, Wakefield, WF6 5HQ

T: 01934 444630
e: info@tpsconsultants.co.uk
www.tpsconsultants.co.uk

Project
Proposed residential development, Avant Homes, Barugh Green Road, Barnsley

Title
Proposed right turn ghost island general arrangement drawing

Status

INFORMATION

Scale @ A1	Date Created	Drawn	Checked
1:250	17.05.24	JT	JT
TPS Project Number		Revision	
P2636		B	
Drawing Number			
D - 1001			

Appendix C

Transport Assessment



TRANSPORT ASSESSMENT
BARUGH GREEN ROAD,
BARNSLEY
AVANT HOMES

December 2024

Document Issue Record

Project Name:	Barugh Green Road, Barnsley
TPS Project Reference:	P2636
Document Reference:	P2636_20241204_Barugh Green Road, Barnsley_Transport Assessment

Revision	Date	Author	Checked	Approved	Notes
0	17.12.24	JA	JT	JT	First draft for client review

Notice

This document has been prepared for the sole use of **Avant Homes** in accordance with the terms of the appointment under which it was produced. TPS Transport Consultants Ltd accepts no responsibility for any use of or reliance on the contents of this document by any third party. No part of this document shall be copied or reproduced in any form without prior written permission of TPS.

Contents

Chapter	Title	Page
1	INTRODUCTION	1
	Introduction	1
	Site Location and Development Proposals	1
	Planning History	2
	Report Structure	2
2	POLICY CONTEXT	4
	Introduction	4
	National Policy Context	4
	Local Policy	6
	Summary	9
3	ACCESSIBILITY	10
	Introduction	10
	Active Travel Options	10
	Local Public Transport Options	14
	Local Amenities	15
	Summary	16
4	LOCAL HIGHWAY NETWORK	17
	Introduction	17
	Highway Network	17
	Road Safety	19
5	TRIP GENERATION AND DISTRIBUTION	21
	Introduction	21
	Trip Generation	21
	Trip Distribution	21
	Materiality	22
6	OPERATIONAL ASSESSMENTS	23
	Introduction	23
	Base Survey Data	23
	NTM Adjusted Temporo Growth Rates	23
	Committed development	24
	Modelling Scenarios	24
	Operational Assessments	24
	Summary	26
7	PARKING AND SERVICING	27
	Introduction	27



Access.....	27
Parking	27
Servicing.....	28
8..... SUMMARY AND CONCLUSIONS	29
Conclusion.....	29

1. INTRODUCTION

INTRODUCTION

- 1.1 TPS Transport Consultants Ltd (TPS) has been appointed by Avant Homes to prepare a Transport Assessment to support a planning application for residential development on land to the south of the A635 Barugh Green Road, Barugh Green, Barnsley.

SITE LOCATION AND DEVELOPMENT PROPOSALS

- 1.2 The site is located approximately 700m east of Barugh Green village centre and 3.7km northwest of Barnsley town centre. The site is currently agricultural land and is bound by the A635 Barugh Green Road to the north, residential dwellings to the east and agricultural land to the south and west. The site location is shown in **Figure 1.1**, below, whilst the proposed site layout is provided at **Appendix A**.

Figure 1.1: Site Location



(Source: Google Earth)

- 1.3 This application is for 155 dwellings, on land that is allocated for mixed use within the Barnsley Local Plan (adopted 2019), forming part of a large allocation, Site MU1 – Land south of

Barugh Green Road, which has an indicative capacity of 1,700 dwellings and 43 ha of employment land.

- 1.4 Access to the site will be taken from a new priority T-junction with the A635 Barugh Green Road, on the northern boundary, which will be bound by 2m wide footways to both sides. To the east of the site access there will be a 3m wide shared footway/cycle path, running north-south through the site. Additional 3m wide footway/cycle paths run east-west to the north and south of the site, providing future cycle connections to the existing residential area to the east, as well as the wider allocation to the south and east, in line with the MU1 Masterplan.

PLANNING HISTORY

- 1.5 It is understood that an application was previously submitted (and withdrawn) for a residential development of 140 dwellings with associated landscaping, infrastructure and open space by Countryside Properties in 2020 (ref. 2020/0977) on the site. Prior to the application being withdrawn no comment was provided by the Local Highway Authority.
- 1.6 The proposed development site is allocated within the Barnsley Local Plan as MU1 "Land south of Barugh Green Road" which has an indicative capacity of 1,700 dwellings and has been outlined for mixed use development. Illustrated in the Barnsley West Masterplan Framework (MU1) prepared by Bond Bryan in 2019, there are four parcels of land (including the proposed site) under private ownership, with the remainder of the allocated site under Strata Sterling Barnsley West Ltd control. It should be noted that the remaining allocation is being developed separately by Strata Sterling Barnsley West Ltd and the scheme being brought forwards by Avant sits separate from the surrounding development of the allocation.

REPORT STRUCTURE

- 1.7 Following this introductory section:
- **Section 2** describes the transport planning policy context within which the proposals will be assessed;
 - **Section 3** details the accessibility of the development site by non-car modes;
 - **Section 4** describes the existing highway network in the vicinity of the development and key routes to the site, with reference to historic road safety records;

- **Section 5** summarises the trip generation associated with the development proposals, and the anticipated trip distribution, by way of a Gravity Model;
- **Section 6** considers the impact of the development at the site access junction and at other off-site junctions;
- **Section 7** considers the access, parking and servicing arrangements; and
- **Section 8** offers a summary and conclusion.

2. POLICY CONTEXT

INTRODUCTION

- 2.1 This section of the Transport Assessment identifies the policy context within which the development proposals have been assessed; it clearly demonstrates how the proposed development would contribute to the overarching principles of national and local transport policy.

NATIONAL POLICY CONTEXT

National Planning Policy Framework (NPPF – DCLG, December 2024)

- 2.2 The revised National Planning Policy Framework was published in December 2024 and sets out the government's planning policies for England and how these are expected to be applied. It continues to encourage development through the planning system, with a presumption in favour of sustainable development. Paragraph 109 states that "Transport issues should be considered from the earliest stages of plan-making and development proposals, using a vision-led approach to identify transport solutions that deliver well-designed, sustainable and popular places. This should involve:
- a) Making transport considerations an important part of early engagement with local communities;
 - b) Ensuring patterns of movement, streets, parking and other transport considerations are integral to the design of schemes, and contribute to making high quality places;
 - c) Understanding and addressing the potential impacts of development on transport networks; and
 - d) Realising opportunities from existing or proposed transport infrastructure, and changing transport technology and usage – for example in relation to the scale, location or density of development that can be accommodated;
 - e) Identifying and pursuing opportunities to promote walking, cycling and public transport use; and
 - f) Identifying, assessing and taking into account the environmental impacts of traffic and transport infrastructure – including appropriate opportunities for avoiding and mitigating any adverse effects, and for net environmental gains."

- 2.3 Paragraph 115 highlights that “in assessing sites that may be allocated for development in plans, or specific applications for development, it should be ensured that:
- a) Sustainable transport modes are priorities taking account of the vision for the site, the type of development and its location;
 - b) Safe and suitable access to the site can be achieved for all users;
 - c) The design of streets, parking areas, other transport elements and the content of associated standards reflects current national guidance, including the National Design Guide and the National Model Design Code; and
 - d) Any significant impacts from the development on the transport network (in terms of capacity and congestions), or on highway safety, can be cost effectively mitigated to an acceptable degree through a vision-led approach.”
- 2.4 Paragraph 116 states that: *“Development should only be prevented or refused on highways grounds if there would be an unacceptable impact on highway safety, or the residual cumulative impacts on the road network, following mitigation, would be severe, taking into account all reasonable future scenarios.”*
- 2.5 Paragraph 117 sets out that applications for development should:
- a) Give priority first to pedestrian and cycle movements, both within the scheme and with neighbouring areas; and second – so far as possible – to facilitating access to high quality public transport, with layouts that maximise the catchment area for bus or other public transport services, and appropriate facilities that encourage public transport use;
 - b) Address the needs of people with disabilities and reduced mobility in relation to all modes of transport;
 - c) Create places that are safe, secure and attractive – which minimise the scope for conflicts between pedestrians, cyclists and vehicles, avoid unnecessary street clutter, and respond to local character and design standards;
 - d) Allow for the efficient delivery of goods, and access by service and emergency vehicles; and
 - e) Be designed to enable charging of plug-in and other ultra-low emission vehicles in safe, accessible and convenient locations.

- 2.6 Paragraph 118 suggests that *“all developments that will generate significant amounts of movement should be required to provide a travel plan, and the application should be supported by a vision-led transport statement or transport assessment so that the likely impacts of the proposal can be assessed and monitored.”*
- 2.7 This Transport Assessment will demonstrate that the development proposals take full advantage of existing facilities for sustainable travel, locally, and will not result in a significant traffic impact on the local road network, therefore, satisfying the requirements of NPPF.

LOCAL POLICY

- 2.8 The proposed development site is allocated within the Barnsley Local Plan as MU1 “Land south of Barugh Green Road” which has an indicative capacity of 1,700 dwellings and has been outlined for mixed use development. For completeness, relevant policy set out in the Barnsley Local Plan is highlighted below.

Barnsley Local Plan (2019)

- 2.9 The Barnsley Local Plan was adopted in January 2019 and sets out the local planning policy for the future development of Barnsley up to 2033. The objectives of the Local Plan are:
- **Policy SD1 Presumption in Favour of Sustainable Development:** *When considering development proposals we will take a positive approach that reflects the presumption in favour of sustainable development contained in the National Planning Policy Framework. We will work proactively with applicants jointly to find solutions which mean that proposals can be approved wherever possible, and to secure development that improves the economic, social and environmental conditions in the area.*
 - **Policy T2 Accessibility Priorities:** *Working with city region partners and other stakeholders transport investment will be set out in Transport Strategy programmes focused on development-transport corridors as shown in the Accessibility Priorities diagram below to:*
 - *Improve sustainable transport and circulation in the Accessibility Improvement Zone (AIZ) area particularly between Principal Towns;*
 - *Implement transport network improvements as supported by evidence from modelling, feasibility studies, consultation, surveys, community engagement etc;*

- *Facilitate sustainable transport links to and from existing and proposed employment, interchange, community and leisure and tourism facilities in the borough, including provision for car parking and enhancing the non car role of the transport corridor shown on the Accessibility Priorities diagram as 'potential enhanced road based public transport corridor';*
- *Promote high quality public transport linking the AIZ to significant places of business, employment and national / international interchange in the Leeds - Sheffield City Region corridor including neighbouring Wakefield, Kirklees, Doncaster, Sheffield and Rotherham; and*
- *Improve direct public transport and freight links to London, Manchester, other Core Cities, national / international interchanges and the Humber ports.*
- **Policy T3 New Development and Sustainable Travel:** *New developments will be expected to:*
 - *Be located and designed to reduce the need to travel, be accessible to public transport and meet the needs of pedestrians and cyclists;*
 - *Provide at least the minimum levels of parking for cycles, motorbikes, scooters, mopeds and disabled people set out in the relevant Supplementary Planning Document;*
 - *Provide a transport statement or assessment in line with guidance set out in the National Planning Policy Framework and guidance including where appropriate regard for cross boundary local authority impacts; and*
 - *Provide a travel plan statement or a travel plan in accordance with guidance set out in the National Planning Policy Framework including where appropriate regard for cross boundary local authority impacts. Travel plans will be secured through a planning obligation or a planning condition.*
- **Policy T4 New Development and Transport Safety:** *New development will be expected to be designed and built to provide all transport users within and surrounding the development with safe, secure and convenient access and movement.*

If a development is not suitably served by the existing highway, or would create or add to problems of safety or the efficiency of the highway or any adjoining rail

infrastructure for users, we will expect developers to take mitigating action or to make a financial contribution to make sure the necessary improvements go ahead. Any contributions will be secured through a planning obligation or planning condition.

- **Policy T5 Reducing the Impact of Road Travel:** *We will reduce the impact of road travel by:
 - *Developing and implementing robust, evidence based air quality action plans to improve air quality; and*
 - *Working with our sub regional partners, fleet and freight operators to improve the efficiency of vehicles and goods delivery, and reduce exhaust emissions; and Implementing measures to ensure the current road system is used efficiently.**

2.10 Specifically in relation to the site allocation, the Local Plan sets out the following:

Site MU1 Land South of Barugh Green Road: *The site is proposed for mixed use predominantly for housing and employment. The indicative number of dwellings proposed on this site is 1,700. These are included in the housing numbers for Urban Barnsley in the housing chapter.*

43 ha of employment land is proposed on the site and is included in the employment land figures in the Urban Barnsley section of the Economy chapter.

The development will be subject to the production and approval of a Masterplan Framework covering the entire site which seeks to ensure that the employment land is developed within the plan period, that community facilities come forward before completion of the housing and that development is brought forward in a comprehensive manner.

Relevant to this document, the development will be expected to:

- Provide a primary school on the site;
- Provide on and off-site highway infrastructure works, including a link road (Claycliffe Link) and improvements at Junction 37 as necessary;
- Provide small scale convenience retail and community facilities in compliance with Local Plan policy TC5 Small Local Shops;
- Provide accessible public open space; and

- Protect the routes of the Public Rights of Way that cross the site, and make provision for these as part of any proposal.
- 2.11 The proposed development takes account of the overarching local policy context by providing a development that is well located to encourage trips by alternative modes of travel to the private car. The development is well located to take advantage of the facilities which have are committed to be developed as part of the wider site allocation, such as a primary school and local facilities.

SUMMARY

- 2.12 This Transport Assessment will demonstrate that the development proposals take full advantage of existing facilities for sustainable travel, locally, and will not result in a significant traffic impact on the local road network, therefore, satisfying the requirements of NPPF and local planning policy.

3. ACCESSIBILITY

INTRODUCTION

- 3.1 This section of the Transport Assessment describes the existing infrastructure that will facilitate and encourage trips to the site by foot, bicycle or public transport, rather than by car. It also considers any specific barriers to sustainable travel and how these are to be addressed, where appropriate.

ACTIVE TRAVEL OPTIONS

Pedestrian Access

- 3.2 The Institution for Highways and Transportation (IHT) offers guidance on walking distance by journey purpose, this is summarised in **Table 3.1** below.


Table 3.1: Walking Distances by Journey Type

Criteria	Town Centres	Commuting / School	Elsewhere
Desirable	200m	500m	400m
Acceptable	400m	1000m	800m
Preferred Maximum	800m	2000m	1200m

(Source: IHT)

- 3.3 As **Table 3.1** shows, a 2km catchment is the preferred maximum walking distance for 'commuting / school'. A 2km walking catchment from the site includes Barugh Green, Higham and Pogmoor. The 2km walking catchment is illustrated in **Figure 3.1**, overleaf.

Figure 3.1: 2km Walking Catchment



(Source: Open Street Map)


- 3.4 Pedestrian access to the site will be taken via the proposed vehicular access from the A635 Barugh Green Road, to the north. The access is to be bound 2m wide footways with dropped kerbs and tactile paving supporting pedestrian movement east-west along the south side of the carriageway, tying in with the existing provision along the A635 Barugh Green Road. As part of the proposed access junction works, a dropped kerb crossing with tactile paving and a pedestrian refuge island will be provided to the east of the access junction, facilitating north/south movement across Barugh Green Road.
- 3.5 To the east of the site access there will be a 3m wide shared footway/cycle path, running north-south through the site. Additional 3m wide footway/cycle paths run east-west to the north and south of the site, providing future cycle connections to the existing residential area to the east, as well as the wider allocation to the south and east, in line with the MUI Masterplan.

- 3.6 Approximately 200m east of the proposed site access, the A635 Barugh Green Road widens to two-lanes on approach to a 4-arm roundabout junction which gives access north via the A637 Claycliffe Road, east via Whaley Road and south, via the A635 Wilthorpe Road. Pedestrian refuge islands comprising dropped kerbs and tactile paving are in place on all approaches, assisting pedestrian movement across the junction. From this junction, the A635 Wilthorpe Road extends south before diverting east, towards Redbrook and Wilthorpe; residential dwellings take direct frontage access along both sides of the carriageway.
- 3.7 From the proposed site access, the A635 Barugh Green Road extends west for approximately 800m, after which the A635 forms the major arm of a signalised crossroads junction which gives access north towards Barugh Green and its associated residential area, south towards Higham and west towards Cawthorne.
- 3.8 Signalised pedestrian crossings are in place on all approaches, with footways and street lighting in place on both sides of the carriageway. Residential dwellings take direct frontage access in the vicinity of the junction, with traffic calming measures in the form of speed humps in place to the south, on Higham Common Road. Walking distances to a number of key local destinations from the site have been provided in the later part of this section.

Cycle Access

- 3.9 Cycling can be a substitute for car trips, particularly those of up to 5km, as well as forming part of longer journeys by public transport. Cycling, therefore, plays an important role in reducing the need to travel by car. As well as the areas encompassed in the walking catchment shown in **Figure 3.1**, the 5km cycling catchment area from the site includes the entirety of Barnsley town centre, Darton, Silkstone, Cawthorne, Pogmoor, and parts of Athersley and Monk Bretton. **Figure 3.2**, overleaf, illustrates a 5km cycle catchment from the site.

Figure 3.2: 5km Cycle Catchment



(Source: Open Street Map)

- 3.10 The site is located an approximate 15 minute cycle distance from Barnsley town centre, making this a realistic alternative to the private car for accessing employment and leisure facilities in the town centre, as well as additional public transport services, at the bus station and rail station.
- 3.11 The closest National Cycle Network (NCN) Route to the site is NCN Route 62 which can be accessed in a 5km (24-minute) cycle via Redbrook Road. As previously mentioned, there will be 3m wide shared footway/cycle paths throughout the site, providing future cycle connections to the existing residential area to the east, as well as the wider allocation to the south and east, in line with the MU1 Masterplan.
- 3.12 It is recognised that there are limited formal cycle facilities and routes in the vicinity of the site. However, given the location of the site in relation to Barnsley town centre, it is expected that some residents could utilise cycling for access to employment and leisure opportunities.

LOCAL PUBLIC TRANSPORT OPTIONS

Local Bus Services

- 3.13 There are a number of bus stops located within a short walk of the site. The closest bus stop are located on the A635 Barugh Green Road, approximately 100m / 140m east of the site. Located on both sides of the carriageway, both stops comprise a shelter, seating and timetable information. Further stops can be accessed approximately 400m / 450m west of the site in Barugh Green village centre. **Figure 3.3**, below, illustrates the location of these bus stops, whilst **Table 3.2** summarises the services that can be accessed from them.

Figure 3.3: Bus Stop Locations



(Source: Google Maps)

Table 3.2: Bus Services

Service		Frequency		
		Weekday	Saturday	Sunday
Barugh Green Road				
93	Barnsley (Circular)	60 mins	60 mins	-
94/A	Barnsley Interchange – Denby Dale	120 mins	120 mins	-
95	Barnsley Interchange – Kexborough	30 mins	30 mins	-
96B	Barnsley Interchange – Wakefield	120 mins	120 mins	120 mins
353	Barnsley - Holmfirth	3 Services*	-	-

412	Barnsley – Penistone Grammar	1 AM / 1 PM Service	-	-
-----	------------------------------	---------------------	---	---

(Source: Public Transport Operator Websites) *Monday, Wednesday, Friday

- 3.14 As can be seen in **Table 3.2**, Barugh Green Road is served by 3-5 separate services per hour, providing services to key destinations, including Barnsley and Wakefield. It is, therefore, expected that residents could make use of the bus services to travel to destinations further afield.

Rail Services

- 3.15 The closest railway station to the site is Barnsley Interchange, located approximately 3.8km southeast of the site. Accessible in an 18-minute cycle via Redbrook Road, Barnsley Interchange can also be accessed in a 24-minute multi-modal journey via 93/94/95/96 bus service, accessible on the A635 Barugh Green Road.
- 3.16 Barnsley Interchange benefits a range of facilities such as accessible ticket machines, waiting rooms and 24 cycle storage spaces. The station benefits from level access to both platforms 2 platforms and is served by approximately 6-8 trains per hour, to a number of regional and national destinations such as Sheffield, Huddersfield and Leeds. **Table 3.3**, below, outlines the key destinations accessible from Barnsley Interchange.

Table 3.3: Barnsley Interchange railway station services

Destination	Frequency
Leeds (Express) via Wakefield Kirkgate	2 per hour
Leeds (Slow) via Castleford	1 per hour
Sheffield (Express) via Meadowhall	1 per hour
Sheffield (Slow) via Wombwell, Chapeltown and Meadowhall	1 per hour
Huddersfield	1 per hour
Nottingham via Sheffield & Chesterfield	1 per hour
Lincoln via Sheffield, Worksop & Gainsborough Lea	1 per hour

(Source: National Rail)

LOCAL AMENITIES

- 3.17 **Table 3.4**, overleaf, provides a summary of local facilities which are available within the preferred maximum walking (2km) or cycling (5km) distances of the site, with approximate journey times. Measurements are taken from the proposed vehicular access, from the A635 Barugh Green Road. It should be noted that, as part of the wider MU1 'Land South of Barugh Green Road' site, the proposals comprise mixed use development and are expected to

provide a primary school, small scale convenience, retail and community facilities and employment facilities, as well as access to public open space. The above will all be accessible within the preferred maximum walking and cycling distances.

Table 3.4: Local Facilities

Amenity	Distance	Walk Time	Cycle Time
Chestnut Tree Pub/Restaurant	350m	5 mins	1 min
Aldi	400m	5 mins	1 min
Claycliffe Business Park	400m	6 mins	2 mins
Barugh Green Recreation Ground	650m	10 mins	3 mins
One Stop Convenience Store	700m	10 mins	3 mins
Little India Takeaway	750m	11 mins	3 mins
Cawthorne Road Day Nursery	800m	12 mins	4 mins
Barugh Surgery	850m	13 mins	4 mins
Pharmacy Wise Barugh Green	900m	13 mins	4 mins
Barugh Green Primary School	1.0km	15 mins	5 mins
The Royal Pub & Restaurant	1.2km	17 mins	4 mins
Sainsbury's Local	1.2km	19 mins	8 mins
The Crown & Anchor Pub	1.3km	18 mins	5 mins
Vets for Pets	1.3km	19 mins	5 mins
The Pantry & Gawber Post Office	1.4km	22 mins	10 mins
Barnsley Business & Innovation Centre	1.5km	22 mins	9 mins
Higham Cricket Club	1.5km	23 mins	9 mins
Tesco Express	1.6km	23 mins	9 mins
Barnsley Hospital	1.8km	28 mins	12 mins
Summer Lane Primary School	2.0km	32 mins	12 mins

(Source: Google Maps)

SUMMARY

- 3.18 Overall, it is considered that there are good opportunities for walking and cycling locally, with good pedestrian infrastructure surrounding the site. Furthermore, bus stops are located within convenient walking distance of the site, giving access to local and regional destinations. Trips to and from the proposed development site can, therefore, easily be undertaken by sustainable modes of travel, thus minimising the use of the private car.

4. LOCAL HIGHWAY NETWORK

INTRODUCTION

- 4.1 This section of the Transport Assessment considers the nature of the existing highway network and summarises the historic accident data for the area surrounding the site.

HIGHWAY NETWORK

- 4.2 A description is provided below of the local highway network in the immediate vicinity of the site; for ease, it is also shown in **Figure 4.1**.

Figure 4.1: Existing Highway Network



(Source: Google Maps)

- 4.3 The site will take vehicular access from the A635 Barugh Green Road, on the northern boundary, via a new priority T-junction. The development proposals comprise a 3m wide right turn ghost island for eastbound vehicles, with a pedestrian refuge island comprising dropped kerbs and tactile paving proposed to the east of the junction, supporting pedestrian movement north-south. In the vicinity of the site, the A635 Barugh Green Road is subject to a 40mph speed limit and is bound by footways and street lighting on both sides.
- 4.4 Running broadly east-west for approximately 1.0km, the A635 Barugh Green Road forms the major arm of a number of priority T-junctions along its length. Approximately 280m west of the proposed site access, Cannon Way takes access to the north, giving access north

towards Claycliffe Business Park; access is supported by a right turn ghost island with central hatching separating the two lanes of traffic. It should be noted that as part of the access proposals for the Strata Sterling Barnsley West scheme this junction is currently being converted to a four arm roundabout junction, with the southern arm providing access to the wider allocation and Cannon Way forming the northern arm of the junction.

- 4.5 Approximately 200m east of the proposed site access, the A635 Barugh Green Road widens to two lanes on approach to a 4-arm roundabout junction which gives access north onto the A637 Claycliffe Road, west via Whaley Road and south via the A635 Wilthorpe Road. The A637 Claycliffe Road is approximately 10m wide and subject to a 40mph speed limit, with footways and street lighting on both sides.
- 4.6 From the roundabout junction, Claycliffe Road runs broadly north-south for approximately 900m, forming the major arm of a number of priority T-junctions along its length. Whaley Road extends east, away from the roundabout junction, giving access to industrial units and business units on both sides, along its length. Approximately 9m wide, Whaley Road is bound by footways and street lighting on both sides, with no parking restrictions in place along its length.
- 4.7 To the south of the roundabout junction, the A635 Wilthorpe Road extends south before diverting east, towards Redbrook and Wilthorpe. In the vicinity of the junction, the carriageway is bound by footways and street lighting on both sides, with residential dwellings taking direct frontage access to the south. After 150m, the A635 Wilthorpe Road forms the major arm of a priority T-junction with Redbrook Road which extends south towards Gawber and Barnsley town centre. Bound by footways and street lighting on both sides, the carriageway is subject to a 40mph speed limit.
- 4.8 Back to the site, the A635 Barugh Green Road extends west for approximately 800m before forming the major arm of a signalised crossroads junction which gives access north towards Barugh Green, south towards Higham and west towards Cawthorne. Bound by footways and street lighting on all approaches, pedestrian movement across the junction is supported by dropped kerbs and tactile paving. Double yellow line parking restrictions are in place in the vicinity of the junction. From this junction, the A635 extends west onto Cawthorne Road which is bound by footways and street lighting on both sides; the footway on the south side of the carriageway terminates after 90m. Past this point, signage indicates vehicles are subject to national speed limit, as the carriageway extends west towards Cawthorne.

ROAD SAFETY

- 4.9 Accident data for the most recent 5-year period (2018 - 2022) has been obtained from www.crashmap.co.uk for the highway network surrounding the site. Crashmap offers a definitive map of the official road collision statistics. The locations and severity of the recorded accidents in the vicinity of the site are shown in **Figure 4.2**, below.

Figure 4.2: Study Area



(Source: Google Maps)

- 4.10 As can be seen in Figure 4.2, a total of 11 accidents have been recorded within the study area, within the most recent 5-year period, which equates to an average of 2.2 accidents per year. Of the accidents recorded, 8 were slight in nature and 3 were serious; no fatalities were recorded in the study area. It is also noted that there have been no accidents on the site frontage or on the western approach to the roundabout to the east, suggesting there are no existing highway safety issues which would be exacerbated by the development proposals.
- 4.11 At the A635 / A637 roundabout junction, to the east of the site, 4 accidents were recorded across the study period. The first accident occurred in 2018 and involved 1 goods vehicle, resulting in 1 casualty suffering slight injuries. Two separate accidents involving 2 cars were recorded in 2020, the first of which resulted in 2 casualties suffering slight injuries; the other accident resulted in 1 casualty suffering serious injuries. To the south of the roundabout junction, an accident in 2022 involving 2 cars and 1 pedal cyclist led to 1 casualty suffering slight injuries.

- 4.12 Along the A635 Barugh Green Road, 2 serious accidents were recorded. The first involved 2 cars and resulted in 2 casualties, whereas the other involved 1 car and 1 pedestrian. At the signalised crossroads junction, to the west of the site, 5 accidents were recorded across the most recent 5-year study period. All 5 accidents were slight in nature, with 2 recorded in 2018, 2 in 2019 and 1 in 2022. Of these accidents, only 1 accident (in 2018) involved a vulnerable road user, as 1 pedal cyclist suffered slight injuries in a collision with a car.
- 4.13 It is considered that the level of accidents recorded over the most recent 5-year period does not indicate that there is an existing road safety issue in the vicinity of the site.

5. TRIP GENERATION AND DISTRIBUTION

INTRODUCTION

5.1 This section of the Transport Assessment considers the likely trip generation associated with the development proposals.

TRIP GENERATION

5.2 The TRICS database has been interrogated to derive representative trip rates associated with the proposed 155 dwellings; the following TRICS parameters have been selected:

- Land Use: Residential, Houses Privately Owned;
- Range: 80 – 250 dwellings;
- Date Range: 01/01/2016 – 14/11/2023; and
- Location: Edge of Town.

5.3 **Table 5.1** summarises the trip rates and resultant trip generation, whilst the full TRICS output is provided at **Appendix B**.

Table 5.1: Proposed Vehicle Trip Rates

Land Use	AM Peak			PM Peak		
	Arrival	Departure	Two-Way	Arrival	Departure	Two-Way
Trip Rates	0.139	0.364	0.503	0.330	0.154	0.484
Trip Generation	22	56	78	51	24	75

(Source: TRICS)

5.4 As can be seen in **Table 5.1**, the proposals are anticipated to generate 78 two-way vehicle trips in the AM peak hour and 75 two-way vehicle trips in the PM peak hour.

TRIP DISTRIBUTION

5.5 Trips associated with the development have been assigned to the local highway network using a gravity model, based on Census 2011 'Location of usual residence and place of work' data for MSOA Barnsley 012, within which the site is located.

5.6 **Table 5.2**, overleaf, provides a summary of the gravity model, whilst the full calculations are provided at **Appendix C**.

Table 5.2: Summary of Trip Distribution

Route	%
A635 Barugh Green Road (Eastbound)	85%
A635 Barugh Green Road (Westbound)	15%

(Source: Consultant Calculation)

5.7 Flow diagrams provided at **Appendix D** show the distribution in **Table 5.2**, represented graphically. This trip distribution has been applied to the predicted trip generation, set out in **Table 5.1** and can be seen on the flow diagram attached at **Appendix E**.

MATERIALITY

5.8 In order to understand the potential impact of the development proposals, an assessment of the uplift in movements as a consequence of the development has been undertaken and is presented in **Table 5.3**, below.

Table 5.3: Number of Development Trips by Junction

Junction	Trips	
	AM	PM
Site Access / A635 Barugh Green Road	78	75
A637 / A635 / Whaley Road Roundabout Junction	67	64
A635 / B6428 / Higham Common Road Crossroads Junction	11	11

(Source: Consultant Calculation)

5.9 A threshold of an uplift of 30 or more two-way trips associated with the development proposals has been applied; beyond this, the uplift in traffic flows is not be considered to be material. Based upon this threshold, and for completeness, further consideration will be given to the impact of the development proposals at the following junctions:

- Site Access / A635 Barugh Green Road;
- A637 / A635 / Whaley Road Roundabout Junction; and
- A635 / B6428 / Higham Common Road Crossroads Junction.

6. OPERATIONAL ASSESSMENTS

INTRODUCTION

- 6.1 This section of the Transport Assessment considers operational assessments of a number of junctions on the local road network, as well as the site access. These assessments also consider the development traffic associated with the proposed development of the surrounding MU1 application, as detailed in the Transport Assessment prepared by Fore Consulting in support of the wider application.
- 6.2 In order to demonstrate the impact of the development proposals on highway capacity. The following junctions have been assessed:
- Site Access / A635 Barugh Green Road;
 - A637 / A635 / Whaley Road Roundabout Junction; and
 - A635 / B6428 / Higham Common Road Crossroads Junction.
- 6.3 Beyond the junctions modelled as part of this Transport Assessment, traffic will dissipate, such that it doesn't have a material impact elsewhere on the highway network.

BASE SURVEY DATA

- 6.4 Fully classified turning counts have been undertaken at the junctions identified above, in order to establish a base situation. The surveys covered the periods 07:00-10:00 and 15:30-18:30 and were undertaken on Tuesday 29th April 2024. An analysis of the turning count data identifies that the network peak hours were 07:45-08:45 and 16:45-17:45. The full traffic count data is included at **Appendix F**, and the surveyed peak hour flows are illustrated in figures provided at **Appendix G**.

NTM ADJUSTED TEMPRO GROWTH RATES

- 6.5 In line with industry standard methodology, the assessments consider a design year 5 years post submission of the planning application, i.e. 2029. To establish the likely traffic growth from the 2024 base traffic flows to a future year of 2029, the TEMPro 7.2 table "RTF 2018 Scenario 1" has been used. The growth factors obtained from Tempro are set out in **Table 6.1**, overleaf.

Table 6.1: NTM Adjusted TEMPro Growth Rates

Amenity	AM	PM
Barnsley 012	1.0394	1.0398

(Source: TEMPro)

COMMITTED DEVELOPMENT

- 6.6 To account for the development traffic associated with the proposed development of the surrounding MU1 application, the total development flows for the application, included within the Fore Consulting Transport Assessment (7 July 2021) have been utilised. These have been taken from Figures 41 and 42, submitted as part of the Transport Assessment. Flow diagrams are provided at **Appendix H**, which show traffic growth to the design year of 2029 and include the committed development as described above.
- 6.7 It should be noted that this presents a robust assessment of background traffic growth, given that the traffic associated with MU1 would be taken account of in the Tempro background traffic growth rates, owing to its allocation in the Local Plan.

MODELLING SCENARIOS

- 6.8 The junctions will be assessed in the following scenarios:
- 2029 AM and PM Base + Committed Development; and
 - 2029 AM and PM Base + Committed Development + Development.

OPERATIONAL ASSESSMENTS

- 6.9 Junctions modelling software has been used to assess the operation of all junctions; the results are summarised for each junction in turn below. The Junctions software predicts the Ratio of Flow to Capacity (RFC) on each approach / turning movement and resultant queue length. An RFC value of less than 0.85 is generally accepted as indicating that a junction is operating within theoretical capacity. The full model outputs are provided at **Appendix I**.
- 6.10 With regard to signalised junctions, Linsig predicts the Degree of Saturation (DoS) as a percentage. A DoS of 90% is considered to demonstrate the practical capacity of a junction.

Site Access / A635 Barugh Green Road

6.11 The results of the assessments of the proposed site access on the A635 Barugh Green Road is summarised in **Table 6.2**, below; the full modelling outputs are provided at **Appendix I**.

Table 6.2: Site Access / A635 Barugh Green Road

	2029 Base + CD + Dev			
	AM Peak		PM Peak	
	RFC	Q	RFC	Q
Site Access – Barugh Green Road East	0.02	0.02	0.01	0.01
Site Access – Barugh Green Road West	0.16	0.19	0.08	0.08
Barugh Green Road West - Site Access	0.01	0.01	0.02	0.02

(Source: Junctions 8)

6.12 As can be seen in **Table 6.2**, the junction of the Site Access / A635 Barugh Green Road is predicted to operate well within its practical capacity (RFC of less than 0.85) in both the AM and PM peak hours.

Barugh Green Road / Wilthorpe Road Roundabout Junction

6.13 **Table 6.3**, below, summarises the results of the assessment of the Barugh Green Road / Wilthorpe Road roundabout junction; the full modelling outputs are provided at **Appendix I**.

Table 6.3: Barugh Green Road / Wilthorpe Road Roundabout Junction

	2029 Base + CD				2029 Base + CD + Dev			
	AM Peak		PM Peak		AM Peak		PM Peak	
	RFC	Q	RFC	Q	RFC	Q	RFC	Q
Claycliffe Road	0.77	3.26	0.68	2.05	0.79	3.70	0.69	2.20
Whaley Road	0.18	0.22	0.24	0.32	0.19	0.23	0.25	0.33
Wilthorpe Road	0.79	3.64	0.84	5.04	0.80	3.86	0.87	6.06
Barugh Green Road	0.63	1.66	0.47	0.86	0.67	2.03	0.48	0.93

(Source: Junctions 8)

6.14 As can be seen in **Table 6.3**, the Barugh Green Road / Wilthorpe Road roundabout junction is predicted to operate broadly in line with its practical capacity (RFC of less than 0.85), with a maximum RFC of 0.87 with the development trips, in the design year of 2029. It is not considered that this impact is material, as the RFC is still below 1.00.

A635 / B6428 / Higham Common Road Crossroads Junction

6.15 **Table 6.4**, below, summarises the results of the operational assessment of the A635 / B6428 / Higham Common Road crossroads junction, in the 2029 Base and the 2029 Base + Development scenarios, in order to demonstrate the impact of the development traffic on this junction. The full outputs are attached at **Appendix I**.

Table 6.4: A635 / B6428 / Higham Common Road Crossroads Junction

	2029 Base				2029 Base + Dev			
	AM Peak		PM Peak		AM Peak		PM Peak	
	DoS	MMQ	DoS	MMQ	DoS	MMQ	DoS	MMQ
Barugh Lane	68.4%	9.7	79.7%	11.4	68.4%	9.7	79.7%	11.4
Barugh Green Road	50.0%	6.6	81.5%	13.9	50.5%	6.7	81.8%	14.0
Higham Common Road	42.7%	5.5	55.9%	8.2	43.0%	5.6	56.5%	8.4
Cawthorne Road	70.5%	12.8	64.3%	10.2	70.7%	12.8	64.6%	10.3
PRC over all lanes	27.7%		10.5%		27.3%		10.0%	

(Source: Junction 8)

6.16 As can be seen in **Table 6.3**, the A635 / B6428 / Higham Common Road crossroads junction is predicted to operate within its practical capacity (DoS of less than 90%) with or without the development trips, in the design year of 2029. The development will have limited impact on the PRC over all lanes and does not result in a material impact in queueing at the junction.

SUMMARY

6.17 Capacity assessments have been undertaken for the site access junction and two off-site junctions where the development proposals were identified as potentially having a material impact. The modelling results indicate all junctions will operate satisfactorily in both peak hours with the addition of the development traffic in both the current and design year and, therefore, no mitigation works are required.

7. PARKING AND SERVICING

INTRODUCTION

- 7.1 This section of the Transport Assessment considers the proposed access, parking and servicing arrangements for the site.

ACCESS

- 7.2 As can be seen from the site layout, provided at **Appendix A**, vehicular access to the proposed development will be taken via a new priority T-junction on the northern boundary of the site, from the A635 Barugh Green Road. Shown at **Appendix J**, the proposed access benefits from a 3m wide right turn ghost island and has been designed in line with the requirements of DMRB. Bound by 2m wide footways and street lighting on both sides, dropped kerbs and tactile paving are proposed to support pedestrian movement east-west, along the A635 Barugh Green Road. Furthermore, a pedestrian refuge island comprising dropped kerbs and tactile paving is proposed immediately east of the proposed access junction, supporting pedestrian movement north-south.
- 7.3 Illustrated at **Appendix J**, 2.4m x 120m visibility splays can be achieved from the Site Access junction, in line with the posted 40mph speed limit along the A635 Barugh Green Road.
- 7.4 The primary route into the site will be 6m wide and bound by a 3m wide footway/cycle path to the east, separated from the carriageway by a grass verge, and a 2m wide footway to the west. Past this point, internal carriageways will be 5.5m wide, with dwellings taking direct frontage access on both sides; the carriageway is to be bound by footways and street lighting along its length. Additional 3m wide footway/cycle paths run east-west to the north and south of the site, providing future cycle connections to the existing residential area to the east, as well as the wider allocation to the south and east, in line with the MUI Masterplan.

PARKING

- 7.5 Car parking standards for new residential developments in Barnsley are provided by Barnsley Metropolitan Borough Council in the Barnsley Local Plan – Parking SPD, adopted in November 2019. For ease, these can be summarised as:
- 1-2 bed dwellings – 1 car parking space;
 - 3+ bed dwellings – 2 car parking spaces;

- 1 visitor car parking space per 4 dwellings (subject to layout); and
- 1 secure cycle space per dwelling (in garage or separate secure covered area within plot).

7.6 As can be seen from the layout provided at **Appendix A**, parking is provided in line with local parking standards; an electric vehicle charging point is provided for each dwelling in line with building regulations. With regard to cycle parking, where dwellings do not provide a garage, alternative storage will be provided in the form of a shed, in order to provide sufficient space(s) per dwelling.

SERVICING

General Servicing and Refuse Collection

7.7 General servicing and delivery access will take place from the roadside within the development. Waste will be collected by Barnsley Metropolitan Borough Council. The swept path analysis, undertaken within the site, shown on drawings provided at **Appendix K**, demonstrates that an 11.6m refuse vehicle can manoeuvre within the site and egress in forward gear, with minimum requirement for reversing throughout the site.

Fire Appliance Access

7.8 Manual for Streets (MfS) indicates that the access requirements for emergency vehicles are generally stipulated by the Fire Service. Table 8 of the *The Building Regulations 2010 'Fire Safety' (2019 edition, incorporating the 2020 amendments) Approved Document B Section 5 'Access and Facilities for the Fire and Rescue Service'*, sets out that a minimum road width of 3.7m be provided and turning facilities should be provided in any cul-de-sac that is more than 20m long. Fire tenders and emergency vehicles will access the site from the A635 Barugh Green Road and can utilise the turning arrangements throughout the site to access all dwellings.

8. SUMMARY AND CONCLUSIONS

8.1 TPS has prepared this Transport Assessment to accompany a planning application for 155 dwellings on land to the south of the A635 Barugh Green Road, Barugh Green, Barnsley. The following summarises the key points:

- The proposals are in keeping with both the local and national transport and land use planning policy agenda;
- The site benefits from good connectivity with the facilities and amenities in the surrounding area, with numerous opportunities for residents to travel by non-car modes;
- An analysis of historic accident data suggests that there are no accident trends that might be exacerbated by the addition of development-related traffic;
- The development proposals are anticipated to generate 78 two-way vehicle trips in the AM peak hour and 75 two-way vehicle trips in the PM peak hour;
- Operational assessments of the local highway network have been undertaken based on 2024 survey data, growthed to a future year of 2029 using NTM adjusted TEMPro growth rates;
- The operational assessments demonstrate that the local highway network has sufficient capacity to accommodate the predicted trip generation of the proposed development;
- The servicing arrangements for the site have been considered; swept path analysis has been undertaken of the proposed turning heads throughout the site, to demonstrate that a refuse vehicle will be able to enter and exit the site in forward gear; and
- Car parking and cycle parking will be provided to meet Barnsley Metropolitan Borough Council parking standards.

CONCLUSION

8.2 Given the above, it is considered that the proposals will not result in a 'severe residual cumulative impact' (the test set out in NPPF); indeed, they will be complementary to the prevailing policy agenda. As such, there are no substantive highway grounds why the development should not be granted consent.



TPS Transport Consultants Ltd

Stonebridge Court, 151-153 Wakefield Road, Horbury, Wakefield, WF4 5HQ

Tel: 01924 664638

Web: www.tpsconsultants.co.uk

REPORT APPENDICES

Appendix A

Indicative Site Layout

Appendix B

TRICS Output

TRIP RATE CALCULATION SELECTION PARAMETERS:

Land Use : 03 - RESIDENTIAL
Category : A - HOUSES PRIVATELY OWNED
TOTAL VEHICLES

Selected regions and areas:

02	SOUTH EAST	
	ES EAST SUSSEX	5 days
	EX ESSEX	2 days
	HC HAMPSHIRE	4 days
	HF HERTFORDSHIRE	1 days
	KC KENT	2 days
	SC SURREY	1 days
	SP SOUTHAMPTON	1 days
	WB WEST BERKSHIRE	1 days
	WS WEST SUSSEX	6 days
04	EAST ANGLIA	
	NF NORFOLK	8 days
	SF SUFFOLK	1 days
06	WEST MIDLANDS	
	ST STAFFORDSHIRE	1 days
11	SCOTLAND	
	AS ABERDEENSHIRE	1 days

Primary Filtering selection:

Parameter: No of Dwellings
 Actual Range: 80 to 250 (units:)
 Range Selected by User: 80 to 250 (units:)

Parking Spaces Range: All Surveys Included

Parking Spaces per Dwelling Range: All Surveys Included

Bedrooms per Dwelling Range: All Surveys Included

Percentage of dwellings privately owned: All Surveys Included

Public Transport Provision:

Selection by: Include all surveys

Date Range: 01/01/16 to 14/11/23

Selected survey days:

Monday	7 days
Tuesday	9 days
Wednesday	10 days
Thursday	6 days
Friday	2 days

Selected survey types:

Manual count	30 days
Directional ATC Count	4 days

Selected Locations:

Edge of Town	34
--------------	----

Selected Location Sub Categories:

Residential Zone	30
Village	1
Out of Town	3

Inclusion of Servicing Vehicles Counts:

Servicing vehicles Included	8 days - Selected
Servicing vehicles Excluded	37 days - Selected

Secondary Filtering selection:

Use Class:

C3	34 days
----	---------

Population within 500m Range:

All Surveys Included

Population within 1 mile:

1,001 to 5,000	4 days
5,001 to 10,000	8 days
10,001 to 15,000	11 days
15,001 to 20,000	6 days
20,001 to 25,000	5 days

Population within 5 miles:

5,001 to 25,000	7 days
25,001 to 50,000	2 days
50,001 to 75,000	3 days
75,001 to 100,000	4 days
100,001 to 125,000	2 days
125,001 to 250,000	12 days
250,001 to 500,000	4 days

Car ownership within 5 miles:

0.6 to 1.0	6 days
1.1 to 1.5	24 days
1.6 to 2.0	4 days

Secondary Filtering selection (Cont.):

Travel Plan:

Yes	26 days
No	8 days

PTAL Rating:

No PTAL Present	33 days
2 Poor	1 days

Covid-19 Restrictions	Yes	At least one survey within the selected data set was undertaken at a time of Covid-19 restrictions
-----------------------	-----	--

LIST OF SITES relevant to selection parameters

1	AS-03-A-02 FARROCHIE ROAD STONEHAVEN	MIXED HOUSES	ABERDEENSHIRE
	Edge of Town Residential Zone Total No of Dwellings:	131	
	Survey date: WEDNESDAY	20/04/22	Survey Type: MANUAL
2	ES-03-A-03 SHEPHAM LANE POLEGATE	MIXED HOUSES & FLATS	EAST SUSSEX
	Edge of Town Residential Zone Total No of Dwellings:	212	
	Survey date: MONDAY	11/07/16	Survey Type: MANUAL
3	ES-03-A-05 RATTLE ROAD NEAR EASTBOURNE STONE CROSS	MIXED HOUSES & FLATS	EAST SUSSEX
	Edge of Town Residential Zone Total No of Dwellings:	99	
	Survey date: WEDNESDAY	05/06/19	Survey Type: MANUAL
4	ES-03-A-07 NEW ROAD HAILSHAM HELLINGLY	MIXED HOUSES & FLATS	EAST SUSSEX
	Edge of Town Residential Zone Total No of Dwellings:	91	
	Survey date: THURSDAY	07/11/19	Survey Type: MANUAL
5	ES-03-A-08 WRESTWOOD ROAD BEXHILL	MIXED HOUSES & FLATS	EAST SUSSEX
	Edge of Town Residential Zone Total No of Dwellings:	110	
	Survey date: WEDNESDAY	12/10/22	Survey Type: MANUAL
6	ES-03-A-10 WATERGATE BEXHILL-ON-SEA	MIXED HOUSES & FLATS	EAST SUSSEX
	Edge of Town Residential Zone Total No of Dwellings:	139	
	Survey date: THURSDAY	28/09/23	Survey Type: MANUAL
7	EX-03-A-02 MANOR ROAD CHIGWELL GRANGE HILL	DETACHED & SEMI-DETACHED	ESSEX
	Edge of Town Residential Zone Total No of Dwellings:	97	
	Survey date: MONDAY	27/11/17	Survey Type: MANUAL

LIST OF SITES relevant to selection parameters (Cont.)

8	EX-03-A-03 KESTREL GROVE RAYLEIGH	MIXED HOUSES	ESSEX
	Edge of Town Residential Zone Total No of Dwellings:	123	
	<i>Survey date: MONDAY</i>	<i>27/09/21</i>	<i>Survey Type: MANUAL</i>
9	HC-03-A-28 EAGLE AVENUE WATERLOOVILLE LOVEDEAN	MIXED HOUSES & FLATS	HAMPSHIRE
	Edge of Town Residential Zone Total No of Dwellings:	125	
	<i>Survey date: MONDAY</i>	<i>08/11/21</i>	<i>Survey Type: MANUAL</i>
10	HC-03-A-33 CROW LANE RINGWOOD CROW	MIXED HOUSES & FLATS	HAMPSHIRE
	Edge of Town Residential Zone Total No of Dwellings:	195	
	<i>Survey date: TUESDAY</i>	<i>04/07/23</i>	<i>Survey Type: MANUAL</i>
11	HC-03-A-34 STONEHAM LANE EASTLEIGH	MIXED HOUSES & FLATS	HAMPSHIRE
	Edge of Town Residential Zone Total No of Dwellings:	243	
	<i>Survey date: TUESDAY</i>	<i>14/11/23</i>	<i>Survey Type: MANUAL</i>
12	HC-03-A-36 HAVANT ROAD EMSWORTH	MIXED HOUSES & FLATS	HAMPSHIRE
	Edge of Town Residential Zone Total No of Dwellings:	145	
	<i>Survey date: TUESDAY</i>	<i>12/09/23</i>	<i>Survey Type: MANUAL</i>
13	HF-03-A-03 HARE STREET ROAD BUNTINGFORD	MIXED HOUSES	HERTFORDSHIRE
	Edge of Town Residential Zone Total No of Dwellings:	160	
	<i>Survey date: MONDAY</i>	<i>08/07/19</i>	<i>Survey Type: MANUAL</i>
14	KC-03-A-04 KILN BARN ROAD AYLESFORD DITTON	SEMI-DETACHED & TERRACED	KENT
	Edge of Town Residential Zone Total No of Dwellings:	110	
	<i>Survey date: FRIDAY</i>	<i>22/09/17</i>	<i>Survey Type: MANUAL</i>

LIST OF SITES relevant to selection parameters (Cont.)

15	KC-03-A-10 HEADCORN ROAD STAPLEHURST	MIXED HOUSES		KENT
	Edge of Town Residential Zone Total No of Dwellings:		106	
	Survey date: <i>TUESDAY</i>		<i>09/05/23</i>	<i>Survey Type: MANUAL</i>
16	NF-03-A-13 BEAUFORT WAY GREAT YARMOUTH BRADWELL	MIXED HOUSES		NORFOLK
	Edge of Town Residential Zone Total No of Dwellings:		198	
	Survey date: <i>TUESDAY</i>		<i>11/09/18</i>	<i>Survey Type: DIRECTIONAL ATC COUNT</i>
17	NF-03-A-15 SILFIELD ROAD WYMONDHAM	MIXED HOUSES & FLATS		NORFOLK
	Edge of Town Out of Town Total No of Dwellings:		235	
	Survey date: <i>THURSDAY</i>		<i>20/09/18</i>	<i>Survey Type: DIRECTIONAL ATC COUNT</i>
18	NF-03-A-32 HUNSTANTON ROAD HUNSTANTON	MIXED HOUSES & FLATS		NORFOLK
	Edge of Town Residential Zone Total No of Dwellings:		164	
	Survey date: <i>WEDNESDAY</i>		<i>21/09/22</i>	<i>Survey Type: DIRECTIONAL ATC COUNT</i>
19	NF-03-A-33 LONDON ROAD ATTLEBOROUGH	MIXED HOUSES		NORFOLK
	Edge of Town Residential Zone Total No of Dwellings:		143	
	Survey date: <i>THURSDAY</i>		<i>29/09/22</i>	<i>Survey Type: MANUAL</i>
20	NF-03-A-34 NORWICH ROAD SWAFFHAM	MIXED HOUSES		NORFOLK
	Edge of Town Out of Town Total No of Dwellings:		80	
	Survey date: <i>TUESDAY</i>		<i>27/09/22</i>	<i>Survey Type: MANUAL</i>
21	NF-03-A-35 REPTON AVENUE NORWICH	MIXED HOUSES & FLATS		NORFOLK
	Edge of Town Residential Zone Total No of Dwellings:		116	
	Survey date: <i>WEDNESDAY</i>		<i>28/09/22</i>	<i>Survey Type: MANUAL</i>

LIST OF SITES relevant to selection parameters (Cont.)

22	NF-03-A-39 HEATH DRIVE HOLT	MIXED HOUSES		NORFOLK
	Edge of Town Residential Zone Total No of Dwellings:		212	
	<i>Survey date: TUESDAY</i>		<i>27/09/22</i>	<i>Survey Type: MANUAL</i>
23	NF-03-A-48 BRANDON ROAD SWAFFHAM	MIXED HOUSES		NORFOLK
	Edge of Town Residential Zone Total No of Dwellings:		181	
	<i>Survey date: THURSDAY</i>		<i>19/09/19</i>	<i>Survey Type: DIRECTIONAL ATC COUNT</i>
24	SC-03-A-05 REIGATE ROAD HORLEY	MIXED HOUSES		SURREY
	Edge of Town Residential Zone Total No of Dwellings:		207	
	<i>Survey date: MONDAY</i>		<i>01/04/19</i>	<i>Survey Type: MANUAL</i>
25	SF-03-A-10 LOVETOFTS DRIVE IPSWICH WHITEHOUSE	TERRACED & SEMI-DETACHED		SUFFOLK
	Edge of Town Residential Zone Total No of Dwellings:		149	
	<i>Survey date: TUESDAY</i>		<i>22/06/21</i>	<i>Survey Type: MANUAL</i>
26	SP-03-A-02 BARNFIELD WAY NEAR SOUTHAMPTON HEDGE END	MIXED HOUSES & FLATS		SOUTHAMPTON
	Edge of Town Out of Town Total No of Dwellings:		250	
	<i>Survey date: TUESDAY</i>		<i>12/10/21</i>	<i>Survey Type: MANUAL</i>
27	ST-03-A-07 BEACONSIDE STAFFORD MARSTON GATE	DETACHED & SEMI-DETACHED		STAFFORDSHIRE
	Edge of Town Residential Zone Total No of Dwellings:		248	
	<i>Survey date: WEDNESDAY</i>		<i>22/11/17</i>	<i>Survey Type: MANUAL</i>
28	WB-03-A-03 DORKING WAY READING CALCOT	MIXED HOUSES		WEST BERKSHIRE
	Edge of Town Residential Zone Total No of Dwellings:		108	
	<i>Survey date: FRIDAY</i>		<i>09/09/22</i>	<i>Survey Type: MANUAL</i>

LIST OF SITES relevant to selection parameters (Cont.)

29	WS-03-A-08	MIXED HOUSES	WEST SUSSEX
	ROUNDSTONE LANE		
	ANGMERING		
	Edge of Town		
	Residential Zone		
	Total No of Dwellings:	180	
	Survey date: THURSDAY	19/04/18	Survey Type: MANUAL
30	WS-03-A-12	MIXED HOUSES	WEST SUSSEX
	MADGWICK LANE		
	CHICHESTER		
	WESTHAMPNETT		
	Edge of Town		
	Village		
	Total No of Dwellings:	152	
	Survey date: WEDNESDAY	16/06/21	Survey Type: MANUAL
31	WS-03-A-13	MIXED HOUSES & FLATS	WEST SUSSEX
	LITTLEHAMPTON ROAD		
	WORTHING		
	WEST DURRINGTON		
	Edge of Town		
	Residential Zone		
	Total No of Dwellings:	197	
	Survey date: WEDNESDAY	23/06/21	Survey Type: MANUAL
32	WS-03-A-14	MIXED HOUSES	WEST SUSSEX
	TODDINGTON LANE		
	LITTLEHAMPTON		
	WICK		
	Edge of Town		
	Residential Zone		
	Total No of Dwellings:	117	
	Survey date: WEDNESDAY	20/10/21	Survey Type: MANUAL
33	WS-03-A-17	MIXED HOUSES & FLATS	WEST SUSSEX
	SHOPWHYKE ROAD		
	CHICHESTER		
	Edge of Town		
	Residential Zone		
	Total No of Dwellings:	86	
	Survey date: WEDNESDAY	01/03/23	Survey Type: MANUAL
34	WS-03-A-19	MIXED HOUSES & FLATS	WEST SUSSEX
	TURNERS HILL ROAD		
	EAST GRINSTEAD		
	Edge of Town		
	Residential Zone		
	Total No of Dwellings:	92	
	Survey date: MONDAY	15/05/23	Survey Type: MANUAL

TRIP RATE for Land Use 03 - RESIDENTIAL/A - HOUSES PRIVATELY OWNED

TOTAL VEHICLES

Calculation factor: 1 DWELLS

BOLD print indicates peak (busiest) period

Time Range	ARRIVALS			DEPARTURES			TOTALS		
	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate
00:00 - 01:00									
01:00 - 02:00									
02:00 - 03:00									
03:00 - 04:00									
04:00 - 05:00									
05:00 - 06:00									
06:00 - 07:00									
07:00 - 08:00	34	153	0.090	34	153	0.293	34	153	0.383
08:00 - 09:00	34	153	0.139	34	153	0.364	34	153	0.503
09:00 - 10:00	34	153	0.139	34	153	0.174	34	153	0.313
10:00 - 11:00	34	153	0.132	34	153	0.149	34	153	0.281
11:00 - 12:00	34	153	0.140	34	153	0.149	34	153	0.289
12:00 - 13:00	34	153	0.154	34	153	0.155	34	153	0.309
13:00 - 14:00	34	153	0.163	34	153	0.159	34	153	0.322
14:00 - 15:00	34	153	0.167	34	153	0.197	34	153	0.364
15:00 - 16:00	34	153	0.256	34	153	0.176	34	153	0.432
16:00 - 17:00	34	153	0.264	34	153	0.163	34	153	0.427
17:00 - 18:00	34	153	0.330	34	153	0.154	34	153	0.484
18:00 - 19:00	34	153	0.267	34	153	0.140	34	153	0.407
19:00 - 20:00	1	97	0.062	1	97	0.052	1	97	0.114
20:00 - 21:00	1	97	0.031	1	97	0.021	1	97	0.052
21:00 - 22:00									
22:00 - 23:00									
23:00 - 24:00									
Total Rates:			2.334			2.346			4.680

Parameter summary

Trip rate parameter range selected: 80 - 250 (units:)
 Survey date date range: 01/01/16 - 14/11/23
 Number of weekdays (Monday-Friday): 38
 Number of Saturdays: 0
 Number of Sundays: 0
 Surveys automatically removed from selection: 7
 Surveys manually removed from selection: 0

Appendix C

Gravity Model


155 Dwellings

Route		%	AM			PM			AADT
			IN	OUT	2-WAY	IN	OUT	2-WAY	24 HR
			0.139	0.364	0.503	0.33	0.154	0.484	-
			22	56	78	51	24	75	698
1	North at Roundabout	21%	4	12	16	11	5	16	145
2	East at Roundabout	0%	0	0	0	0	0	0	0
3	South at Roundabout	65%	14	36	50	33	15	49	451
4	North at Crossroads	1%	0	1	1	1	0	1	8
5	West at Crossroads	5%	1	3	4	3	1	4	36
6	South at Crossroads	8%	2	5	6	4	2	6	58
		100%	22	56	78	51	24	75	698

Junctions		%	IN	OUT	2-WAY	IN	OUT	2-WAY	AADT
1	Roundabout (to the east)	85%	18	48	67	44	20	64	596
2	Crossroads (to the west)	15%	3	8	11	7	3	11	102

Appendix D


Trip Distribution Flows




Client: Avant Homes	Project: Barugh Green, Barnsley	Title: Trip Distribution		Number: P2636	Revision: -	Date Dec-24	Checked JA		
						Design JA	Approved JA		

Appendix E

Trip Generation Flows



Client: Avant Homes	Project: Barugh Green, Barnsley	Title: Trip Generation AM		Number: P2636	Revision: -	Date: Dec-24	Checked: JA	
						Design: JA	Approved: JA	



Client: Avant Homes	Project: Barugh Green, Barnsley	Title: Trip Generation PM		Number: P2636	Revision: -	Date: Dec-24	Checked: JA	
							Design: JA	Approved: JA


Appendix F

Count Data


<https://www.dropbox.com/scl/fo/pe1c3q966udmt1nir14ff/AIDGIDUuREGDwxZ - N378f0?rlkey=gs73fx7ed45e6pukstxifdja8&dl=0>

Appendix G


2024 Base and CD Flows




Client:	Project:	Title:		Number:	Revision:	Date	Dec-24	Checked	JA
Avant Homes	Barugh Green, Barnsley	2024 Base AM		P2636	-	Design	JA	Approved	JA



Client: Avant Homes	Project: Barugh Green, Barnsley	Title: 2024 Base PM		Number: P2636	Revision: -	Date: Dec-24	Checked: JA		
						Design: JA	Approved: JA		




Client: Avant Homes	Project: Barugh Green, Barnsley	Title: Committed Development AM		Number: P2636	Revision: -	Date: Dec-24	Checked: JA	
						Design: JA	Approved: JA	




Client: Avant Homes	Project: Barugh Green, Barnsley	Title: Committed Development PM		Number: P2636	Revision: -	Date: Dec-24	Checked: JA		
						Design: JA	Approved: JA		

Appendix H


Committed Development (CD), 2029 Base + CD and 2029 Base CD +
Development Flows




Client: Avant Homes	Project: Barugh Green, Barnsley	Title: 2029 Base + Committed Development AM		Number: P2636	Revision: -	Date: Dec-24	Checked: JA	
						Design: JA	Approved: JA	



Client: Avant Homes	Project: Barugh Green, Barnsley	Title: 2029 Base + Committed Development PM		Number: P2636	Revision: -	Date: Dec-24	Checked: JA		
						Design: JA	Approved: JA		



Client: Avant Homes	Project: Barugh Green, Barnsley	Title: 2029 Base + Committed Development + Development AM		Number: P2636	Revision: -	Date	Dec-24	Checked	JA
						Design	JA	Approved	JA



Client: Avant Homes	Project: Barugh Green, Barnsley	Title: 2029 Base + Committed Development + Development PM		Number: P2636	Revision: -	Date	Dec-24	Checked	JA
						Design	JA	Approved	JA

Appendix I


Junction Modelling Output

Full Input Data And Results
Full Input Data And Results


User and Project Details

Project:	Barugh Green Road
Title:	Barugh Green Crossroads
Location:	
Client:	Avant Homes
Checked By:	JT
Checked By Date:	JT
Additional detail:	
File name:	Barugh Green Road_Cawthorne Road.lsg3x
Author:	JT
Company:	TPS Consultants Ltd
Address:	

Network Layout Diagram



Phase Diagram



Phase Input Data

Phase Name	Phase Type	Assoc. Phase	Street Min	Cont Min
A	Traffic		7	7
B	Traffic		7	7
C	Traffic		7	7
D	Traffic		7	7
E	Pedestrian		7	7
F	Pedestrian		7	7
G	Pedestrian		7	7
H	Pedestrian		7	7

Full Input Data And Results


Phase Intergrens Matrix

		Starting Phase							
		A	B	C	D	E	F	G	H
Terminating Phase	A	6	-	6	6	6	6	6	6
	B	6	6	-	6	6	6	6	6
	C	-	6	6	-	6	6	6	6
	D	6	-	6	6	-	6	6	6
	E	6	6	6	6	-	-	-	-
	F	6	6	6	6	-	-	-	-
	G	6	6	6	6	-	-	-	-
	H	6	6	6	6	-	-	-	-

Phases in Stage

Stage No.	Phases in Stage
1	A C
2	B D
3	E F G H

Stage Diagram



Phase Delays

Term. Stage	Start Stage	Phase	Type	Value	Cont value
There are no Phase Delays defined					

Prohibited Stage Change

		To Stage		
		1	2	3
From Stage	1	6	6	6
	2	6	6	6
	3	6	6	6

Full Input Data And Results

Give-Way Lane Input Data

Junction: Unnamed Junction											
Lane	Movement	Max Flow when Giving Way (PCU/Hr)	Min Flow when Giving Way (PCU/Hr)	Opposing Lane	Opp. Lane Coeff.	Opp. Mvmnts.	Right Turn Storage (PCU)	Non-Blocking Storage (PCU)	RTF	Right Turn Move up (s)	Max Turns in Intergreen (PCU)
1/1 (Barugh Lane)	7/1 (Right)	1439	0	3/1	1.09	To 5/1 (Ahead) To 7/1 (Left)	2.00	2.00	0.50	2	2.00
2/1 (Barugh Green Road (E))	5/1 (Right)	1439	0	4/1	1.09	To 5/1 (Left) To 6/1 (Ahead)	2.00	4.00	0.50	2	2.00
3/1 (Higham Common Road)	6/1 (Right)	1439	0	1/1	1.09	To 6/1 (Left) To 8/1 (Ahead)	2.00	2.00	0.50	2	2.00
4/1 (Cawthorne Road)	8/1 (Right)	1439	0	2/1	1.09	To 7/1 (Ahead) To 8/1 (Left)	2.00	3.00	0.50	2	2.00

Full Input Data And Results

Lane Input Data

Junction: Unnamed Junction												
Lane	Lane Type	Phases	Start Disp.	End Disp.	Physical Length (PCU)	Sat Flow Type	Def User Saturation Flow (PCU/Hr)	Lane Width (m)	Gradient	Nearside Lane	Turns	Turning Radius (m)
1/1 (Barugh Lane)	O	B	2	3	60.0	Geom	-	3.50	0.00	Y	Arm 6 Left	9.00
											Arm 7 Right	17.00
											Arm 8 Ahead	Inf
2/1 (Barugh Green Road (E))	O	C	2	3	60.0	Geom	-	4.30	0.00	Y	Arm 5 Right	15.00
											Arm 7 Ahead	Inf
											Arm 8 Left	12.00
3/1 (Higham Common Road)	O	D	2	3	60.0	Geom	-	3.00	0.00	Y	Arm 5 Ahead	Inf
											Arm 6 Right	15.00
											Arm 7 Left	10.00
4/1 (Cawthorne Road)	O	A	2	3	60.0	Geom	-	4.50	0.00	Y	Arm 5 Left	10.00
											Arm 6 Ahead	Inf
											Arm 8 Right	16.00
5/1 (Barugh Lane)	U		2	3	60.0	Inf	-	-	-	-	-	-
6/1 (Barugh Green Road (E))	U		2	3	60.0	Inf	-	-	-	-	-	-
7/1 (Cawthorne Road)	U		2	3	60.0	Inf	-	-	-	-	-	-
8/1 (Higham Common Road)	U		2	3	60.0	Inf	-	-	-	-	-	-

Traffic Flow Groups

Flow Group	Start Time	End Time	Duration	Formula
1: '2029 Base + CD AM'	08:00	09:00	01:00	
2: '2029 Base + CD PM'	16:00	17:00	01:00	
3: '2029 Base + CD + Development AM'	08:00	09:00	01:00	
4: '2029 Base + CD + Development PM'	16:00	17:00	01:00	

Full Input Data And Results

Scenario 1: '2029 Base AM' (FG1: '2029 Base + CD AM', Plan 1: 'Network Control Plan 1')

Traffic Flows, Desired

Desired Flow :

	Destination					
	A	B	C	D	Tot.	
Origin	A	0	57	204	137	398
	B	62	0	83	191	336
	C	173	58	0	39	270
	D	138	361	57	0	556
	Tot.	373	476	344	367	1560

Traffic Lane Flows

Lane	Scenario 1: 2029 Base AM
Junction: Unnamed Junction	
1/1	398
2/1	336
3/1	270
4/1	556
5/1	373
6/1	476
7/1	367
8/1	344

Full Input Data And Results

Lane Saturation Flows

Junction: Unnamed Junction								
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat Flow (PCU/Hr)	Flared Sat Flow (PCU/Hr)
1/1 (Barugh Lane)	3.50	0.00	Y	Arm 6 Left	9.00	14.3 %	1864	1864
				Arm 7 Right	17.00	34.4 %		
				Arm 8 Ahead	Inf	51.3 %		
2/1 (Barugh Green Road (E))	4.30	0.00	Y	Arm 5 Right	15.00	18.5 %	1949	1949
				Arm 7 Ahead	Inf	56.8 %		
				Arm 8 Left	12.00	24.7 %		
3/1 (Higham Common Road)	3.00	0.00	Y	Arm 5 Ahead	Inf	64.1 %	1836	1836
				Arm 6 Right	15.00	21.5 %		
				Arm 7 Left	10.00	14.4 %		
4/1 (Cawthorne Road)	4.50	0.00	Y	Arm 5 Left	10.00	24.8 %	1973	1973
				Arm 6 Ahead	Inf	64.9 %		
				Arm 8 Right	16.00	10.3 %		
5/1 (Barugh Lane Lane 1)	Infinite Saturation Flow						Inf	Inf
6/1 (Barugh Green Road (E) Lane 1)	Infinite Saturation Flow						Inf	Inf
7/1 (Cawthorne Road Lane 1)	Infinite Saturation Flow						Inf	Inf
8/1 (Higham Common Road Lane 1)	Infinite Saturation Flow						Inf	Inf

Scenario 2: '2029 Base PM' (FG2: '2029 Base + CD PM', Plan 1: 'Network Control Plan 1')

Traffic Flows, Desired

Desired Flow :

	Destination					
	A	B	C	D	Tot.	
Origin	A	0	60	196	158	414
B	111	0	69	337	517	
C	272	61	0	57	390	
D	176	219	58	0	453	
Tot.	559	340	323	552	1774	

Full Input Data And Results

Traffic Lane Flows

Lane	Scenario 2: 2029 Base PM
Junction: Unnamed Junction	
1/1	414
2/1	517
3/1	390
4/1	453
5/1	559
6/1	340
7/1	552
8/1	323

Lane Saturation Flows

Junction: Unnamed Junction								
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat Flow (PCU/Hr)	Flared Sat Flow (PCU/Hr)
1/1 (Barugh Lane)	3.50	0.00	Y	Arm 6 Left	9.00	14.5 %	1858	1858
				Arm 7 Right	17.00	38.2 %		
				Arm 8 Ahead	Inf	47.3 %		
2/1 (Barugh Green Road (E))	4.30	0.00	Y	Arm 5 Right	15.00	21.5 %	1970	1970
				Arm 7 Ahead	Inf	65.2 %		
				Arm 8 Left	12.00	13.3 %		
3/1 (Higham Common Road)	3.00	0.00	Y	Arm 5 Ahead	Inf	69.7 %	1846	1846
				Arm 6 Right	15.00	15.6 %		
				Arm 7 Left	10.00	14.6 %		
4/1 (Cawthorne Road)	4.50	0.00	Y	Arm 5 Left	10.00	38.9 %	1929	1929
				Arm 6 Ahead	Inf	48.3 %		
				Arm 8 Right	16.00	12.8 %		
5/1 (Barugh Lane Lane 1)				Infinite Saturation Flow			Inf	Inf
6/1 (Barugh Green Road (E) Lane 1)				Infinite Saturation Flow			Inf	Inf
7/1 (Cawthorne Road Lane 1)				Infinite Saturation Flow			Inf	Inf
8/1 (Higham Common Road Lane 1)				Infinite Saturation Flow			Inf	Inf

Full Input Data And Results

Scenario 3: '2029 Base + Dev AM ' (FG3: '2029 Base + CD + Development AM', Plan 1: 'Network Control Plan 1')

Traffic Flows, Desired

Desired Flow :

	Destination					
	A	B	C	D	Tot.	
Origin	A	0	57	204	137	398
	B	62	0	88	194	344
	C	173	60	0	39	272
	D	138	363	57	0	558
	Tot.	373	480	349	370	1572

Traffic Lane Flows

Lane	Scenario 3: 2029 Base + Dev AM
Junction: Unnamed Junction	
1/1	398
2/1	344
3/1	272
4/1	558
5/1	373
6/1	480
7/1	370
8/1	349

Full Input Data And Results

Lane Saturation Flows

Junction: Unnamed Junction								
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat Flow (PCU/Hr)	Flared Sat Flow (PCU/Hr)
1/1 (Barugh Lane)	3.50	0.00	Y	Arm 6 Left	9.00	14.3 %	1864	1864
				Arm 7 Right	17.00	34.4 %		
				Arm 8 Ahead	Inf	51.3 %		
2/1 (Barugh Green Road (E))	4.30	0.00	Y	Arm 5 Right	15.00	18.0 %	1948	1948
				Arm 7 Ahead	Inf	56.4 %		
				Arm 8 Left	12.00	25.6 %		
3/1 (Higham Common Road)	3.00	0.00	Y	Arm 5 Ahead	Inf	63.6 %	1835	1835
				Arm 6 Right	15.00	22.1 %		
				Arm 7 Left	10.00	14.3 %		
4/1 (Cawthorne Road)	4.50	0.00	Y	Arm 5 Left	10.00	24.7 %	1973	1973
				Arm 6 Ahead	Inf	65.1 %		
				Arm 8 Right	16.00	10.2 %		
5/1 (Barugh Lane Lane 1)	Infinite Saturation Flow						Inf	Inf
6/1 (Barugh Green Road (E) Lane 1)	Infinite Saturation Flow						Inf	Inf
7/1 (Cawthorne Road Lane 1)	Infinite Saturation Flow						Inf	Inf
8/1 (Higham Common Road Lane 1)	Infinite Saturation Flow						Inf	Inf

Scenario 4: '2029 Base + Dev PM' (FG4: '2029 Base + CD + Development PM', Plan 1: 'Network Control Plan 1')

Traffic Flows, Desired

Desired Flow :

	Destination					
	A	B	C	D	Tot.	
Origin	A	0	60	196	158	414
B	111	0	71	339	521	
C	272	65	0	57	394	
D	176	221	58	0	455	
Tot.	559	346	325	554	1784	

Full Input Data And Results

Traffic Lane Flows


Lane	Scenario 4: 2029 Base + Dev PM
Junction: Unnamed Junction	
1/1	414
2/1	521
3/1	394
4/1	455
5/1	559
6/1	346
7/1	554
8/1	325

Lane Saturation Flows

Junction: Unnamed Junction								
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat Flow (PCU/Hr)	Flared Sat Flow (PCU/Hr)
1/1 (Barugh Lane)	3.50	0.00	Y	Arm 6 Left	9.00	14.5 %	1858	1858
				Arm 7 Right	17.00	38.2 %		
				Arm 8 Ahead	Inf	47.3 %		
2/1 (Barugh Green Road (E))	4.30	0.00	Y	Arm 5 Right	15.00	21.3 %	1969	1969
				Arm 7 Ahead	Inf	65.1 %		
				Arm 8 Left	12.00	13.6 %		
3/1 (Higham Common Road)	3.00	0.00	Y	Arm 5 Ahead	Inf	69.0 %	1845	1845
				Arm 6 Right	15.00	16.5 %		
				Arm 7 Left	10.00	14.5 %		
4/1 (Cawthorne Road)	4.50	0.00	Y	Arm 5 Left	10.00	38.7 %	1930	1930
				Arm 6 Ahead	Inf	48.6 %		
				Arm 8 Right	16.00	12.7 %		
5/1 (Barugh Lane Lane 1)				Infinite Saturation Flow			Inf	Inf
6/1 (Barugh Green Road (E) Lane 1)				Infinite Saturation Flow			Inf	Inf
7/1 (Cawthorne Road Lane 1)				Infinite Saturation Flow			Inf	Inf
8/1 (Higham Common Road Lane 1)				Infinite Saturation Flow			Inf	Inf

Scenario 1: '2029 Base AM' (FG1: '2029 Base + CD AM', Plan 1: 'Network Control Plan 1')


Stage Sequence Diagram




Stage Timings

Stage	1	2	3
Duration	35	30	7
Change Point	0	41	77

Signal Timings Diagram



Full Input Data And Results
Network Layout Diagram



Full Input Data And Results

Network Results

Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network: Barugh Green Crossroads	-	-	N/A	-	-		-	-	-	-	-	-	70.5%
Unnamed Junction	-	-	N/A	-	-		-	-	-	-	-	-	70.5%
1/1	Barugh Lane Left Right Ahead	O	N/A	N/A	B		1	30	-	398	1864	582	68.4%
2/1	Barugh Green Road (E) Right Ahead Left	O	N/A	N/A	C		1	35	-	336	1949	672	50.0%
3/1	Higham Common Road Ahead Right Left	O	N/A	N/A	D		1	30	-	270	1836	632	42.7%
4/1	Cawthorne Road Left Ahead Right	O	N/A	N/A	A		1	35	-	556	1973	789	70.5%
5/1	Barugh Lane	U	N/A	N/A	-		-	-	-	373	Inf	Inf	0.0%
6/1	Barugh Green Road (E)	U	N/A	N/A	-		-	-	-	476	Inf	Inf	0.0%
7/1	Cawthorne Road	U	N/A	N/A	-		-	-	-	367	Inf	Inf	0.0%
8/1	Higham Common Road	U	N/A	N/A	-		-	-	-	344	Inf	Inf	0.0%


Full Input Data And Results

Item	Arriving (pcu)	Leaving (pcu)	Turners In Gaps (pcu)	Turners When Unopposed (pcu)	Turners In Intergreen (pcu)	Uniform Delay (pcuHr)	Rand + Oversat Delay (pcuHr)	Storage Area Uniform Delay (pcuHr)	Total Delay (pcuHr)	Av. Delay Per PCU (s/pcu)	Max. Back of Uniform Queue (pcu)	Rand + Oversat Queue (pcu)	Mean Max Queue (pcu)
Network: Barugh Green Crossroads	-	-	314	0	0	9.8	3.1	0.5	13.5	-	-	-	-
Unnamed Junction	-	-	314	0	0	9.8	3.1	0.5	13.5	-	-	-	-
1/1	398	398	137	0	0	2.8	1.1	0.2	4.1	36.7	8.6	1.1	9.7
2/1	336	336	62	0	0	1.8	0.5	0.2	2.6	27.6	6.1	0.5	6.6
3/1	270	270	58	0	0	1.7	0.4	0.1	2.1	28.5	5.2	0.4	5.5
4/1	556	556	57	0	0	3.5	1.2	0.0	4.7	30.5	11.6	1.2	12.8
5/1	373	373	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
6/1	476	476	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
7/1	367	367	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
8/1	344	344	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
C1			PRC for Signalled Lanes (%):	27.7	Total Delay for Signalled Lanes (pcuHr):	13.47	Cycle Time (s):		90				
			PRC Over All Lanes (%):	27.7	Total Delay Over All Lanes(pcuHr):	13.47							

Full Input Data And Results

Scenario 2: '2029 Base PM' (FG2: '2029 Base + CD PM', Plan 1: 'Network Control Plan 1')


Stage Sequence Diagram




Stage Timings

Stage	1	2	3
Duration	32	33	7
Change Point	0	38	77

Signal Timings Diagram



Full Input Data And Results
Network Layout Diagram



Full Input Data And Results

Network Results

Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network: Barugh Green Crossroads	-	-	N/A	-	-		-	-	-	-	-	-	81.5%
Unnamed Junction	-	-	N/A	-	-		-	-	-	-	-	-	81.5%
1/1	Barugh Lane Left Right Ahead	O	N/A	N/A	B		1	33	-	414	1858	519	79.7%
2/1	Barugh Green Road (E) Right Ahead Left	O	N/A	N/A	C		1	32	-	517	1970	635	81.5%
3/1	Higham Common Road Ahead Right Left	O	N/A	N/A	D		1	33	-	390	1846	697	55.9%
4/1	Cawthorne Road Left Ahead Right	O	N/A	N/A	A		1	32	-	453	1929	704	64.3%
5/1	Barugh Lane	U	N/A	N/A	-		-	-	-	559	Inf	Inf	0.0%
6/1	Barugh Green Road (E)	U	N/A	N/A	-		-	-	-	340	Inf	Inf	0.0%
7/1	Cawthorne Road	U	N/A	N/A	-		-	-	-	552	Inf	Inf	0.0%
8/1	Higham Common Road	U	N/A	N/A	-		-	-	-	323	Inf	Inf	0.0%


Full Input Data And Results

Item	Arriving (pcu)	Leaving (pcu)	Turners In Gaps (pcu)	Turners When Unopposed (pcu)	Turners In Intergreen (pcu)	Uniform Delay (pcuHr)	Rand + Oversat Delay (pcuHr)	Storage Area Uniform Delay (pcuHr)	Total Delay (pcuHr)	Av. Delay Per PCU (s/pcu)	Max. Back of Uniform Queue (pcu)	Rand + Oversat Queue (pcu)	Mean Max Queue (pcu)
Network: Barugh Green Crossroads	-	-	388	0	0	11.9	5.5	0.8	18.2	-	-	-	-
Unnamed Junction	-	-	388	0	0	11.9	5.5	0.8	18.2	-	-	-	-
1/1	414	414	158	0	0	2.9	1.9	0.3	5.2	44.9	9.5	1.9	11.4
2/1	517	517	111	0	0	3.6	2.1	0.3	6.0	42.1	11.8	2.1	13.9
3/1	390	390	61	0	0	2.4	0.6	0.0	3.0	28.1	7.6	0.6	8.2
4/1	453	453	58	0	0	3.0	0.9	0.1	4.0	31.8	9.3	0.9	10.2
5/1	559	559	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
6/1	340	340	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
7/1	552	552	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
8/1	323	323	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
C1			PRC for Signalled Lanes (%):	10.5	Total Delay for Signalled Lanes (pcuHr):	18.24	Cycle Time (s):		90				
			PRC Over All Lanes (%):	10.5	Total Delay Over All Lanes(pcuHr):	18.24							

Full Input Data And Results

Scenario 3: '2029 Base + Dev AM' (FG3: '2029 Base + CD + Development AM', Plan 1: 'Network Control Plan 1')


Stage Sequence Diagram




Stage Timings

Stage	1	2	3
Duration	35	30	7
Change Point	0	41	77

Signal Timings Diagram



Full Input Data And Results
Network Layout Diagram



Full Input Data And Results

Network Results

Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network: Barugh Green Crossroads	-	-	N/A	-	-		-	-	-	-	-	-	70.7%
Unnamed Junction	-	-	N/A	-	-		-	-	-	-	-	-	70.7%
1/1	Barugh Lane Left Right Ahead	O	N/A	N/A	B		1	30	-	398	1864	582	68.4%
2/1	Barugh Green Road (E) Right Ahead Left	O	N/A	N/A	C		1	35	-	344	1948	682	50.5%
3/1	Higham Common Road Ahead Right Left	O	N/A	N/A	D		1	30	-	272	1835	632	43.0%
4/1	Cawthorne Road Left Ahead Right	O	N/A	N/A	A		1	35	-	558	1973	789	70.7%
5/1	Barugh Lane	U	N/A	N/A	-		-	-	-	373	Inf	Inf	0.0%
6/1	Barugh Green Road (E)	U	N/A	N/A	-		-	-	-	480	Inf	Inf	0.0%
7/1	Cawthorne Road	U	N/A	N/A	-		-	-	-	370	Inf	Inf	0.0%
8/1	Higham Common Road	U	N/A	N/A	-		-	-	-	349	Inf	Inf	0.0%


Full Input Data And Results

Item	Arriving (pcu)	Leaving (pcu)	Turners In Gaps (pcu)	Turners When Unopposed (pcu)	Turners In Intergreen (pcu)	Uniform Delay (pcuHr)	Rand + Oversat Delay (pcuHr)	Storage Area Uniform Delay (pcuHr)	Total Delay (pcuHr)	Av. Delay Per PCU (s/pcu)	Max. Back of Uniform Queue (pcu)	Rand + Oversat Queue (pcu)	Mean Max Queue (pcu)
Network: Barugh Green Crossroads	-	-	316	0	0	9.9	3.1	0.5	13.6	-	-	-	-
Unnamed Junction	-	-	316	0	0	9.9	3.1	0.5	13.6	-	-	-	-
1/1	398	398	137	0	0	2.8	1.1	0.2	4.1	36.7	8.6	1.1	9.7
2/1	344	344	62	0	0	1.9	0.5	0.2	2.6	27.6	6.2	0.5	6.7
3/1	272	272	60	0	0	1.7	0.4	0.1	2.2	28.6	5.2	0.4	5.6
4/1	558	558	57	0	0	3.5	1.2	0.1	4.7	30.6	11.6	1.2	12.8
5/1	373	373	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
6/1	480	480	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
7/1	370	370	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
8/1	349	349	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
C1			PRC for Signalled Lanes (%):	27.3	Total Delay for Signalled Lanes (pcuHr):	13.60	Cycle Time (s):		90				
			PRC Over All Lanes (%):	27.3	Total Delay Over All Lanes(pcuHr):	13.60							

Full Input Data And Results

Scenario 4: '2029 Base + Dev PM' (FG4: '2029 Base + CD + Development PM', Plan 1: 'Network Control Plan 1')


Stage Sequence Diagram




Stage Timings

Stage	1	2	3
Duration	32	33	7
Change Point	0	38	77

Signal Timings Diagram



Full Input Data And Results
Network Layout Diagram



Full Input Data And Results

Network Results

Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network: Barugh Green Crossroads	-	-	N/A	-	-		-	-	-	-	-	-	81.8%
Unnamed Junction	-	-	N/A	-	-		-	-	-	-	-	-	81.8%
1/1	Barugh Lane Left Right Ahead	O	N/A	N/A	B		1	33	-	414	1858	519	79.7%
2/1	Barugh Green Road (E) Right Ahead Left	O	N/A	N/A	C		1	32	-	521	1969	637	81.8%
3/1	Higham Common Road Ahead Right Left	O	N/A	N/A	D		1	33	-	394	1845	697	56.5%
4/1	Cawthorne Road Left Ahead Right	O	N/A	N/A	A		1	32	-	455	1930	705	64.6%
5/1	Barugh Lane	U	N/A	N/A	-		-	-	-	559	Inf	Inf	0.0%
6/1	Barugh Green Road (E)	U	N/A	N/A	-		-	-	-	346	Inf	Inf	0.0%
7/1	Cawthorne Road	U	N/A	N/A	-		-	-	-	554	Inf	Inf	0.0%
8/1	Higham Common Road	U	N/A	N/A	-		-	-	-	325	Inf	Inf	0.0%

Full Input Data And Results

Item	Arriving (pcu)	Leaving (pcu)	Turners In Gaps (pcu)	Turners When Unopposed (pcu)	Turners In Intergreen (pcu)	Uniform Delay (pcuHr)	Rand + Oversat Delay (pcuHr)	Storage Area Uniform Delay (pcuHr)	Total Delay (pcuHr)	Av. Delay Per PCU (s/pcu)	Max. Back of Uniform Queue (pcu)	Rand + Oversat Queue (pcu)	Mean Max Queue (pcu)
Network: Barugh Green Crossroads	-	-	392	0	0	12.0	5.6	0.8	18.4	-	-	-	-
Unnamed Junction	-	-	392	0	0	12.0	5.6	0.8	18.4	-	-	-	-
1/1	414	414	158	0	0	2.9	1.9	0.3	5.2	45.0	9.5	1.9	11.4
2/1	521	521	111	0	0	3.7	2.2	0.3	6.1	42.3	11.9	2.2	14.0
3/1	394	394	65	0	0	2.4	0.6	0.0	3.1	28.2	7.8	0.6	8.4
4/1	455	455	58	0	0	3.0	0.9	0.1	4.0	31.9	9.4	0.9	10.3
5/1	559	559	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
6/1	346	346	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
7/1	554	554	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
8/1	325	325	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
C1			PRC for Signalled Lanes (%):	10.0	Total Delay for Signalled Lanes (pcuHr):	18.41	Cycle Time (s):		90				
			PRC Over All Lanes (%):	10.0	Total Delay Over All Lanes(pcuHr):	18.41							

Junctions 8
ARCADY 8 - Roundabout Module
Version: 8.0.6.541 [19821,26/11/2015] © Copyright TRL Limited, 2024
For sales and distribution information, program advice and maintenance, contact TRL: Tel: +44 (0)1344 770758 email: software@trl.co.uk Web: http://www.trlsoftware.co.uk
The users of this computer program for the solution of an engineering problem are in no way relieved of their responsibility for the correctness of the solution

Filename: Barugh Green Road_Wilthorpe Road RBT.arc8
Path: C:\Users\micro\Dropbox\Project Files & Management\TPS Project Files\P2636. Barugh Green, Barnsley\Technical\Junction Modelling
Report generation date: 16/12/2024 09:19:48

- » (Default Analysis Set) - 2029 B + CD, AM
- » (Default Analysis Set) - 2029 B + CD, PM
- » (Default Analysis Set) - 2029 B + CD + D, AM
- » (Default Analysis Set) - 2029 B + CD + D, PM

Summary of junction performance

	AM			PM		
	Queue (PCU)	Delay (s)	RFC	Queue (PCU)	Delay (s)	RFC
A1 - 2029 B + CD						
Claycliffe Road	3.26	14.70	0.77	2.05	9.03	0.68
Whaley Road	0.22	5.68	0.18	0.32	5.83	0.24
Wilthorpe Road	3.64	9.34	0.79	5.04	12.77	0.84
Barugh Green Road	1.66	8.42	0.63	0.86	5.56	0.47
A1 - 2029 B + CD + D						
Claycliffe Road	3.70	16.66	0.79	2.20	9.57	0.69
Whaley Road	0.23	5.94	0.19	0.33	6.01	0.25
Wilthorpe Road	3.86	9.81	0.80	6.06	15.10	0.87
Barugh Green Road	2.03	9.59	0.67	0.93	5.75	0.48

Values shown are the maximum values over all time segments. Delay is the maximum value of average delay per arriving vehicle.

"D1 - 2029 B + CD, AM " model duration: 07:30 - 09:00
 "D2 - 2029 B + CD, PM" model duration: 16:30 - 18:00
 "D3 - 2029 B + CD + D, AM" model duration: 07:30 - 09:00
 "D4 - 2029 B + CD + D, PM" model duration: 16:30 - 18:00

Run using Junctions 8.0.6.541 at 16/12/2024 09:19:44

File summary

Title	Barugh Green Road / Wilthorpe Road
Location	Barugh Green, Barnsley
Site Number	
Date	16/12/2024
Version	
Status	(new file)
Identifier	
Client	Avant Homes
Jobnumber	P2636
Enumerator	JT
Description	

Analysis Options

Vehicle Length (m)	Do Queue Variations	Calculate Residual Capacity	Residual Capacity Criteria Type	RFC Threshold	Average Delay Threshold (s)	Queue Threshold (PCU)
5.75			N/A	0.85	36.00	20.00

Units

Distance Units	Speed Units	Traffic Units Input	Traffic Units Results	Flow Units	Average Delay Units	Total Delay Units	Rate Of Delay Units
m	kph	PCU	PCU	perHour	s	-Min	perMin

(Default Analysis Set) - 2029 B + CD, AM

Data Errors and Warnings

Severity	Area	Item	Description
Warning	Geometry	Barugh Green Road - Roundabout Geometry	Effective flare length is over 30m, which is outside the normal range. Treat capacities with increasing caution.

Analysis Set Details

Name	Roundabout Capacity Model	Description	Include In Report	Use Specific Demand Set(s)	Specific Demand Set (s)	Locked	Network Flow Scaling Factor (%)	Network Capacity Scaling Factor (%)	Reason For Scaling Factors
(Default Analysis Set)	ARCADY		✓				100.000	100.000	

Demand Set Details

Name	Scenario Name	Time Period Name	Description	Traffic Profile Type	Model Start Time (HH:mm)	Model Finish Time (HH:mm)	Model Time Period Length (min)	Time Segment Length (min)	Results For Central Hour Only	Single Time Segment Only	Locked	Run Automatically	Use Relationship	Relationship
2029 B + CD, AM	2029 B + CD	AM		ONE HOUR	07:30	09:00	90	15				✓		

Junction Network

Junctions

Junction	Name	Junction Type	Arm Order	Grade Separated	Large Roundabout	Do Geometric Delay	Junction Delay (s)	Junction LOS
1	(untitled)	Roundabout	1,2,3,4				10.37	B

Junction Network Options

Driving Side	Lighting
Left	Normal/unknown

Arms

Arms

Name	Arm	Name	Description
Claycliffe Road	1	Claycliffe Road	
Whaley Road	2	Whaley Road	
Wilthorpe Road	3	Wilthorpe Road	
Barugh Green Road	4	Barugh Green Road	

Capacity Options

Name	Minimum Capacity (PCU/hr)	Maximum Capacity (PCU/hr)	Assume Flat Start Profile	Initial Queue (PCU)
Claycliffe Road	0.00	99999.00		0.00
Whaley Road	0.00	99999.00		0.00
Wilthorpe Road	0.00	99999.00		0.00
Barugh Green Road	0.00	99999.00		0.00

Roundabout Geometry

Name	V - Approach road half-width (m)	E - Entry width (m)	I' - Effective flare length (m)	R - Entry radius (m)	D - Inscribed circle diameter (m)	PHI - Conflict (entry) angle (deg)	Exit Only
Claycliffe Road	3.90	5.90	12.00	12.50	35.00	19.00	
Whaley Road	4.70	5.60	9.00	15.00	35.00	25.00	
Wilthorpe Road	3.00	7.50	25.00	74.00	35.00	19.00	
Barugh Green Road	3.70	8.00	45.00	10.00	35.00	65.00	

Slope / Intercept / Capacity

Roundabout Slope and Intercept used in model

Name	Enter slope and intercept directly	Entered slope	Entered intercept (PCU/hr)	Final Slope	Final Intercept (PCU/hr)
Claycliffe Road		(calculated)	(calculated)	0.632	1590.842
Whaley Road		(calculated)	(calculated)	0.638	1632.403
Wilthorpe Road		(calculated)	(calculated)	0.716	1905.194
Barugh Green Road		(calculated)	(calculated)	0.611	1757.942

The slope and intercept shown above include any corrections and adjustments.

Traffic Flows

Demand Set Data Options

Default Vehicle Mix	Vehicle Mix Varies Over Time	Vehicle Mix Varies Over Turn	Vehicle Mix Varies Over Entry	Vehicle Mix Source	PCU Factor for a HV (PCU)	Default Turning Proportions	Estimate from entry/exit counts	Turning Proportions Vary Over Time	Turning Proportions Vary Over Turn	Turning Proportions Vary Over Entry
		✓	✓	HV Percentages	2.00				✓	✓

Entry Flows

General Flows Data

Name	Profile Type	Use Turning Counts	Average Demand Flow (PCU/hr)	Flow Scaling Factor (%)
Claycliffe Road	ONE HOUR	✓	748.00	100.000
Whaley Road	ONE HOUR	✓	129.00	100.000
Wilthorpe Road	ONE HOUR	✓	1302.00	100.000
Barugh Green Road	ONE HOUR	✓	655.00	100.000

Turning Proportions

Turning Counts / Proportions (PCU/hr) - (untitled) (for whole period)

		To			
		Claycliffe Road	Whaley Road	Wilthorpe Road	Barugh Green Road
From	Claycliffe Road	5.000	40.000	644.000	59.000
	Whaley Road	20.000	1.000	83.000	25.000
	Wilthorpe Road	689.000	164.000	27.000	422.000
	Barugh Green Road	94.000	77.000	483.000	1.000

Turning Proportions (PCU) - (untitled) (for whole period)

		To			
		Claycliffe Road	Whaley Road	Wilthorpe Road	Barugh Green Road
From	Claycliffe Road	0.01	0.05	0.86	0.08
	Whaley Road	0.16	0.01	0.64	0.19
	Wilthorpe Road	0.53	0.13	0.02	0.32
	Barugh Green Road	0.14	0.12	0.74	0.00

Vehicle Mix

Average PCU Per Vehicle - (untitled) (for whole period)

		To			
		Claycliffe Road	Whaley Road	Wilthorpe Road	Barugh Green Road
From	Claycliffe Road	1.000	1.000	1.000	1.000
	Whaley Road	1.000	1.000	1.000	1.000
	Wilthorpe Road	1.000	1.000	1.000	1.000
	Barugh Green Road	1.000	1.000	1.000	1.000

Heavy Vehicle Percentages - (untitled) (for whole period)

		To			
From		Claycliffe Road	Whaley Road	Wilthorpe Road	Barugh Green Road
	Claycliffe Road	0.0	0.0	0.0	0.0
	Whaley Road	0.0	0.0	0.0	0.0
	Wilthorpe Road	0.0	0.0	0.0	0.0
	Barugh Green Road	0.0	0.0	0.0	0.0

Results

Results Summary for whole modelled period

Name	Max RFC	Max Delay (s)	Max Queue (PCU)	Max LOS	Average Demand (PCU/hr)	Total Junction Arrivals (PCU)	Total Queueing Delay (PCU-min)	Average Queueing Delay (s)	Rate Of Queueing Delay (PCU-min/min)	Inclusive Total Queueing Delay (PCU-min)	Inclusive Average Queueing Delay (s)
Claycliffe Road	0.77	14.70	3.26	B	686.38	1029.57	157.88	9.20	1.75	157.89	9.20
Whaley Road	0.18	5.68	0.22	A	118.37	177.56	13.90	4.70	0.15	13.90	4.70
Wilthorpe Road	0.79	9.34	3.64	A	1194.74	1792.11	190.77	6.39	2.12	190.79	6.39
Barugh Green Road	0.63	8.42	1.66	A	601.04	901.56	91.98	6.12	1.02	91.98	6.12

Main Results for each time segment

Main results: (07:30-07:45)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	563.13	140.78	559.81	605.51	564.26	0.00	1234.14	892.39	0.456	0.00	0.83	5.314	A
Whaley Road	97.12	24.28	96.71	211.29	912.79	0.00	1049.87	602.10	0.093	0.00	0.10	3.774	A
Wilthorpe Road	980.21	245.05	975.73	926.37	83.13	0.00	1845.68	1695.76	0.531	0.00	1.12	4.116	A
Barugh Green Road	493.12	123.28	490.81	379.90	678.96	0.00	1343.10	994.12	0.367	0.00	0.58	4.213	A

Main results: (07:45-08:00)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	672.44	168.11	670.38	724.87	675.58	0.00	1163.78	892.39	0.578	0.83	1.34	7.265	A
Whaley Road	115.97	28.99	115.81	252.96	1093.00	0.00	934.86	602.10	0.124	0.10	0.14	4.395	A
Wilthorpe Road	1170.47	292.62	1168.01	1109.26	99.55	0.00	1833.93	1695.76	0.638	1.12	1.74	5.385	A
Barugh Green Road	588.83	147.21	587.67	454.79	812.77	0.00	1261.34	994.12	0.467	0.58	0.87	5.335	A

Main results: (08:00-08:15)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	823.56	205.89	816.35	885.22	825.36	0.00	1069.09	892.39	0.770	1.34	3.15	13.862	B
Whaley Road	142.03	35.51	141.71	308.82	1332.89	0.00	781.77	602.10	0.182	0.14	0.22	5.622	A
Wilthorpe Road	1433.53	358.38	1426.23	1353.12	121.48	0.00	1818.24	1695.76	0.788	1.74	3.56	9.017	A
Barugh Green Road	721.17	180.29	718.09	555.22	992.49	0.00	1151.53	994.12	0.626	0.87	1.64	8.247	A

Main results: (08:15-08:30)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	823.56	205.89	823.09	889.43	828.93	0.00	1066.84	892.39	0.772	3.15	3.26	14.698	B
Whaley Road	142.03	35.51	142.02	310.41	1341.61	0.00	776.20	602.10	0.183	0.22	0.22	5.676	A
Wilthorpe Road	1433.53	358.38	1433.20	1361.46	122.17	0.00	1817.74	1695.76	0.789	3.56	3.64	9.340	A
Barugh Green Road	721.17	180.29	721.06	558.07	997.30	0.00	1148.59	994.12	0.628	1.64	1.66	8.415	A

Main results: (08:30-08:45)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	672.44	168.11	679.88	730.83	680.67	0.00	1160.56	892.39	0.579	3.26	1.40	7.603	A
Whaley Road	115.97	28.99	116.28	255.21	1105.34	0.00	926.99	602.10	0.125	0.22	0.14	4.443	A
Wilthorpe Road	1170.47	292.62	1177.86	1121.08	100.54	0.00	1833.22	1695.76	0.638	3.64	1.79	5.555	A
Barugh Green Road	588.83	147.21	591.92	458.83	819.57	0.00	1257.18	994.12	0.468	1.66	0.89	5.437	A

Main results: (08:45-09:00)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	563.13	140.78	565.34	609.90	568.32	0.00	1231.58	892.39	0.457	1.40	0.85	5.422	A
Whaley Road	97.12	24.28	97.28	212.89	920.77	0.00	1044.78	602.10	0.093	0.14	0.10	3.802	A
Wilthorpe Road	980.21	245.05	982.82	934.24	83.82	0.00	1845.20	1695.76	0.531	1.79	1.14	4.188	A
Barugh Green Road	493.12	123.28	494.34	382.75	683.88	0.00	1340.09	994.12	0.368	0.89	0.59	4.264	A

Queueing Delay Results for each time segment
Queueing Delay results: (07:30-07:45)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	11.99	0.80	5.314	A	A
Whaley Road	1.49	0.10	3.774	A	A
Wilthorpe Road	16.26	1.08	4.116	A	A
Barugh Green Road	8.40	0.56	4.213	A	A

Queueing Delay results: (07:45-08:00)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	19.33	1.29	7.265	A	A
Whaley Road	2.08	0.14	4.395	A	A
Wilthorpe Road	25.10	1.67	5.385	A	A
Barugh Green Road	12.63	0.84	5.335	A	A

Queueing Delay results: (08:00-08:15)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	42.69	2.85	13.862	B	B
Whaley Road	3.23	0.22	5.622	A	A
Wilthorpe Road	49.36	3.29	9.017	A	A
Barugh Green Road	23.29	1.55	8.247	A	A

Queueing Delay results: (08:15-08:30)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	48.29	3.22	14.698	B	B
Whaley Road	3.33	0.22	5.676	A	A
Wilthorpe Road	54.16	3.61	9.340	A	A
Barugh Green Road	24.81	1.65	8.415	A	A

Queueing Delay results: (08:30-08:45)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	22.37	1.49	7.603	A	A
Whaley Road	2.20	0.15	4.443	A	A
Wilthorpe Road	28.22	1.88	5.555	A	A
Barugh Green Road	13.84	0.92	5.437	A	A

Queueing Delay results: (08:45-09:00)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	13.20	0.88	5.422	A	A
Whaley Road	1.57	0.10	3.802	A	A
Wilthorpe Road	17.67	1.18	4.188	A	A
Barugh Green Road	9.01	0.60	4.264	A	A

(Default Analysis Set) - 2029 B + CD, PM

Data Errors and Warnings

Severity	Area	Item	Description
Warning	Geometry	Barugh Green Road - Roundabout Geometry	Effective flare length is over 30m, which is outside the normal range. Treat capacities with increasing caution.

Analysis Set Details

Name	Roundabout Capacity Model	Description	Include In Report	Use Specific Demand Set(s)	Specific Demand Set (s)	Locked	Network Flow Scaling Factor (%)	Network Capacity Scaling Factor (%)	Reason For Scaling Factors
(Default Analysis Set)	ARCADY		✓				100.000	100.000	

Demand Set Details

Name	Scenario Name	Time Period Name	Description	Traffic Profile Type	Model Start Time (HH:mm)	Model Finish Time (HH:mm)	Model Time Period Length (min)	Time Segment Length (min)	Results For Central Hour Only	Single Time Segment Only	Locked	Run Automatically	Use Relationship	Relationship
2029 B + CD, PM	2029 B + CD	PM		ONE HOUR	16:30	18:00	90	15				✓		

Junction Network

Junctions

Junction	Name	Junction Type	Arm Order	Grade Separated	Large Roundabout	Do Geometric Delay	Junction Delay (s)	Junction LOS
1	(untitled)	Roundabout	1,2,3,4				9.98	A

Junction Network Options

Driving Side	Lighting
Left	Normal/unknown

Arms

Arms

Name	Arm	Name	Description
Claycliffe Road	1	Claycliffe Road	
Whaley Road	2	Whaley Road	
Wilthorpe Road	3	Wilthorpe Road	
Barugh Green Road	4	Barugh Green Road	

Capacity Options

Name	Minimum Capacity (PCU/hr)	Maximum Capacity (PCU/hr)	Assume Flat Start Profile	Initial Queue (PCU)
Claycliffe Road	0.00	99999.00		0.00
Whaley Road	0.00	99999.00		0.00
Wilthorpe Road	0.00	99999.00		0.00
Barugh Green Road	0.00	99999.00		0.00

Roundabout Geometry

Name	V - Approach road half-width (m)	E - Entry width (m)	I' - Effective flare length (m)	R - Entry radius (m)	D - Inscribed circle diameter (m)	PHI - Conflict (entry) angle (deg)	Exit Only
Claycliffe Road	3.90	5.90	12.00	12.50	35.00	19.00	
Whaley Road	4.70	5.60	9.00	15.00	35.00	25.00	
Wilthorpe Road	3.00	7.50	25.00	74.00	35.00	19.00	
Barugh Green Road	3.70	8.00	45.00	10.00	35.00	65.00	

Slope / Intercept / Capacity

Roundabout Slope and Intercept used in model

Name	Enter slope and intercept directly	Entered slope	Entered intercept (PCU/hr)	Final Slope	Final Intercept (PCU/hr)
Claycliffe Road		(calculated)	(calculated)	0.632	1590.842
Whaley Road		(calculated)	(calculated)	0.638	1632.403
Wilthorpe Road		(calculated)	(calculated)	0.716	1905.194
Barugh Green Road		(calculated)	(calculated)	0.611	1757.942

The slope and intercept shown above include any corrections and adjustments.

Traffic Flows

Demand Set Data Options

Default Vehicle Mix	Vehicle Mix Varies Over Time	Vehicle Mix Varies Over Turn	Vehicle Mix Varies Over Entry	Vehicle Mix Source	PCU Factor for a HV (PCU)	Default Turning Proportions	Estimate from entry/exit counts	Turning Proportions Vary Over Time	Turning Proportions Vary Over Turn	Turning Proportions Vary Over Entry
		✓	✓	HV Percentages	2.00				✓	✓

Entry Flows

General Flows Data

Name	Profile Type	Use Turning Counts	Average Demand Flow (PCU/hr)	Flow Scaling Factor (%)
Claycliffe Road	ONE HOUR	✓	754.00	100.000
Whaley Road	ONE HOUR	✓	178.00	100.000
Wilthorpe Road	ONE HOUR	✓	1333.00	100.000
Barugh Green Road	ONE HOUR	✓	512.00	100.000

Turning Proportions

Turning Counts / Proportions (PCU/hr) - (untitled) (for whole period)

		To			
		Claycliffe Road	Whaley Road	Wilthorpe Road	Barugh Green Road
From	Claycliffe Road	4.000	20.000	609.000	121.000
	Whaley Road	38.000	0.000	102.000	38.000
	Wilthorpe Road	666.000	68.000	37.000	562.000
	Barugh Green Road	96.000	21.000	395.000	0.000

Turning Proportions (PCU) - (untitled) (for whole period)

		To			
		Claycliffe Road	Whaley Road	Wilthorpe Road	Barugh Green Road
From	Claycliffe Road	0.01	0.03	0.81	0.16
	Whaley Road	0.21	0.00	0.57	0.21
	Wilthorpe Road	0.50	0.05	0.03	0.42
	Barugh Green Road	0.19	0.04	0.77	0.00

Vehicle Mix

Average PCU Per Vehicle - (untitled) (for whole period)

		To			
		Claycliffe Road	Whaley Road	Wilthorpe Road	Barugh Green Road
From	Claycliffe Road	1.000	1.000	1.000	1.000
	Whaley Road	1.000	1.000	1.000	1.000
	Wilthorpe Road	1.000	1.000	1.000	1.000
	Barugh Green Road	1.000	1.000	1.000	1.000

Heavy Vehicle Percentages - (untitled) (for whole period)

		To			
		Claycliffe Road	Whaley Road	Wilthorpe Road	Barugh Green Road
From	Claycliffe Road	0.0	0.0	0.0	0.0
	Whaley Road	0.0	0.0	0.0	0.0
	Wilthorpe Road	0.0	0.0	0.0	0.0
	Barugh Green Road	0.0	0.0	0.0	0.0

Results

Results Summary for whole modelled period

Name	Max RFC	Max Delay (s)	Max Queue (PCU)	Max LOS	Average Demand (PCU/hr)	Total Junction Arrivals (PCU)	Total Queueing Delay (PCU-min)	Average Queueing Delay (s)	Rate Of Queueing Delay (PCU-min/min)	Inclusive Total Queueing Delay (PCU-min)	Inclusive Average Queueing Delay (s)
Claycliffe Road	0.68	9.03	2.05	A	691.88	1037.83	114.22	6.60	1.27	114.23	6.60
Whaley Road	0.24	5.83	0.32	A	163.34	245.00	19.58	4.80	0.22	19.58	4.80
Wilthorpe Road	0.84	12.77	5.04	B	1223.18	1834.78	240.58	7.87	2.67	240.61	7.87
Barugh Green Road	0.47	5.56	0.86	A	469.82	704.73	53.23	4.53	0.59	53.24	4.53

Main Results for each time segment

Main results: (16:30-16:45)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	567.65	141.91	564.75	602.37	390.60	0.00	1343.93	938.43	0.422	0.00	0.72	4.604	A
Whaley Road	134.01	33.50	133.44	81.67	873.68	0.00	1074.83	473.50	0.125	0.00	0.14	3.822	A
Wilthorpe Road	1003.55	250.89	998.55	856.52	150.60	0.00	1797.39	1649.11	0.558	0.00	1.25	4.479	A
Barugh Green Road	385.46	96.37	383.93	540.11	609.04	0.00	1385.82	1110.34	0.278	0.00	0.38	3.589	A

Main results: (16:45-17:00)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	677.83	169.46	676.40	721.05	467.62	0.00	1295.23	938.43	0.523	0.72	1.08	5.808	A
Whaley Road	160.02	40.00	159.79	97.77	1046.25	0.00	964.69	473.50	0.166	0.14	0.20	4.471	A
Wilthorpe Road	1198.34	299.58	1195.21	1025.69	180.36	0.00	1776.09	1649.11	0.675	1.25	2.03	6.164	A
Barugh Green Road	460.28	115.07	459.67	646.57	729.00	0.00	1312.52	1110.34	0.351	0.38	0.54	4.218	A

Main results: (17:00-17:15)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	830.17	207.54	826.43	879.23	571.70	0.00	1229.44	938.43	0.675	1.08	2.02	8.850	A
Whaley Road	195.98	49.00	195.52	119.28	1278.85	0.00	816.26	473.50	0.240	0.20	0.31	5.796	A
Wilthorpe Road	1467.66	366.92	1456.38	1253.88	220.49	0.00	1747.36	1649.11	0.840	2.03	4.85	11.929	B
Barugh Green Road	563.72	140.93	562.44	788.38	888.49	0.00	1215.08	1110.34	0.464	0.54	0.86	5.504	A

Main results: (17:15-17:30)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	830.17	207.54	830.04	884.84	573.54	0.00	1228.28	938.43	0.676	2.02	2.05	9.031	A
Whaley Road	195.98	49.00	195.97	119.97	1283.61	0.00	813.21	473.50	0.241	0.31	0.32	5.831	A
Wilthorpe Road	1467.66	366.92	1466.91	1258.31	221.28	0.00	1746.80	1649.11	0.840	4.85	5.04	12.770	B
Barugh Green Road	563.72	140.93	563.69	793.50	894.69	0.00	1211.29	1110.34	0.465	0.86	0.86	5.558	A

Main results: (17:30-17:45)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	677.83	169.46	681.58	728.97	470.32	0.00	1293.53	938.43	0.524	2.05	1.12	5.919	A
Whaley Road	160.02	40.00	160.48	98.74	1053.16	0.00	960.29	473.50	0.167	0.32	0.20	4.503	A
Wilthorpe Road	1198.34	299.58	1210.02	1032.13	181.51	0.00	1775.26	1649.11	0.675	5.04	2.12	6.497	A
Barugh Green Road	460.28	115.07	461.55	653.79	737.74	0.00	1307.18	1110.34	0.352	0.86	0.55	4.264	A

Main results: (17:45-18:00)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	567.65	141.91	569.16	607.15	393.02	0.00	1342.40	938.43	0.423	1.12	0.74	4.664	A
Whaley Road	134.01	33.50	134.24	82.30	879.88	0.00	1070.88	473.50	0.125	0.20	0.14	3.845	A
Wilthorpe Road	1003.55	250.89	1006.92	862.44	151.67	0.00	1796.62	1649.11	0.559	2.12	1.28	4.579	A
Barugh Green Road	385.46	96.37	386.10	544.52	614.07	0.00	1382.74	1110.34	0.279	0.55	0.39	3.616	A

Queueing Delay Results for each time segment

Queueing Delay results: (16:30-16:45)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	10.53	0.70	4.604	A	A
Whaley Road	2.08	0.14	3.822	A	A
Wilthorpe Road	18.05	1.20	4.479	A	A
Barugh Green Road	5.62	0.37	3.589	A	A

Queueing Delay results: (16:45-17:00)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	15.75	1.05	5.808	A	A
Whaley Road	2.91	0.19	4.471	A	A
Wilthorpe Road	29.17	1.94	6.164	A	A
Barugh Green Road	7.88	0.53	4.218	A	A

Queueing Delay results: (17:00-17:15)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	28.56	1.90	8.850	A	A
Whaley Road	4.59	0.31	5.796	A	A
Wilthorpe Road	65.06	4.34	11.929	B	B
Barugh Green Road	12.46	0.83	5.504	A	A

Queueing Delay results: (17:15-17:30)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	30.60	2.04	9.031	A	A
Whaley Road	4.72	0.31	5.831	A	A
Wilthorpe Road	74.48	4.97	12.770	B	B
Barugh Green Road	12.92	0.86	5.558	A	A

Queueing Delay results: (17:30-17:45)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	17.41	1.16	5.919	A	A
Whaley Road	3.08	0.21	4.503	A	A
Wilthorpe Road	33.98	2.27	6.497	A	A
Barugh Green Road	8.41	0.56	4.264	A	A

Queueing Delay results: (17:45-18:00)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	11.39	0.76	4.664	A	A
Whaley Road	2.19	0.15	3.845	A	A
Wilthorpe Road	19.84	1.32	4.579	A	A
Barugh Green Road	5.94	0.40	3.616	A	A

(Default Analysis Set) - 2029 B + CD + D, AM

Data Errors and Warnings

Severity	Area	Item	Description
Warning	Geometry	Barugh Green Road - Roundabout Geometry	Effective flare length is over 30m, which is outside the normal range. Treat capacities with increasing caution.

Analysis Set Details

Name	Roundabout Capacity Model	Description	Include In Report	Use Specific Demand Set(s)	Specific Demand Set (s)	Locked	Network Flow Scaling Factor (%)	Network Capacity Scaling Factor (%)	Reason For Scaling Factors
(Default Analysis Set)	ARCADY		✓				100.000	100.000	

Demand Set Details

Name	Scenario Name	Time Period Name	Description	Traffic Profile Type	Model Start Time (HH:mm)	Model Finish Time (HH:mm)	Model Time Period Length (min)	Time Segment Length (min)	Results For Central Hour Only	Single Time Segment Only	Locked	Run Automatically	Use Relationship	Relationship
2029 B + CD + D, AM	2029 B + CD + D	AM		ONE HOUR	07:30	09:00	90	15				✓		

Junction Network

Junctions

Junction	Name	Junction Type	Arm Order	Grade Separated	Large Roundabout	Do Geometric Delay	Junction Delay (s)	Junction LOS
1	(untitled)	Roundabout	1,2,3,4				11.36	B

Junction Network Options

Driving Side	Lighting
Left	Normal/unknown

Arms

Arms

Name	Arm	Name	Description
Claycliffe Road	1	Claycliffe Road	
Whaley Road	2	Whaley Road	
Wilthorpe Road	3	Wilthorpe Road	
Barugh Green Road	4	Barugh Green Road	

Capacity Options

Name	Minimum Capacity (PCU/hr)	Maximum Capacity (PCU/hr)	Assume Flat Start Profile	Initial Queue (PCU)
Claycliffe Road	0.00	99999.00		0.00
Whaley Road	0.00	99999.00		0.00
Wilthorpe Road	0.00	99999.00		0.00
Barugh Green Road	0.00	99999.00		0.00

Roundabout Geometry

Name	V - Approach road half-width (m)	E - Entry width (m)	I' - Effective flare length (m)	R - Entry radius (m)	D - Inscribed circle diameter (m)	PHI - Conflict (entry) angle (deg)	Exit Only
Claycliffe Road	3.90	5.90	12.00	12.50	35.00	19.00	
Whaley Road	4.70	5.60	9.00	15.00	35.00	25.00	
Wilthorpe Road	3.00	7.50	25.00	74.00	35.00	19.00	
Barugh Green Road	3.70	8.00	45.00	10.00	35.00	65.00	

Slope / Intercept / Capacity

Roundabout Slope and Intercept used in model

Name	Enter slope and intercept directly	Entered slope	Entered intercept (PCU/hr)	Final Slope	Final Intercept (PCU/hr)
Claycliffe Road		(calculated)	(calculated)	0.632	1590.842
Whaley Road		(calculated)	(calculated)	0.638	1632.403
Wilthorpe Road		(calculated)	(calculated)	0.716	1905.194
Barugh Green Road		(calculated)	(calculated)	0.611	1757.942

The slope and intercept shown above include any corrections and adjustments.

Traffic Flows

Demand Set Data Options

Default Vehicle Mix	Vehicle Mix Varies Over Time	Vehicle Mix Varies Over Turn	Vehicle Mix Varies Over Entry	Vehicle Mix Source	PCU Factor for a HV (PCU)	Default Turning Proportions	Estimate from entry/exit counts	Turning Proportions Vary Over Time	Turning Proportions Vary Over Turn	Turning Proportions Vary Over Entry
		✓	✓	HV Percentages	2.00				✓	✓

Entry Flows

General Flows Data

Name	Profile Type	Use Turning Counts	Average Demand Flow (PCU/hr)	Flow Scaling Factor (%)
Claycliffe Road	ONE HOUR	✓	752.00	100.000
Whaley Road	ONE HOUR	✓	129.00	100.000
Wilthorpe Road	ONE HOUR	✓	1316.00	100.000
Barugh Green Road	ONE HOUR	✓	703.00	100.000

Turning Proportions

Turning Counts / Proportions (PCU/hr) - (untitled) (for whole period)

		To			
		Claycliffe Road	Whaley Road	Wilthorpe Road	Barugh Green Road
From	Claycliffe Road	5.000	40.000	644.000	63.000
	Whaley Road	20.000	1.000	83.000	25.000
	Wilthorpe Road	689.000	164.000	27.000	436.000
	Barugh Green Road	106.000	77.000	519.000	1.000

Turning Proportions (PCU) - (untitled) (for whole period)

		To			
		Claycliffe Road	Whaley Road	Wilthorpe Road	Barugh Green Road
From	Claycliffe Road	0.01	0.05	0.86	0.08
	Whaley Road	0.16	0.01	0.64	0.19
	Wilthorpe Road	0.52	0.12	0.02	0.33
	Barugh Green Road	0.15	0.11	0.74	0.00

Vehicle Mix

Average PCU Per Vehicle - (untitled) (for whole period)

		To			
		Claycliffe Road	Whaley Road	Wilthorpe Road	Barugh Green Road
From	Claycliffe Road	1.000	1.000	1.000	1.000
	Whaley Road	1.000	1.000	1.000	1.000
	Wilthorpe Road	1.000	1.000	1.000	1.000
	Barugh Green Road	1.000	1.000	1.000	1.000

Heavy Vehicle Percentages - (untitled) (for whole period)

		To			
		Claycliffe Road	Whaley Road	Wilthorpe Road	Barugh Green Road
From	Claycliffe Road	0.0	0.0	0.0	0.0
	Whaley Road	0.0	0.0	0.0	0.0
	Wilthorpe Road	0.0	0.0	0.0	0.0
	Barugh Green Road	0.0	0.0	0.0	0.0

Results

Results Summary for whole modelled period

Name	Max RFC	Max Delay (s)	Max Queue (PCU)	Max LOS	Average Demand (PCU/hr)	Total Junction Arrivals (PCU)	Total Queueing Delay (PCU-min)	Average Queueing Delay (s)	Rate Of Queueing Delay (PCU-min/min)	Inclusive Total Queueing Delay (PCU-min)	Inclusive Average Queueing Delay (s)
Claycliffe Road	0.79	16.66	3.70	C	690.05	1035.07	172.22	9.98	1.91	172.24	9.98
Whaley Road	0.19	5.94	0.23	A	118.37	177.56	14.38	4.86	0.16	14.38	4.86
Wilthorpe Road	0.80	9.81	3.86	A	1207.58	1811.38	199.27	6.60	2.21	199.30	6.60
Barugh Green Road	0.67	9.59	2.03	A	645.09	967.63	108.13	6.70	1.20	108.14	6.71

Main Results for each time segment

Main results: (07:30-07:45)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	566.15	141.54	562.71	614.45	591.14	0.00	1217.15	894.13	0.465	0.00	0.86	5.473	A
Whaley Road	97.12	24.28	96.70	211.26	942.58	0.00	1030.86	596.54	0.094	0.00	0.10	3.852	A
Wilthorpe Road	990.75	247.69	986.15	953.17	86.12	0.00	1843.55	1694.03	0.537	0.00	1.15	4.176	A
Barugh Green Road	529.26	132.31	526.67	393.35	678.92	0.00	1343.12	1002.84	0.394	0.00	0.65	4.382	A

Main results: (07:45-08:00)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	676.03	169.01	673.80	735.56	707.74	0.00	1143.44	894.13	0.591	0.86	1.42	7.629	A
Whaley Road	115.97	28.99	115.80	252.92	1128.62	0.00	912.13	596.54	0.127	0.10	0.14	4.519	A
Wilthorpe Road	1183.06	295.76	1180.48	1141.31	103.12	0.00	1831.38	1694.03	0.646	1.15	1.79	5.508	A
Barugh Green Road	631.98	158.00	630.60	470.89	812.71	0.00	1261.38	1002.84	0.501	0.65	0.99	5.694	A

Main results: (08:00-08:15)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	827.97	206.99	819.50	898.00	864.18	0.00	1044.55	894.13	0.793	1.42	3.53	15.444	C
Whaley Road	142.03	35.51	141.69	308.62	1375.06	0.00	754.85	596.54	0.188	0.14	0.23	5.869	A
Wilthorpe Road	1448.94	362.24	1441.06	1391.03	125.72	0.00	1815.20	1694.03	0.798	1.79	3.77	9.424	A
Barugh Green Road	774.02	193.50	770.03	574.64	992.14	0.00	1151.74	1002.84	0.672	0.99	1.99	9.334	A

Main results: (08:15-08:30)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	827.97	206.99	827.31	902.61	868.51	0.00	1041.82	894.13	0.795	3.53	3.70	16.656	C
Whaley Road	142.03	35.51	142.02	310.39	1385.43	0.00	748.24	596.54	0.190	0.23	0.23	5.937	A
Wilthorpe Road	1448.94	362.24	1448.56	1400.89	126.55	0.00	1814.60	1694.03	0.798	3.77	3.86	9.808	A
Barugh Green Road	774.02	193.50	773.85	577.85	997.27	0.00	1148.61	1002.84	0.674	1.99	2.03	9.594	A

Main results: (08:30-08:45)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	676.03	169.01	684.88	742.07	713.88	0.00	1139.56	894.13	0.593	3.70	1.49	8.066	A
Whaley Road	115.97	28.99	116.31	255.42	1143.33	0.00	902.74	596.54	0.128	0.23	0.15	4.580	A
Wilthorpe Road	1183.06	295.76	1191.06	1155.33	104.31	0.00	1830.53	1694.03	0.646	3.86	1.86	5.697	A
Barugh Green Road	631.98	158.00	636.01	475.43	819.94	0.00	1256.96	1002.84	0.503	2.03	1.02	5.833	A

Main results: (08:45-09:00)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	566.15	141.54	568.57	619.04	595.64	0.00	1214.31	894.13	0.466	1.49	0.88	5.597	A
Whaley Road	97.12	24.28	97.29	212.94	951.27	0.00	1025.31	596.54	0.095	0.15	0.11	3.881	A
Wilthorpe Road	990.75	247.69	993.49	961.70	86.86	0.00	1843.02	1694.03	0.538	1.86	1.17	4.252	A
Barugh Green Road	529.26	132.31	530.72	396.39	683.96	0.00	1340.04	1002.84	0.395	1.02	0.66	4.455	A

Queueing Delay Results for each time segment

Queueing Delay results: (07:30-07:45)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	12.41	0.83	5.473	A	A
Whaley Road	1.52	0.10	3.852	A	A
Wilthorpe Road	16.66	1.11	4.176	A	A
Barugh Green Road	9.39	0.63	4.382	A	A

Queueing Delay results: (07:45-08:00)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	20.35	1.36	7.629	A	A
Whaley Road	2.14	0.14	4.519	A	A
Wilthorpe Road	25.91	1.73	5.508	A	A
Barugh Green Road	14.42	0.96	5.694	A	A

Queueing Delay results: (08:00-08:15)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	47.30	3.15	15.444	C	B
Whaley Road	3.37	0.22	5.869	A	A
Wilthorpe Road	51.93	3.46	9.424	A	A
Barugh Green Road	28.01	1.87	9.334	A	A

Queueing Delay results: (08:15-08:30)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	54.53	3.64	16.656	C	B
Whaley Road	3.48	0.23	5.937	A	A
Wilthorpe Road	57.34	3.82	9.808	A	A
Barugh Green Road	30.21	2.01	9.594	A	A

Queueing Delay results: (08:30-08:45)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	23.93	1.60	8.066	A	A
Whaley Road	2.27	0.15	4.580	A	A
Wilthorpe Road	29.29	1.95	5.697	A	A
Barugh Green Road	15.97	1.06	5.833	A	A

Queueing Delay results: (08:45-09:00)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	13.71	0.91	5.597	A	A
Whaley Road	1.60	0.11	3.881	A	A
Wilthorpe Road	18.15	1.21	4.252	A	A
Barugh Green Road	10.13	0.68	4.455	A	A

(Default Analysis Set) - 2029 B + CD + D, PM

Data Errors and Warnings

Severity	Area	Item	Description
Warning	Geometry	Barugh Green Road - Roundabout Geometry	Effective flare length is over 30m, which is outside the normal range. Treat capacities with increasing caution.

Analysis Set Details

Name	Roundabout Capacity Model	Description	Include In Report	Use Specific Demand Set(s)	Specific Demand Set (s)	Locked	Network Flow Scaling Factor (%)	Network Capacity Scaling Factor (%)	Reason For Scaling Factors
(Default Analysis Set)	ARCADY		✓				100.000	100.000	

Demand Set Details

Name	Scenario Name	Time Period Name	Description	Traffic Profile Type	Model Start Time (HH:mm)	Model Finish Time (HH:mm)	Model Time Period Length (min)	Time Segment Length (min)	Results For Central Hour Only	Single Time Segment Only	Locked	Run Automatically	Use Relationship	Relationship
2029 B + CD + D, FM	2029 B + CD + D	FM		ONE HOUR	16:30	18:00	90	15				✓		

Junction Network

Junctions

Junction	Name	Junction Type	Arm Order	Grade Separated	Large Roundabout	Do Geometric Delay	Junction Delay (s)	Junction LOS
1	(untitled)	Roundabout	1,2,3,4				11.29	B

Junction Network Options

Driving Side	Lighting
Left	Normal/unknown

Arms

Arms

Name	Arm	Name	Description
Claycliffe Road	1	Claycliffe Road	
Whaley Road	2	Whaley Road	
Wilthorpe Road	3	Wilthorpe Road	
Barugh Green Road	4	Barugh Green Road	

Capacity Options

Name	Minimum Capacity (PCU/hr)	Maximum Capacity (PCU/hr)	Assume Flat Start Profile	Initial Queue (PCU)
Claycliffe Road	0.00	99999.00		0.00
Whaley Road	0.00	99999.00		0.00
Wilthorpe Road	0.00	99999.00		0.00
Barugh Green Road	0.00	99999.00		0.00

Roundabout Geometry

Name	V - Approach road half-width (m)	E - Entry width (m)	I' - Effective flare length (m)	R - Entry radius (m)	D - Inscribed circle diameter (m)	PHI - Conflict (entry) angle (deg)	Exit Only
Claycliffe Road	3.90	5.90	12.00	12.50	35.00	19.00	
Whaley Road	4.70	5.60	9.00	15.00	35.00	25.00	
Wilthorpe Road	3.00	7.50	25.00	74.00	35.00	19.00	
Barugh Green Road	3.70	8.00	45.00	10.00	35.00	65.00	

Slope / Intercept / Capacity

Roundabout Slope and Intercept used in model

Name	Enter slope and intercept directly	Entered slope	Entered intercept (PCU/hr)	Final Slope	Final Intercept (PCU/hr)
Claycliffe Road		(calculated)	(calculated)	0.632	1590.842
Whaley Road		(calculated)	(calculated)	0.638	1632.403
Wilthorpe Road		(calculated)	(calculated)	0.716	1905.194
Barugh Green Road		(calculated)	(calculated)	0.611	1757.942

The slope and intercept shown above include any corrections and adjustments.

Traffic Flows

Demand Set Data Options

Default Vehicle Mix	Vehicle Mix Varies Over Time	Vehicle Mix Varies Over Turn	Vehicle Mix Varies Over Entry	Vehicle Mix Source	PCU Factor for a HV (PCU)	Default Turning Proportions	Estimate from entry/exit counts	Turning Proportions Vary Over Time	Turning Proportions Vary Over Turn	Turning Proportions Vary Over Entry
		✓	✓	HV Percentages	2.00				✓	✓

Entry Flows

General Flows Data

Name	Profile Type	Use Turning Counts	Average Demand Flow (PCU/hr)	Flow Scaling Factor (%)
Claycliffe Road	ONE HOUR	✓	765.00	100.000
Whaley Road	ONE HOUR	✓	178.00	100.000
Wilthorpe Road	ONE HOUR	✓	1366.00	100.000
Barugh Green Road	ONE HOUR	✓	532.00	100.000

Turning Proportions

Turning Counts / Proportions (PCU/hr) - (untitled) (for whole period)

		To			
		Claycliffe Road	Whaley Road	Wilthorpe Road	Barugh Green Road
From	Claycliffe Road	4.000	20.000	609.000	132.000
	Whaley Road	38.000	0.000	102.000	38.000
	Wilthorpe Road	666.000	68.000	37.000	595.000
	Barugh Green Road	101.000	21.000	410.000	0.000

Turning Proportions (PCU) - (untitled) (for whole period)

		To			
		Claycliffe Road	Whaley Road	Wilthorpe Road	Barugh Green Road
From	Claycliffe Road	0.01	0.03	0.80	0.17
	Whaley Road	0.21	0.00	0.57	0.21
	Wilthorpe Road	0.49	0.05	0.03	0.44
	Barugh Green Road	0.19	0.04	0.77	0.00

Vehicle Mix

Average PCU Per Vehicle - (untitled) (for whole period)

		To			
		Claycliffe Road	Whaley Road	Wilthorpe Road	Barugh Green Road
From	Claycliffe Road	1.000	1.000	1.000	1.000
	Whaley Road	1.000	1.000	1.000	1.000
	Wilthorpe Road	1.000	1.000	1.000	1.000
	Barugh Green Road	1.000	1.000	1.000	1.000

Heavy Vehicle Percentages - (untitled) (for whole period)

		To			
		Claycliffe Road	Whaley Road	Wilthorpe Road	Barugh Green Road
From	Claycliffe Road	0.0	0.0	0.0	0.0
	Whaley Road	0.0	0.0	0.0	0.0
	Wilthorpe Road	0.0	0.0	0.0	0.0
	Barugh Green Road	0.0	0.0	0.0	0.0

Results

Results Summary for whole modelled period

Name	Max RFC	Max Delay (s)	Max Queue (PCU)	Max LOS	Average Demand (PCU/hr)	Total Junction Arrivals (PCU)	Total Queueing Delay (PCU-min)	Average Queueing Delay (s)	Rate Of Queueing Delay (PCU-min/min)	Inclusive Total Queueing Delay (PCU-min)	Inclusive Average Queueing Delay (s)
Claycliffe Road	0.69	9.57	2.20	A	701.98	1052.97	120.66	6.88	1.34	120.67	6.88
Whaley Road	0.25	6.01	0.33	A	163.34	245.00	20.03	4.90	0.22	20.03	4.90
Wilthorpe Road	0.87	15.10	6.06	C	1253.47	1880.20	274.66	8.76	3.05	274.69	8.77
Barugh Green Road	0.48	5.75	0.93	A	488.17	732.26	56.73	4.65	0.63	56.74	4.65

Main Results for each time segment

Main results: (16:30-16:45)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	575.93	143.98	572.93	606.02	401.81	0.00	1336.84	933.75	0.431	0.00	0.75	4.695	A
Whaley Road	134.01	33.50	133.43	81.65	893.09	0.00	1062.44	469.29	0.126	0.00	0.14	3.872	A
Wilthorpe Road	1028.40	257.10	1023.07	867.70	158.83	0.00	1791.50	1642.94	0.574	0.00	1.33	4.654	A
Barugh Green Road	400.52	100.13	398.90	572.97	608.92	0.00	1385.89	1127.16	0.289	0.00	0.40	3.641	A

Main results: (16:45-17:00)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	687.72	171.93	686.19	725.36	481.05	0.00	1286.75	933.75	0.534	0.75	1.13	5.978	A
Whaley Road	160.02	40.00	159.79	97.75	1069.49	0.00	949.87	469.29	0.168	0.14	0.20	4.555	A
Wilthorpe Road	1228.01	307.00	1224.46	1039.06	190.21	0.00	1769.04	1642.94	0.694	1.33	2.22	6.567	A
Barugh Green Road	478.26	119.56	477.60	685.86	728.81	0.00	1312.64	1127.16	0.364	0.40	0.57	4.307	A

Main results: (17:00-17:15)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	842.28	210.57	838.15	883.43	587.93	0.00	1219.18	933.75	0.691	1.13	2.16	9.347	A
Whaley Road	195.98	49.00	195.50	119.14	1306.94	0.00	798.33	469.29	0.245	0.20	0.32	5.966	A
Wilthorpe Road	1503.99	376.00	1489.82	1269.96	232.48	0.00	1738.78	1642.94	0.865	2.22	5.76	13.735	B
Barugh Green Road	585.74	146.44	584.35	835.29	887.01	0.00	1215.98	1127.16	0.482	0.57	0.92	5.686	A

Main results: (17:15-17:30)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	842.28	210.57	842.12	890.13	590.02	0.00	1217.86	933.75	0.692	2.16	2.20	9.569	A
Whaley Road	195.98	49.00	195.97	119.95	1312.20	0.00	794.97	469.29	0.247	0.32	0.33	6.009	A
Wilthorpe Road	1503.99	376.00	1502.80	1274.78	233.38	0.00	1738.13	1642.94	0.865	5.76	6.06	15.101	C
Barugh Green Road	585.74	146.44	585.70	841.73	894.45	0.00	1211.43	1127.16	0.484	0.92	0.93	5.753	A

Main results: (17:30-17:45)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	687.72	171.93	691.86	734.94	484.13	0.00	1284.80	933.75	0.535	2.20	1.17	6.114	A
Whaley Road	160.02	40.00	160.50	98.89	1077.09	0.00	945.01	469.29	0.169	0.33	0.21	4.593	A
Wilthorpe Road	1228.01	307.00	1242.93	1046.07	191.53	0.00	1768.10	1642.94	0.695	6.06	2.33	7.042	A
Barugh Green Road	478.26	119.56	479.65	695.04	739.42	0.00	1306.16	1127.16	0.366	0.93	0.58	4.364	A

Main results: (17:45-18:00)

Name	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Exit Flow (PCU/hr)	Circulating Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	Saturation Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
Claycliffe Road	575.93	143.98	577.54	611.12	404.38	0.00	1335.21	933.75	0.431	1.17	0.77	4.762	A
Whaley Road	134.01	33.50	134.25	82.32	899.60	0.00	1058.29	469.29	0.127	0.21	0.15	3.896	A
Wilthorpe Road	1028.40	257.10	1032.25	873.86	159.99	0.00	1790.67	1642.94	0.574	2.33	1.37	4.770	A
Barugh Green Road	400.52	100.13	401.21	577.94	614.30	0.00	1382.60	1127.16	0.290	0.58	0.41	3.669	A

Queueing Delay Results for each time segment

Queueing Delay results: (16:30-16:45)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	10.88	0.73	4.695	A	A
Whaley Road	2.11	0.14	3.872	A	A
Wilthorpe Road	19.19	1.28	4.654	A	A
Barugh Green Road	5.92	0.39	3.641	A	A

Queueing Delay results: (16:45-17:00)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	16.43	1.10	5.978	A	A
Whaley Road	2.97	0.20	4.555	A	A
Wilthorpe Road	31.71	2.11	6.567	A	A
Barugh Green Road	8.36	0.56	4.307	A	A

Queueing Delay results: (17:00-17:15)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	30.46	2.03	9.347	A	A
Whaley Road	4.72	0.31	5.966	A	A
Wilthorpe Road	75.59	5.04	13.735	B	B
Barugh Green Road	13.35	0.89	5.686	A	A

Queueing Delay results: (17:15-17:30)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	32.82	2.19	9.569	A	A
Whaley Road	4.87	0.32	6.009	A	A
Wilthorpe Road	89.09	5.94	15.101	C	B
Barugh Green Road	13.88	0.93	5.753	A	A

Queueing Delay results: (17:30-17:45)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	18.26	1.22	6.114	A	A
Whaley Road	3.14	0.21	4.593	A	A
Wilthorpe Road	37.86	2.52	7.042	A	A
Barugh Green Road	8.95	0.60	4.364	A	A

Queueing Delay results: (17:45-18:00)

Name	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
Claycliffe Road	11.80	0.79	4.762	A	A
Whaley Road	2.22	0.15	3.896	A	A
Wilthorpe Road	21.22	1.41	4.770	A	A
Barugh Green Road	6.27	0.42	3.669	A	A



Junctions 8
PICADY 8 - Priority Intersection Module
Version: 8.0.6.541 [19821,26/11/2015] © Copyright TRL Limited, 2024
For sales and distribution information, program advice and maintenance, contact TRL: Tel: +44 (0)1344 770758 email: software@trl.co.uk Web: http://www.trlsoftware.co.uk
The users of this computer program for the solution of an engineering problem are in no way relieved of their responsibility for the correctness of the solution

Filename: Barugh Green Road_Site Access.arc8
Path: C:\Users\micro\Dropbox\Project Files & Management\TPS Project Files\P2636. Barugh Green, Barnsley\Technical\Junction Modelling
Report generation date: 16/12/2024 09:13:09

- » (Default Analysis Set) - 2029 B + CD + D, AM
- » (Default Analysis Set) - 2029 B + CD + D, PM

Summary of junction performance

	AM			PM		
	Queue (PCU)	Delay (s)	RFC	Queue (PCU)	Delay (s)	RFC
A1 - 2029 B + CD + D						
Stream B-C	0.02	7.06	0.02	0.01	7.73	0.01
Stream B-A	0.19	12.89	0.16	0.08	13.37	0.08
Stream C-A	-	-	-	-	-	-
Stream C-B	0.01	6.71	0.01	0.02	7.74	0.02
Stream A-B	-	-	-	-	-	-
Stream A-C	-	-	-	-	-	-

Values shown are the maximum values over all time segments. Delay is the maximum value of average delay per arriving vehicle.

"D3 - 2029 B + CD + D, AM " model duration: 07:30 - 09:00
 "D4 - 2029 B + CD + D, PM" model duration: 16:30 - 18:00

Run using Junctions 8.0.6.541 at 16/12/2024 09:13:08

File summary

Title	Barugh Green Road / Site Access
Location	Barugh Green, Barnsley
Site Number	
Date	16/12/2024
Version	
Status	(new file)
Identifier	
Client	Avant Homes
Jobnumber	P2636
Enumerator	TPS
Description	

Analysis Options

Vehicle Length (m)	Do Queue Variations	Calculate Residual Capacity	Residual Capacity Criteria Type	RFC Threshold	Average Delay Threshold (s)	Queue Threshold (PCU)
5.75			N/A	0.85	36.00	20.00

Units

Distance Units	Speed Units	Traffic Units Input	Traffic Units Results	Flow Units	Average Delay Units	Total Delay Units	Rate Of Delay Units
m	kph	PCU	PCU	perHour	s	-Min	perMin

(Default Analysis Set) - 2029 B + CD + D, AM

Data Errors and Warnings

Severity	Area	Item	Description
Warning	Minor arm flare	Site Access - Minor Arm Geometry	Is flare very short? Estimated flare length is zero but has been increased to 1 because a zero flare length is not allowed.

Analysis Set Details

Name	Roundabout Capacity Model	Description	Include In Report	Use Specific Demand Set(s)	Specific Demand Set (s)	Locked	Network Flow Scaling Factor (%)	Network Capacity Scaling Factor (%)	Reason For Scaling Factors
(Default Analysis Set)	N/A		✓				100.000	100.000	

Demand Set Details

Name	Scenario Name	Time Period Name	Description	Traffic Profile Type	Model Start Time (HH:mm)	Model Finish Time (HH:mm)	Model Time Period Length (min)	Time Segment Length (min)	Results For Central Hour Only	Single Time Segment Only	Locked	Run Automatically	Use Relationship	Relationship
2029 B + CD + D, AM	2029 B + CD + D	AM		ONE HOUR	07:30	09:00	90	15				✓		

Junction Network

Junctions

Junction	Name	Junction Type	Major Road Direction	Arm Order	Do Geometric Delay	Junction Delay (s)	Junction LOS
1	(untitled)	T-Junction	Two-way	A,B,C		11.79	B

Junction Network Options

Driving Side	Lighting
Left	Normal/unknown

Arms

Arms

Name	Arm	Name	Description	Arm Type
Barugh Green Road East	A	Barugh Green Road East		Major
Site Access	B	Site Access		Minor
Barugh Green Road West	C	Barugh Green Road West		Major

Major Arm Geometry

Name	Width of carriageway (m)	Has kerbed central reserve	Width of kerbed central reserve (m)	Has right turn bay	Width For Right Turn (m)	Visibility For Right Turn (m)	Blocks?	Blocking Queue (PCU)
Barugh Green Road West	7.00		0.00	✓	3.00	100.00		

Geometries for Arm C are measured opposite Arm B. Geometries for Arm A (if relevant) are measured opposite Arm D.

Minor Arm Geometry

Name	Minor Arm Type	Lane Width (m)	Lane Width (Left) (m)	Lane Width (Right) (m)	Width at give-way (m)	Width at 5m (m)	Width at 10m (m)	Width at 15m (m)	Width at 20m (m)	Estimate Flare Length	Flare Length (PCU)	Visibility To Left (m)	Visibility To Right (m)
Site Access	One lane plus flare				10.00	4.40	3.00	2.75	2.75	✓	1.00	120	120

Slope / Intercept / Capacity

Priority Intersection Slopes and Intercepts

Junction	Stream	Intercept (PCU/hr)	Slope for A-B	Slope for A-C	Slope for C-A	Slope for C-B
1	B-A	604.387	0.105	0.266	0.167	0.380
1	B-C	686.475	0.101	0.254	-	-
1	C-B	686.890	0.255	0.255	-	-

The slopes and intercepts shown above do NOT include any corrections or adjustments.

Streams may be combined, in which case capacity will be adjusted.

Values are shown for the first time segment only; they may differ for subsequent time segments.

Traffic Flows

Demand Set Data Options

Default Vehicle Mix	Vehicle Mix Varies Over Time	Vehicle Mix Varies Over Turn	Vehicle Mix Varies Over Entry	Vehicle Mix Source	PCU Factor for a HV (PCU)	Default Turning Proportions	Estimate from entry/exit counts	Turning Proportions Vary Over Time	Turning Proportions Vary Over Turn	Turning Proportions Vary Over Entry
		✓	✓	HV Percentages	2.00				✓	✓

Entry Flows

General Flows Data

Name	Profile Type	Use Turning Counts	Average Demand Flow (PCU/hr)	Flow Scaling Factor (%)
Barugh Green Road East	ONE HOUR	✓	524.00	100.000
Site Access	ONE HOUR	✓	56.00	100.000
Barugh Green Road West	ONE HOUR	✓	658.00	100.000

Turning Proportions

Turning Counts / Proportions (PCU/hr) - (untitled) (for whole period)

		To		
		Barugh Green Road East	Site Access	Barugh Green Road West
From	Barugh Green Road East	0.000	18.000	506.000
	Site Access	48.000	0.000	8.000
	Barugh Green Road West	655.000	3.000	0.000

Turning Proportions (PCU) - (untitled) (for whole period)

		To		
		Barugh Green Road East	Site Access	Barugh Green Road West
From	Barugh Green Road East	0.00	0.03	0.97
	Site Access	0.86	0.00	0.14
	Barugh Green Road West	1.00	0.00	0.00

Vehicle Mix

Average PCU Per Vehicle - (untitled) (for whole period)

		To		
		Barugh Green Road East	Site Access	Barugh Green Road West
From	Barugh Green Road East	1.000	1.000	1.000
	Site Access	1.000	1.000	1.000
	Barugh Green Road West	1.000	1.000	1.000

Heavy Vehicle Percentages - (untitled) (for whole period)

		To		
		Barugh Green Road East	Site Access	Barugh Green Road West
From	Barugh Green Road East	0.0	0.0	0.0
	Site Access	0.0	0.0	0.0
	Barugh Green Road West	0.0	0.0	0.0

Results

Results Summary for whole modelled period

Stream	Max RFC	Max Delay (s)	Max Queue (PCU)	Max LOS	Average Demand (PCU/hr)	Total Junction Arrivals (PCU)	Total Queueing Delay (PCU-min)	Average Queueing Delay (s)	Rate Of Queueing Delay (PCU-min/min)	Inclusive Total Queueing Delay (PCU-min)	Inclusive Average Queueing Delay (s)
B-C	0.02	7.06	0.02	A	7.34	11.01	1.22	6.66	0.01	1.22	6.66
B-A	0.16	12.89	0.19	B	44.05	66.07	12.16	11.04	0.14	12.16	11.04
C-A	-	-	-	-	601.04	901.56	-	-	-	-	-
C-B	0.01	6.71	0.01	A	2.75	4.13	0.44	6.41	0.00	0.44	6.41
A-B	-	-	-	-	16.52	24.78	-	-	-	-	-
A-C	-	-	-	-	464.31	696.47	-	-	-	-	-

Main Results for each time segment

Main results: (07:30-07:45)

Stream	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
B-C	6.02	1.51	5.98	0.00	575.15	0.010	0.00	0.01	6.324	A
B-A	36.14	9.03	35.76	0.00	418.15	0.086	0.00	0.09	9.406	A
C-A	493.12	123.28	493.12	0.00	-	-	-	-	-	-
C-B	2.26	0.56	2.24	0.00	586.47	0.004	0.00	0.00	6.161	A
A-B	13.55	3.39	13.55	0.00	-	-	-	-	-	-
A-C	380.94	95.24	380.94	0.00	-	-	-	-	-	-

Main results: (07:45-08:00)

Stream	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
B-C	7.19	1.80	7.18	0.00	552.12	0.013	0.01	0.01	6.605	A
B-A	43.15	10.79	43.02	0.00	382.01	0.113	0.09	0.13	10.620	B
C-A	588.83	147.21	588.83	0.00	-	-	-	-	-	-
C-B	2.70	0.67	2.69	0.00	566.98	0.005	0.00	0.00	6.379	A
A-B	16.18	4.05	16.18	0.00	-	-	-	-	-	-
A-C	454.88	113.72	454.88	0.00	-	-	-	-	-	-

Main results: (08:00-08:15)

Stream	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
B-C	8.81	2.20	8.79	0.00	518.90	0.017	0.01	0.02	7.056	A
B-A	52.85	13.21	52.61	0.00	332.02	0.159	0.13	0.19	12.871	B
C-A	721.17	180.29	721.17	0.00	-	-	-	-	-	-
C-B	3.30	0.83	3.30	0.00	540.03	0.006	0.00	0.01	6.706	A
A-B	19.82	4.95	19.82	0.00	-	-	-	-	-	-
A-C	557.12	139.28	557.12	0.00	-	-	-	-	-	-

Main results: (08:15-08:30)

Stream	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
B-C	8.81	2.20	8.81	0.00	518.74	0.017	0.02	0.02	7.058	A
B-A	52.85	13.21	52.84	0.00	332.03	0.159	0.19	0.19	12.894	B
C-A	721.17	180.29	721.17	0.00	-	-	-	-	-	-
C-B	3.30	0.83	3.30	0.00	540.03	0.006	0.01	0.01	6.706	A
A-B	19.82	4.95	19.82	0.00	-	-	-	-	-	-
A-C	557.12	139.28	557.12	0.00	-	-	-	-	-	-

Main results: (08:30-08:45)

Stream	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
B-C	7.19	1.80	7.21	0.00	551.88	0.013	0.02	0.01	6.608	A
B-A	43.15	10.79	43.39	0.00	382.02	0.113	0.19	0.13	10.639	B
C-A	588.83	147.21	588.83	0.00	-	-	-	-	-	-
C-B	2.70	0.67	2.70	0.00	566.98	0.005	0.01	0.00	6.379	A
A-B	16.18	4.05	16.18	0.00	-	-	-	-	-	-
A-C	454.88	113.72	454.88	0.00	-	-	-	-	-	-

Main results: (08:45-09:00)

Stream	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
B-C	6.02	1.51	6.03	0.00	574.87	0.010	0.01	0.01	6.330	A
B-A	36.14	9.03	36.27	0.00	418.17	0.086	0.13	0.10	9.429	A
C-A	493.12	123.28	493.12	0.00	-	-	-	-	-	-
C-B	2.26	0.56	2.26	0.00	586.47	0.004	0.00	0.00	6.163	A
A-B	13.55	3.39	13.55	0.00	-	-	-	-	-	-
A-C	380.94	95.24	380.94	0.00	-	-	-	-	-	-

Queueing Delay Results for each time segment
Queueing Delay results: (07:30-07:45)

Stream	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
B-C	0.15	0.01	6.324	A	A
B-A	1.35	0.09	9.406	A	A
C-A	-	-	-	-	-
C-B	0.06	0.00	6.161	A	A
A-B	-	-	-	-	-
A-C	-	-	-	-	-

Queueing Delay results: (07:45-08:00)

Stream	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
B-C	0.19	0.01	6.605	A	A
B-A	1.83	0.12	10.620	B	B
C-A	-	-	-	-	-
C-B	0.07	0.00	6.379	A	A
A-B	-	-	-	-	-
A-C	-	-	-	-	-

Queueing Delay results: (08:00-08:15)

Stream	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
B-C	0.25	0.02	7.056	A	A
B-A	2.69	0.18	12.871	B	B
C-A	-	-	-	-	-
C-B	0.09	0.01	6.706	A	A
A-B	-	-	-	-	-
A-C	-	-	-	-	-

Queueing Delay results: (08:15-08:30)

Stream	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
B-C	0.26	0.02	7.058	A	A
B-A	2.81	0.19	12.894	B	B
C-A	-	-	-	-	-
C-B	0.09	0.01	6.706	A	A
A-B	-	-	-	-	-
A-C	-	-	-	-	-

Queueing Delay results: (08:30-08:45)

Stream	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
B-C	0.20	0.01	6.608	A	A
B-A	2.00	0.13	10.639	B	B
C-A	-	-	-	-	-
C-B	0.07	0.00	6.379	A	A
A-B	-	-	-	-	-
A-C	-	-	-	-	-

Queueing Delay results: (08:45-09:00)

Stream	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
B-C	0.16	0.01	6.330	A	A
B-A	1.48	0.10	9.429	A	A
C-A	-	-	-	-	-
C-B	0.06	0.00	6.163	A	A
A-B	-	-	-	-	-
A-C	-	-	-	-	-

(Default Analysis Set) - 2029 B + CD + D, PM

Data Errors and Warnings

Severity	Area	Item	Description
Warning	Minor arm flare	Site Access - Minor Arm Geometry	Is flare very short? Estimated flare length is zero but has been increased to 1 because a zero flare length is not allowed.

Analysis Set Details

Name	Roundabout Capacity Model	Description	Include In Report	Use Specific Demand Set(s)	Specific Demand Set (s)	Locked	Network Flow Scaling Factor (%)	Network Capacity Scaling Factor (%)	Reason For Scaling Factors
(Default Analysis Set)	N/A		✓				100.000	100.000	

Demand Set Details

Name	Scenario Name	Time Period Name	Description	Traffic Profile Type	Model Start Time (HH:mm)	Model Finish Time (HH:mm)	Model Time Period Length (min)	Time Segment Length (min)	Results For Central Hour Only	Single Time Segment Only	Locked	Run Automatically	Use Relationship	Relationship
2029 B + CD + D, FM	2029 B + CD + D	FM		ONE HOUR	16:30	18:00	90	15				✓		

Junction Network

Junctions

Junction	Name	Junction Type	Major Road Direction	Arm Order	Do Geometric Delay	Junction Delay (s)	Junction LOS
1	(untitled)	T-Junction	Two-way	A,B,C		11.50	B

Junction Network Options

Driving Side	Lighting
Left	Normal/unknown

Arms

Arms

Name	Arm	Name	Description	Arm Type
Barugh Green Road East	A	Barugh Green Road East		Major
Site Access	B	Site Access		Minor
Barugh Green Road West	C	Barugh Green Road West		Major

Major Arm Geometry

Name	Width of carriageway (m)	Has kerbed central reserve	Width of kerbed central reserve (m)	Has right turn bay	Width For Right Turn (m)	Visibility For Right Turn (m)	Blocks?	Blocking Queue (PCU)
Barugh Green Road West	7.00		0.00	✓	3.00	100.00		

Geometries for Arm C are measured opposite Arm B. Geometries for Arm A (if relevant) are measured opposite Arm D.

Minor Arm Geometry

Name	Minor Arm Type	Lane Width (m)	Lane Width (Left) (m)	Lane Width (Right) (m)	Width at give-way (m)	Width at 5m (m)	Width at 10m (m)	Width at 15m (m)	Width at 20m (m)	Estimate Flare Length	Flare Length (PCU)	Visibility To Left (m)	Visibility To Right (m)
Site Access	One lane plus flare				10.00	4.40	3.00	2.75	2.75	✓	1.00	120	120

Slope / Intercept / Capacity

Priority Intersection Slopes and Intercepts

Junction	Stream	Intercept (PCU/hr)	Slope for A-B	Slope for A-C	Slope for C-A	Slope for C-B
1	B-A	605.019	0.105	0.266	0.168	0.381
1	B-C	684.561	0.100	0.254	-	-
1	C-B	686.890	0.255	0.255	-	-

The slopes and intercepts shown above do NOT include any corrections or adjustments.

Streams may be combined, in which case capacity will be adjusted.

Values are shown for the first time segment only; they may differ for subsequent time segments.

Traffic Flows

Demand Set Data Options

Default Vehicle Mix	Vehicle Mix Varies Over Time	Vehicle Mix Varies Over Turn	Vehicle Mix Varies Over Entry	Vehicle Mix Source	PCU Factor for a HV (PCU)	Default Turning Proportions	Estimate from entry/exit counts	Turning Proportions Vary Over Time	Turning Proportions Vary Over Turn	Turning Proportions Vary Over Entry
		✓	✓	HV Percentages	2.00				✓	✓

Entry Flows

General Flows Data

Name	Profile Type	Use Turning Counts	Average Demand Flow (PCU/hr)	Flow Scaling Factor (%)
Barugh Green Road East	ONE HOUR	✓	765.00	100.000
Site Access	ONE HOUR	✓	23.00	100.000
Barugh Green Road West	ONE HOUR	✓	518.00	100.000

Turning Proportions

Turning Counts / Proportions (PCU/hr) - (untitled) (for whole period)

		To		
		Barugh Green Road East	Site Access	Barugh Green Road West
From	Barugh Green Road East	0.000	44.000	721.000
	Site Access	20.000	0.000	3.000
	Barugh Green Road West	511.000	7.000	0.000

Turning Proportions (PCU) - (untitled) (for whole period)

		To		
		Barugh Green Road East	Site Access	Barugh Green Road West
From	Barugh Green Road East	0.00	0.06	0.94
	Site Access	0.87	0.00	0.13
	Barugh Green Road West	0.99	0.01	0.00

Vehicle Mix

Average PCU Per Vehicle - (untitled) (for whole period)

		To		
From		Barugh Green Road East	Site Access	Barugh Green Road West
	Barugh Green Road East	1.000	1.000	1.000
	Site Access	1.000	1.000	1.000
	Barugh Green Road West	1.000	1.000	1.000

Heavy Vehicle Percentages - (untitled) (for whole period)

		To		
From		Barugh Green Road East	Site Access	Barugh Green Road West
	Barugh Green Road East	0.0	0.0	0.0
	Site Access	0.0	0.0	0.0
	Barugh Green Road West	0.0	0.0	0.0

Results

Results Summary for whole modelled period

Stream	Max RFC	Max Delay (s)	Max Queue (PCU)	Max LOS	Average Demand (PCU/hr)	Total Junction Arrivals (PCU)	Total Queueing Delay (PCU-min)	Average Queueing Delay (s)	Rate Of Queueing Delay (PCU-min/min)	Inclusive Total Queueing Delay (PCU-min)	Inclusive Average Queueing Delay (s)
B-C	0.01	7.73	0.01	A	2.75	4.13	0.50	7.20	0.01	0.50	7.20
B-A	0.08	13.37	0.08	B	18.35	27.53	5.21	11.36	0.06	5.21	11.36
C-A	-	-	-	-	468.90	703.35	-	-	-	-	-
C-B	0.02	7.74	0.02	A	6.42	9.64	1.16	7.20	0.01	1.16	7.20
A-B	-	-	-	-	40.38	60.56	-	-	-	-	-
A-C	-	-	-	-	661.60	992.40	-	-	-	-	-

Main Results for each time segment

Main results: (16:30-16:45)

Stream	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
B-C	2.26	0.56	2.24	0.00	538.26	0.004	0.00	0.00	6.715	A
B-A	15.06	3.76	14.90	0.00	390.43	0.039	0.00	0.04	9.582	A
C-A	384.71	96.18	384.71	0.00	-	-	-	-	-	-
C-B	5.27	1.32	5.23	0.00	540.28	0.010	0.00	0.01	6.728	A
A-B	33.13	8.28	33.13	0.00	-	-	-	-	-	-
A-C	542.81	135.70	542.81	0.00	-	-	-	-	-	-

Main results: (16:45-17:00)

Stream	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
B-C	2.70	0.67	2.69	0.00	509.34	0.005	0.00	0.01	7.104	A
B-A	17.98	4.49	17.92	0.00	348.77	0.052	0.04	0.05	10.880	B
C-A	459.38	114.84	459.38	0.00	-	-	-	-	-	-
C-B	6.29	1.57	6.28	0.00	511.82	0.012	0.01	0.01	7.120	A
A-B	39.56	9.89	39.56	0.00	-	-	-	-	-	-
A-C	648.16	162.04	648.16	0.00	-	-	-	-	-	-

Main results: (17:00-17:15)

Stream	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
B-C	3.30	0.83	3.30	0.00	468.94	0.007	0.01	0.01	7.731	A
B-A	22.02	5.51	21.91	0.00	291.18	0.076	0.05	0.08	13.363	B
C-A	562.62	140.66	562.62	0.00	-	-	-	-	-	-
C-B	7.71	1.93	7.69	0.00	472.48	0.016	0.01	0.02	7.745	A
A-B	48.44	12.11	48.44	0.00	-	-	-	-	-	-
A-C	793.84	198.46	793.84	0.00	-	-	-	-	-	-

Main results: (17:15-17:30)

Stream	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
B-C	3.30	0.83	3.30	0.00	468.86	0.007	0.01	0.01	7.732	A
B-A	22.02	5.51	22.02	0.00	291.18	0.076	0.08	0.08	13.374	B
C-A	562.62	140.66	562.62	0.00	-	-	-	-	-	-
C-B	7.71	1.93	7.71	0.00	472.48	0.016	0.02	0.02	7.745	A
A-B	48.44	12.11	48.44	0.00	-	-	-	-	-	-
A-C	793.84	198.46	793.84	0.00	-	-	-	-	-	-

Main results: (17:30-17:45)

Stream	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
B-C	2.70	0.67	2.70	0.00	509.22	0.005	0.01	0.01	7.106	A
B-A	17.98	4.49	18.08	0.00	348.78	0.052	0.08	0.06	10.891	B
C-A	459.38	114.84	459.38	0.00	-	-	-	-	-	-
C-B	6.29	1.57	6.31	0.00	511.82	0.012	0.02	0.01	7.123	A
A-B	39.56	9.89	39.56	0.00	-	-	-	-	-	-
A-C	648.16	162.04	648.16	0.00	-	-	-	-	-	-

Main results: (17:45-18:00)

Stream	Total Demand (PCU/hr)	Junction Arrivals (PCU)	Entry Flow (PCU/hr)	Pedestrian Demand (Ped/hr)	Capacity (PCU/hr)	RFC	Start Queue (PCU)	End Queue (PCU)	Delay (s)	LOS
B-C	2.26	0.56	2.26	0.00	538.11	0.004	0.01	0.00	6.720	A
B-A	15.06	3.76	15.11	0.00	390.43	0.039	0.06	0.04	9.594	A
C-A	384.71	96.18	384.71	0.00	-	-	-	-	-	-
C-B	5.27	1.32	5.28	0.00	540.28	0.010	0.01	0.01	6.728	A
A-B	33.13	8.28	33.13	0.00	-	-	-	-	-	-
A-C	542.81	135.70	542.81	0.00	-	-	-	-	-	-

Queueing Delay Results for each time segment

Queueing Delay results: (16:30-16:45)

Stream	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
B-C	0.06	0.00	6.715	A	A
B-A	0.57	0.04	9.582	A	A
C-A	-	-	-	-	-
C-B	0.14	0.01	6.728	A	A
A-B	-	-	-	-	-
A-C	-	-	-	-	-

Queueing Delay results: (16:45-17:00)

Stream	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
B-C	0.08	0.01	7.104	A	A
B-A	0.78	0.05	10.880	B	B
C-A	-	-	-	-	-
C-B	0.18	0.01	7.120	A	A
A-B	-	-	-	-	-
A-C	-	-	-	-	-

Queueing Delay results: (17:00-17:15)

Stream	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
B-C	0.10	0.01	7.731	A	A
B-A	1.17	0.08	13.363	B	B
C-A	-	-	-	-	-
C-B	0.24	0.02	7.745	A	A
A-B	-	-	-	-	-
A-C	-	-	-	-	-

Queueing Delay results: (17:15-17:30)

Stream	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
B-C	0.11	0.01	7.732	A	A
B-A	1.21	0.08	13.374	B	B
C-A	-	-	-	-	-
C-B	0.25	0.02	7.745	A	A
A-B	-	-	-	-	-
A-C	-	-	-	-	-

Queueing Delay results: (17:30-17:45)

Stream	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
B-C	0.08	0.01	7.106	A	A
B-A	0.85	0.06	10.891	B	B
C-A	-	-	-	-	-
C-B	0.19	0.01	7.123	A	A
A-B	-	-	-	-	-
A-C	-	-	-	-	-




Queueing Delay results: (17:45-18:00)

Stream	Queueing Total Delay (PCU-min)	Queueing Rate Of Delay (PCU-min/min)	Average Delay Per Arriving Vehicle (s)	Unsignalised Level Of Service	Signalised Level Of Service
B-C	0.06	0.00	6.720	A	A
B-A	0.63	0.04	9.594	A	A
C-A	-	-	-	-	-
C-B	0.15	0.01	6.728	A	A
A-B	-	-	-	-	-
A-C	-	-	-	-	-



Appendix J

Proposed Site Access Arrangements / Visibility Splays



17.12.24	A	Site layout plan updated to final layout	JA	JT
Date	Rev	Description	Drawn	Checked



ADDRESS TPS Transport Consultants Ltd,
Stonebridge Court,
151-153 Wakefield Road,
Horbury, Wakefield,
WF6 5HQ

T: 01934 444630
e: info@tpsconsultants.co.uk
www.tpsconsultants.co.uk

Project
Proposed residential development,
Avant Homes,
Barugh Green Road, Barnsley

Title
Proposed right turn ghost island
general arrangement drawing

INFORMATION			
Scale @ A1	Date Created	Drawn	Checked
1:250	17.05.24	JT	JT
TPS Project Number		Revision	
P2636		B	
Drawing Number			
D - 1001			




Standard Notes

1. This drawing is to be read in conjunction with all relevant Architect's and Engineer's drawings and specification.
2. This drawing should not be scaled.

Location Plan

Notes and Keys

Date	Rev	Description	Drawn	Checked
17/12/24	A	Updated in line with final layout	JA	JT



TPS

ADDRESS: TPS Transport Consultants Ltd, Stonebridge Court, 151-153 Wakefield Road, Holbury, Wakefield, WF4 5HQ

t: 01934 644638
e: info@tpsconsultants.co.uk
www.tpsconsultants.co.uk

Project
Barugh Green
Barnsley

Title
Visibility Splays and Forward Visibility
in line with 20mph speed limit

Status

INFORMATION


Scale @ A1	Date Created	Drawn	Checked
	05/12/24	JA	JT

TPS Project Number	Revision
P2636	A


Drawing Number
P2636 - V - 1001

Appendix K

Swept Path Analysis




11.6 Refuse
 Overall Length 11.600m
 Overall Width 2.550m
 Overall Body Height 3.760m
 Min Body Ground Clearance 0.312m
 Track Width 2.550m
 Lock to lock time 4.00s
 Kerb to Kerb Turning Radius 10.150m



17.12.24	A	Updated in line with final layout	JA	JT
Date	Rev	Description	Drawn	Chkd

TPS Transport Consultants Ltd
 Stonebridge Court
 151-153 Wakefield Road
 Horbury
 Wakefield
 WF4 5HQ
 t: 01924 664638
 e: info@tpsconsultants.co.uk
 www.tpsconsultants.co.uk

Project Barugh Green, Barnsley				
Title Swept Path Analysis - 11.6m Refuse Vehicle				
Date 05/12/24	Designed by JA	Checked by JT		
Drawing Number P2636 - T - 1001			Scale @ A3 1:250	Revision A



Dennis Sabre Fire Tender (LWB)
 Overall Length 7.700m
 Overall Width 2.430m
 Overall Body Height 3.512m
 Min Body Ground Clearance 0.397m
 Track Width 2.380m
 Lock to lock time 5.00s
 Kerb to Kerb Turning Radius 7.400m

17.12.24	A	Updated in line with final layout	JA	JT
Date	Rev	Description	Drawn	Chkd

TPS Transport Consultants Ltd
 Stonebridge Court
 151-153 Wakefield Road
 Horbury
 Wakefield
 WF4 5HQ
 t: 01924 664638
 e: info@tpsconsultants.co.uk
 www.tpsconsultants.co.uk

Project				
Barugh Green, Barnsley				
Title				
Swept Path Analysis - Fire Tender				
Date	Designed by	Checked by		
05/12/24	JA	JT		
Drawing Number			Scale @ A3	Revision
P2636 - T - 1002			1:250	A