



Sales Office: 0845 3020600
Technical Support: 08704 113344
Manufacturing Standards: see page 19

BPCO10

Q24 110
Q24 111

Kerb, Channel & Edging..... page 232
Block Paving..... page 104
Block Paving..... page 105
Block Paving..... page 108
Block Paving..... page 110
Block Paving..... page 122

Keyblok

Concrete Block Paving



- Concrete Block Paving.
- 9 colour finishes.
- 200 x 100mm rectangular block paver with integral spacers.
- UK's most trusted concrete block paving. Highly durable with chamfered top surface profile.
- Suitable for use in any loading application.
- Typical applications: Ports, Airports, Service Yards and Adopted Highways.
- Compliant to BS EN 1338:2003.
- Bond Pattern: Herringbone, Stretcher Course, Basketweave.
- Keyblok can be machine laid. Please refer to the Machine Lay section, page 122.

Colours

Precise colour and surface texture should be judged from actual materials rather than photographic representations.



Burnt Ochre, Keyblok, Port Glasgow

Thickness (mm)	Plan Size (mm nom.)	Pack Size (m ² approx)	Edge	Unit Weight (kg approx)	Pack Weight (kg approx)	Brindle (Ref No.)	Burnt Ochre (Ref No.)	Bracken (Ref No.)	Natural (Ref No.)	Charcoal (Ref No.)	Buff (Ref No.)	Marigold (Ref No.)	Red (Ref No.)	White (Ref No.)
60mm	200 x 100	8.08	Chamfered	2.8	1131	PV2051750	PV2052000	PV2052250	PV2050250	PV2050500	PV2050750	PV2051000	PV2051500	PV2604500
65mm	200 x 100	7.44	Chamfered	3	1116	PV4051750	PV4052000		PV4050250	PV4050500	PV4050750	PV4051000	PV4051500	
80mm	200 x 100	6.16	Chamfered	3.7	1140	PV5051750	PV5052000	PV5052250	PV5050250	PV5050500	PV5050750	PV5051000	PV5051500	PV5604500
100mm	200 x 100	4.88	Chamfered	4.6	1122	PV6051750	PV6052000		PV6050250	PV6050500	PV6050750	PV6051000	PV6051500	

Keyblok with reference numbers indicated in bold black are available ex-stock.
Keyblok with reference numbers indicated in light black are manufactured to order. Contact our sales office to discuss your requirements.

*Natural products are manufactured from aggregates sourced locally to the works and contain no pigmentation, therefore colour variation between products from different works is possible.

◀ Charcoal Keyblok, John Pounds Medical Centre, Portsmouth