



### Key

- Application site boundary
- Existing vegetation & associated RPA to be retained
- Existing vegetation to be removed
- Existing hedge/row to be retained as shown & brought into positive management. Hedge to be filled as required with native hedgerow species.
- LEAP
- LEAP

### Plant Schedule

#### Trees - Plots

Abbr	Species	Supply	Size	Birth	Number
AMARH	Amelanchier arborea 'Robit Hill'	HS1d BR	350-425cm	12-14cm	1
BETPE	Betula pendula	HS1d BR	350-425cm	12-14cm	4
ILENS	Ilex 'New Dawn'	HS1d BR	350-425cm	12-14cm	9
LIQUES	Ligustrum lucidum 'Excelsium Superbum'	HS1d BR	350-425cm	12-14cm	5
MAKOSI	Magnolia kobus 'Isis'	HS1d BR	350-425cm	12-14cm	5
QUERO	Quercus 'acutifolia'	HS1d BR	425-600cm	14-16cm	3
TREES	<i>Gleditsia tracanthos</i> 'Skyline'	HS1d BR	425-600cm	14-16cm	5
Total: 28					

#### Shrubs - Public Open Space

Abbr	Species	Supply	Size	Birth	Number
ACECAM	Acer campestre	SS1d BR	300-350cm	10-12cm	3
ALCO	Alnus cordata	SS1d BR	300-350cm	10-12cm	3
BETPE	Betula pendula	SS1d BR	300-350cm	10-12cm	6
FAGSY	Fagus sylvatica	SS1d BR	300-350cm	10-12cm	6
PRUPA	Prunus padus	SS1d BR	300-350cm	10-12cm	3
PYCOM	Pyrus communis	SS1d BR	300-350cm	10-12cm	5
QUERO	Quercus 'acutifolia'	SS1d BR	300-350cm	10-12cm	10
SORBAR	Sorbus aria 'Magical'	SS1d BR	300-350cm	10-12cm	4
TILCO	Tilia cordata	SS1d BR	300-350cm	10-12cm	10
ALCO	Alnus cordata	HS1d BR	350-425cm	12-14cm	5
BETPE	Betula pendula	HS1d BR	350-425cm	12-14cm	16
MALTR	Malus troyana	HS1d BR	350-425cm	12-14cm	3
ACECAM	Acer campestre 'Streetwise'	HS1d BR	425-600cm	14-16cm	8
AMARH	Amelanchier arborea 'Robit Hill'	HS1d BR	425-600cm	14-16cm	12
BETPE	Betula pendula	HS1d BR	425-600cm	14-16cm	4
TILCOOR	Tilia cordata 'Greening'	HS1d BR	425-600cm	14-16cm	1
PYRCACH	Pyrus catus 'Chancellor'	HS1d BR	425-600cm	14-16cm	1
Total: 109					

#### Specimen Shrubs

Abbr	Species	Pot Size	Height	Habit	Number
PHOAR	Phormium 'Amazing Red'	25L	100-150cm	Top Cm	10
PHOJE	Phormium 'Jester'	25L	100-125cm	Top Cm	5
PHOWAV	Phormium 'Yellow Wave'	25L	100-125cm	Top Cm	5
PHOWIS	Phormium 'Fraser Red'	50L	200-225cm	SS1d 10-12cm	4
Total: 24					

#### Single-Species Hedgerows

Abbr	Species	Pot Size	Height	Habit	Density	Length	Number
VIBTEVP	Viburnum tinus 'Eve Pinner'	5L	40-60cm	Bushy	0.32cr	255.27m	726
PRULU	Prunus laetifolia	10L	80-100cm	Bushy	0.42cr	480.11m	1225
VIBTEVP	Viburnum tinus 'Eve Pinner'	10L	80-100cm	Bushy	0.32cr	87.22m	236
Total: 2927							

#### Shrubs - Plots

Abbr	Species	Pot Size	Height	Habit	Density	Area	Number
CORALE	Cornus alba 'Elegansissima'	3L	60-80cm	Branching	0.82cr	46.7m²	61
AUCJA	Aucuba japonica	10L	60-80cm	Bushy	0.82cr	44.23m²	77
AUCJACR	Aucuba japonica 'Crotolaria'	10L	40-60cm	Bushy	0.82cr	2.47m²	4
BRASU	Brachyglottis 'Sunshine'	10L	40-60cm	Bushy	0.72cr	32.34m²	62
CEATHR	Ceanothus thyrsiflorus 'repens'	10L	40-60cm	Bushy	0.72cr	34.74m²	61
CHOPP	Choisy 'Aster Pearl'	10L	40-60cm	Bushy	0.72cr	42.1m²	97
CHOTES	Choisy 'terata 'Sundance'	10L	40-60cm	Bushy	0.72cr	47.8m²	109
ELAPUMA	Elaeagnus pungens 'Maculata'	10L	80-100cm	Bushy	0.82cr	46.7m²	61
EUOFOENG	Eucyrtus fortunei 'Emerald 'n' Gold'	10L	40-60cm	Bushy	0.72cr	200.76m²	488
EUOFOENG	Eucyrtus fortunei 'Emerald Galaxy'	10L	40-60cm	Bushy	0.72cr	95.51m²	216
EUOFOENG	Eucyrtus fortunei 'Emerald Galaxy'	10L	80-100cm	Bushy	0.72cr	15.66m²	4
FATJA	Fatsia japonica	10L	60-80cm	Bushy	0.82cr	44.23m²	77
HEBMA	Hebe 'Margery'	10L	30-40cm	Bushy	0.82cr	11.65m²	26
HEBMA	Hebe 'Mrs Winderley'	10L	30-40cm	Bushy	0.72cr	24.79m²	59
HEBPO	Hebe 'Purple Queen'	10L	40-60cm	Bushy	0.82cr	24.32m²	56
HEBALRE	Hebe 'albacora 'Red Edge'	10L	30-40cm	Bushy	0.72cr	175.54m²	408
HEBMA	Hebe 'prigutata 'Suntanstar'	10L	30-40cm	Bushy	0.72cr	106.64m²	242
HYTH	Hypericum 'Hidotea'	10L	40-60cm	Bushy	0.82cr	11.65m²	26
LAVANMU	Lavandula angustifolia 'Munstead'	10L	30-40cm	Bushy	0.72cr	54.33m²	126
LAVIN	Lavandula 'intermedia 'Cross'	10L	30-40cm	Bushy	0.72cr	48.13m²	116
LONNIG	Lonicera 'nieba 'Bagueand's Gold'	10L	40-60cm	Bushy	0.72cr	5.97m²	9
PHORRER	Photinia x fraseri 'Red Robin'	10L	80-100cm	Bushy	0.82cr	2.47m²	4
PITTEOB	Pittosporum tenuifolium 'Coffi Bat'	10L	30-40cm	Bushy	0.72cr	44.81m²	100
PITTEB	Pittosporum tenuifolium 'Tom Thum'	10L	30-40cm	Bushy	0.72cr	9.79m²	22
PRULACL	Prunus laurocerasus 'Oto Lyuker'	10L	60-80cm	Bushy	0.82cr	9.99m²	18
PRULACL	Prunus laurocerasus 'Oto Lyuker'	10L	60-80cm	Bushy	0.72cr	29.56m²	70
SARHCHU	Sarcococca 'chrysantha'	10L	30-40cm	Bushy	0.72cr	66.05m²	150
SKUJARU	Skimmia japonica 'Fragrans'	10L	40-60cm	Bushy	0.72cr	23.89m²	52
SKUJARU	Skimmia japonica 'Rubra'	10L	40-60cm	Bushy	0.72cr	95.88m²	221
VIBDA	Viburnum davidii	10L	40-60cm	Bushy	0.72cr	122.56m²	270
VIBTI	Viburnum tinus	10L	40-60cm	Bushy	0.72cr	17.64m²	37
Total: 1574.99m² - 1574.99m²							

#### Shrubs - PDS

Abbr	Species	Pot Size	Height	Habit	Density	Area	Number
CORALS	Cornus alba 'Sibirica'	3L	60-80cm	Branching	0.82cr	72.21m²	116
CORSAMF	Cornus sanguinea 'Midwinter Fire'	3L	60-80cm	Branching	0.82cr	74.66m²	118
CORSTF	Cornus stolonifera 'Flavescens'	3L	60-80cm	Branching	0.82cr	72.21m²	116
Total: 258.08m²							

#### Shrubs - Play

Abbr	Species	Pot Size	Height	Habit	Density	Area	Number
CHOSNA	Choisy 'terata 'Sundance'	3L	20-30cm	Bushy	0.62cr	7.52m²	22
LAVANMU	Lavandula angustifolia 'Munstead'	3L	20-30cm	Bushy	0.62cr	6.06m²	17
ROOF	Rosmarinus officinalis	3L	20-30cm	Bushy	0.62cr	4.54m²	13
STITE	Thuja tonkawana	3L	Full Pot	0.62cr	7.52m²	22	
THYVU	Thymus vulgaris	3L	Full Pot	0.62cr	4.54m²	13	
Total: 30.28m²							

#### Native Hedgerow - Species-Rich (Transplants)

Abbr	Species	Supply	Height	Density	Mix %	Length	Number	
CORSA	Cornus sanguinea	T1-1 3Bx60	60-80cm	0.32cr	Double Staggered at 0.5m offset	10%	10.07m	71
CRAMON	Crataegus monogyna	T1-1 3Bx60	60-80cm	0.32cr	Double Staggered at 0.5m offset	35%	35.27m	257
EUOFOENG	Eucyrtus fortunei	T1-1 3Bx60	60-80cm	0.32cr	Double Staggered at 0.5m offset	15%	10.07m	71
ILEX	Ilex aquifolium	2L 3Bx60	40-60cm	0.32cr	Double Staggered at 0.5m offset	15%	15.11m	104
LIQVU	Ligustrum vulgare	T1-1 3Bx60	60-80cm	0.32cr	Double Staggered at 0.5m offset	15%	15.11m	104
ROSCA	Rosa canina	T1-1 3Bx60	60-80cm	0.32cr	Double Staggered at 0.5m offset	15%	15.04m	37
VIBOP	Viburnum opulus	T1-1 3Bx60	60-80cm	0.32cr	Double Staggered at 0.5m offset	10%	10.07m	71
Total: 100.74m² - Total: 695								

#### Native Scrub - Species-Rich

Abbr	Species	Supply	Height	Mix %	Density	Area	Number
CORSA	Cornus sanguinea	T1-1 3Bx60	60-80cm	15%	0.2cr	55.54m²	56
CORAV	Cornus avellana	T1-1 3Bx60	60-80cm	35%	0.2cr	100.33m²	131
EUOFOENG	Eucyrtus fortunei	T1-1 3Bx60	60-80cm	10%	0.2cr	37.23m²	58
ILEX	Ilex aquifolium	2L 3Bx60	40-60cm	15%	0.2cr	55.54m²	56
LIQVU	Ligustrum vulgare	T1-1 3Bx60	60-80cm	5%	0.2cr	18.85m²	19
ROSCA	Rosa canina	T1-1 3Bx60	60-80cm	10%	0.2cr	37.23m²	58
VIBOP	Viburnum opulus	T1-1 3Bx60	60-80cm	10%	0.2cr	37.23m²	58
Total: 372.95m² - Total: 376							

#### Bulbs

Abbr	Species	Supply	Density	Number
CROCHBP	Crocus chrysanthus 'Blue Pearl'	Bulb	200m²	303
CROCHCB	Crocus chrysanthus 'Cream Beauty'	Bulb	200m²	303
GALM	Galenium 'iris'	Bulb	200m²	403
MUSARBS	Muscari americanum 'Blue Spike'	Bulb	200m²	403
NARCA	Narcissus 'Carnivalus'	Bulb	200m²	303
NARTT	Narcissus 'Tete a Tete'	Bulb	200m²	303
Total: 2018				

#### Turf & Seeding

- Turf**: Turf to gardens to be laid as Rolawn 'Medalion', or similar approved.
- Amenity Grass**: A22 low maintenance seed mixture, as supplied by Geminal (www.geminal.com) or similar approved.
- Meadow Grassland**: EM1 seed mixture for meadows, as supplied by Emorsgate Seeds (www.wildseed.co.uk) or similar approved.
- Wet Meadow Grassland**: EM1 seed mixture for wetlands, as supplied by Emorsgate Seeds (www.wildseed.co.uk) or similar approved.

Drawing to be read in conjunction with GLV0211 SP 01 Landscape Specification.