This drawing is the copyright of Rosetta Landscape Design and cannot be reproduced in any form without the express consent of the company. Written and scaled dimensions to be checked on site, any discrepancies reported prior to work commencing. **If in doubt please ask.**

This drawing has been prepared for the purpose of planning approval.

Planting Notes

Topsoil shall be a minimum of 400mm depth over planting beds and graded to fall. Imported topsoil must be BS3882:2007 compliant and existing topsoil must be cultivated in accordance with BS3882:2007. No cultivation should take place in wet/ waterlogged conditions.

Herbicide and cultivation: Topsoil to be treated with two applications of herbicide prior to planting, where necessary, strictly in accordance with the Control of Pesticides Regulations 1986 (as amended 1997 or, otherwise, updated/superseded legislation) and following manufacturer's instructions by qualified staff. The topsoil shall than be cultivated to 150mm depth.

Planting: All planting and turfing shall conform to BS: 3936: 1992 and BS:4428:1989.

Trees: Standard trees to be planted in pits 800x800x450mm or dimensions of rootball, whichever is greater. Tree to be supported by 1N stake (1500mm long, per tree, 600mm above ground, 75mm diameter) and 1N bio-degradeable tie. Heavy Standard trees to be planted in pits 1000x1000x600mm or dimensions of rootball, whichever is greater. Tree to be supported by 2N stakes (1500mm long, 600mm above ground, 75mm diameter), cross bar (400x100x15mm) and 1N/ bio-degradeable ties. Algiture soil improver and 150g Enmag (or, equivalent) to be incorporated into the soil of all new tree pits. Trees to be planted centrally within a tree pit.

Container grown shrubs, transplants and whips: Shrubs and transplants shall be planted in pits 300x300x400mm depth), and the backfill shall include 3 litres of peat-free tree and shrub compost. Where two or more shrub species are indicated within a single bed each species shall be randomly mixed throughout the bed in groups of 3/5.

Herbicide: Spot treat with herbicide throughout the maintenance period in accordance with the manufacturer's instructions.

Mulch: Planting beds to receive 75mm depth pulverized ornamental bark mulch. Native woodland/edge plants to be planted with 800g flax fibre mulch mat pinned to soil. Native hedgerow to be planted through 800g flax fibre mulch roll, edges tucked. Ensure the top of the mulch layer is a minimum of 15mm below adjacent pavements and other surfaces, to prevent spillage.

Plant position: Final position of trees and shrubs subject to confirmation of service location and approval of statutory undertakers.

Protection to planting: Native trees and shrubs within mixes to be protected by shelter guards as supplied by Acorn Planting Products Ltd (01508 528763), or equivalent.

Ornamental hedging: Hedges to comprise a single row of plants. 400mm wide trench excavated to take plants and topsoil cultivated to 400mm depth prior to application of fertiliser.

Grass: All turf/seeded areas to be cultivated and levelled as required removing any stones, rubble, subsoil, general construction waste.

Planting Season: Bare-root shrubs to be planted between mid-November and mid-March dependant upon the planting season.

LEGEND

- Proposed tree Standard (Heavy)
- Proposed tree Standard (Selected)
- Proposed shrub bed
- Proposed specimen shrub
- Proposed hedge
- Proposed grass
- Proposed Low Maintenance Grass Mix (Germinal Seeds UK A22)
- Proposed Native Mix 1
- Proposed Native Mix 2

Plant Codes (full schedules on 2573/1)

Code	Plant Name
Ac	Acer campestre
AcLRS	Acer campestre 'Louise Red Shine'
AcS	Acer campestre 'Streetwise'
ApEQ	Acer platanoides 'Emerald Queen'
Aco	Alnus cordata
AsRH	Amelanchier arborea 'Robin Hill'
BIAN	Berberis thunbergii 'Atropurpurea Nana'
BIA	Berberis thunbergii 'Atropurpurea'
Bp	Betula pendula
CBM	Ceanothus 'Blue Mound'
CxsCG	Chaenomeles x superba 'Crimson and Gold'
Ct	Choisya ternata
CaS	Cornus alba 'Sibirica'
CsF	Cornus stolonifera 'Flaviramea'
Cav	Corylus avellana
Cm	Crataegus monogyna
CxpAl	Cytisus x praecox 'Allgold'
EfEG	Euonymus fortunei 'Emerald 'n' Gold'
EfSQ	Euonymus fortunei 'Silver Queen'
Fj	Fatsia japonica
HMW	Hebe 'Mrs Winder'
HRE	Hebe 'Red Edge'
HHid	Hypericum 'Hidcote'
LaH	Lavandula angustifolia 'Hidcote'
LaM	Lavandula angustifolia 'Munstead'
LnBG	Lonicera nitida 'Baggesen's Gold'
Mt	Malus tschonoskii
PxRR	Photinia x fraseri 'Red Robin'
PaP	Prunus avium 'Plena'
Pl	Prunus laurocerasus
PlOL	Prunus laurocerasus 'Otto Luyken'
PsRa	Prunus sargentii 'Rancho'
Ps	Prunus spinosa
PSR	Pyracantha 'Saphyr Red'
PSY	Pyracantha 'Saphyr Yellow'
PcRS	Pyrus calleryana 'Red Spire'
RIy	Rhus typhina
Sc	Salix caprea
SoP	Salvia officinalis 'Purpurascens'
SoT	Salvia officinalis 'Tricolor'
Sacon	Sarcococca confusa
Shu	Sarcococca humilis
SjRu	Skimmia japonica 'Rubella'
SaCR	Sorbus aucuparia 'Cardinal Royal'
SaSS	Sorbus aucuparia 'Sheerwater Seedling'
SiB	Sorbus intermedia 'Brouwers'
Txe	Tilia x euchlora
Vd	Viburnum davidii
Vo	Viburnum opulus
WIV	Weigela florida 'Variegata'
YfGSw	Yucca flaccida 'Golden Sword'

Rev B: Revised to client comments - 31Jul15 (BP)

Rev A: Revised to STEN 'Proposed Planning Layout' 1512-02-G - 28Jul15 (BP)

Base: STEN 'Proposed Planning Layout' 1512-02-C

PROJECT	North Gawber Colliery, Barnsley		
TITLE	Detailed Landscape Proposals (3 of 4)		
CLIENT	Ben Bailey Homes		
DATE	10 Jul 15	SCALE 1 : 250	SHEET A0
DRAWN	MP/jr	DRAWING NO	2573/3
CHECKED	MP	REVISION	B

ROSETTA LANDSCAPE DESIGN
Chartered Landscape Architects
1 Isis Court Rosetta Way
York YO26 5NA
Telephone +44 (0)1904 794276
Facsimile +44 (0)1904 786962
Email design@rosettalandscape.co.uk
Web www.rosettalandscape.co.uk